


Memphis District

Invitation for Bid No. DACW66-03-B-0011



**US Army Corps
of Engineers®**

Project Title:

**AUSTIN, MISSISSIPPI
SEEPAGE RELIEF WELLS**

Location:

TUNICA COUNTY, MISSISSIPPI

Construction Solicitation and Specifications

THIS PROJECT IS LIMITED TO 8(A) ELIGIBLES IN THE FOLLOWING
STATES: Missouri, Illinois, Kentucky, Tennessee, Mississippi and Arkansas

Date: MAY 2003

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>
00010	SOLICITATION, OFFER, AND AWARD (SF 1442), BIDDING SCHEDULE, PLANT AND EQUIPMENT SCHEDULE, NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION, AND WAGE RATES
00100	INSTRUCTIONS, CONDITIONS AND NOTICES TO BIDDERS
00600	REPRESENTATIONS AND CERTIFICATIONS AND OTHER STATEMENTS OF BIDDERS
00700	CONTRACT CLAUSES
00800	SPECIAL CONTRACT REQUIREMENTS

TECHNICAL SPECIFICATIONS

DIVISION 1 - GENERAL REQUIREMENTS

01025	MEASUREMENT AND PAYMENT
01130	ENVIRONMENTAL PROTECTION
01451	CONTRACTOR QUALITY CONTROL
01452	PROJECT SIGNS, BARRICADES, AND TRAFFIC CONTROL SIGNS

DIVISION 2 - SITE WORK

02114	CLEARING
02215	GEOTEXTILE (FILTER FABRIC)
02225	EARTHWORK
02542	STONE PROTECTION
02545	CRUSHED STONE AND ARMORLOC BLOCKS
02546	AGGREGATE SURFACING
02700	CULVERT INSTALLATION
02704	STEEL PIPE INSTALLATION
02708	RELIEF WELLS
02936	ESTABLISHMENT OF TURF

DIVISION 3 – CONCRETE

03307 CONCRETE FOR MINOR STRUCTURES

DIVISIONS 4 THRU 14 – NOT USED

DIVISION 15 – MECHANICAL

15175 DISCHARGE PIPE AND APPURTENANCES

DIVISIONS 16 - NOT USED

SOLICITATION, OFFER, AND AWARD (Construction, Alteration, or Repair)	1. SOLICITATION NO.	2. TYPE OF SOLICITATION	3. DATE ISSUED	PAGE OF PAGES
	DACW66-03-B-0011	<input checked="" type="checkbox"/> SEALED BID (IFB) <input type="checkbox"/> NEGOTIATED (RFP)	05/05/2003	1

IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.

4. CONTRACT NO.	5. REQUISITION/PURCHASE REQUEST NO.	6. PROJECT NO.
	W38XGR-3092-2413	DACW66-03-B-0011
7. ISSUED BY	CODE	8. ADDRESS OFFER TO
	W38XGR	
U S ARMY ENGINEER DISTRICT, MEMPHIS CONTRACTING DIVISION (CEMVM-CT) 167 NORTH MAIN STRET B202 MEMPHIS, TN 38103-1894		ADDRESS SAME AS BLOCK 7. HAND DELIVERED BIDS RECEIVED IN ROOM 681, CLIFFORD DAVIS FEDERAL BUILDING, 167 NORTH MAIN STREET, MEMPHIS, TN
9. FOR INFORMATION CALL:	A. NAME	B. TELEPHONE NO. (Include area code) (NO COLLECT CALLS)
	SEE BIDDING SCHEDULE	

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying no., date):

The work required is for Austin, Mississippi Seepage Relief Wells, Tunica County, Mississippi

Description of Work: The work consists of clearing and disposal of debris therefrom; excavate and move existing embankment; placement of geotextile; culvert installation; stone protection to include crushed stone, armorloc blocks, bedding material and riprap; steel pipe installation; placement of aggregate surfacing; installation of relief wells; construction of adjacent ditches; construction of pump pads, and concrete outlet structures; establishment of turf; and providing environmental protection. There are fourteen sheets in the set of drawings.

The estimated value of the proposed work is between \$1,000,000.00 and \$5,000,000.00.

This is a competitive 8(a).

General Decision No. MS020020 is located behind Section 00010.

11. The Contractor shall begin performance within <u>10</u> calendar days and complete it within <u>225</u> calendar days after receiving	
<input type="checkbox"/> award, <input checked="" type="checkbox"/> notice to proceed. This performance period is <input checked="" type="checkbox"/> mandatory, <input type="checkbox"/> negotiable. (See <u>Sec. 00800, Para. 1.1</u> .)	
12A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? (If "YES," indicate within how many calendar days after award in Item 12B.)	12B. CALENDAR DAYS
<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	10

13. ADDITIONAL SOLICITATION REQUIREMENTS:

A. Sealed offers in original and 0 copies to perform the work required are due at the place specified in Item 8 by 1430 (hour) local time 05 Jun 2003 (date). If this is a sealed bid solicitation, offers must be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

B. An offer guarantee ☒ is, ☐ is not required.

C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

D. Offers providing less than 60 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

14. NAME AND ADDRESS OF OFFEROR (Include ZIP Code) <div style="display: flex; justify-content: space-between; margin-top: 10px;"> CAGE #: DUNS #: </div>				15. TELEPHONE NO. (Include area code) 16. REMITTANCE ADDRESS (Include only if different than Item 14)			
CODE FACILITY CODE							
17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within ____ calendar days after the date offers are due. (Insert any number equal to or greater than the minimum requirement stated in Item 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.) <div style="display: flex;"> <div style="width: 15%; text-align: right; padding-right: 10px;"> AMOUNTS </div> <div style="width: 85%; border-left: 1px solid black; height: 80px;"></div> </div>							
18. The offeror agrees to furnish any required performance and payment bonds.							
19. ACKNOWLEDGMENT OF AMENDMENTS (The offeror acknowledges receipt of amendments to the solicitation - give number and date of each)							
AMENDMENT NO.							
DATE							
20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER (Type or print)					20B. SIGNATURE		20C. OFFER DATE
AWARD (To be completed by Government)							
21. ITEMS ACCEPTED:							
22. AMOUNT				23. ACCOUNTING AND APPROPRIATION DATA			
24. SUBMIT INVOICES TO ADDRESS SHOWN IN (4 copies unless otherwise specified)			ITEM	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO <div style="display: flex; justify-content: space-between;"> <input type="checkbox"/> 10 U.S.C. 2304(c) () <input type="checkbox"/> 41 U.S.C. 253(c) () </div>			
26. ADMINISTERED BY CODE			27. PAYMENT WILL BE MADE BY				
CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE							
<input type="checkbox"/> 28. NEGOTIATED AGREEMENT (contractor is required to sign this document and return ____ copies to issuing office.) Contractor agrees to furnish and deliver all items or perform all work, requisitions identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.				<input type="checkbox"/> 29. AWARD (Contractor is not required to sign this document.) Your offer on this solicitation, is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.			
30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN (Type or print)				31A. NAME OF CONTRACTING OFFICER (Type or print)			
30B. SIGNATURE			30C. DATE	31B. UNITED STATES OF AMERICA BY		31C. AWARD DATE	

AUSTIN, MISSISSIPPI
SEEPAGE RELIEF WELLS
MISSISSIPPI RIVER AND TRIBUTARIES - CONSTRUCTION

SECTION 00010
SUPPLIES OR SERVICES AND PRICES/COSTS

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>ESTIMATED QUANTITY</u>	<u>U/M</u>	<u>U/P</u>	<u>AMOUNT</u>
0001	Mobilization and Demobilization	1	LS	XXX.XX	____.____
0002	Clearing	1	LS	XXX.XX	____.____
0003	Excavation	15,713	CY	____.____	____.____
0004	Relief Wells 10"	3,855	LF	____.____	____.____
0005	Pumping Test				
0005AA	First 112 Hours	112	HR	____.____	____.____
0005AB	All over 112 Hours	50	HR	____.____	____.____
0006	Pilot Hole Boring	4695	LF	____.____	____.____
0007	Guard Posts	230	EA	____.____	____.____
0008	16" Steel Pipe	1110	LF	____.____	____.____
0009	Concrete Outlet Structures	2	EA	____.____	____.____
0010	Crushed Stone, Armorloc Blocks, and Geotextiles	1	LS	XXX.XX	____.____
0011	Riprap "R-90"	23	TN	____.____	____.____
0012	Aggregate Surfacing	1	LS	XXX.XX	____.____
0013	Corrugated Metal Pipe, 24-Inch	60	LF	____.____	____.____
0014	Establishment of Turf	1	LS	XXX.XX	____.____
0015	Environmental Protection	1	LS	XXX.XX	____.____

Total Items 0001 thru 0015 \$ ____.

NOTE: Item No. 0005 has been divided into sub-items.
A bid for the work shall include a bid for each of these
sub-items. Bidders should refer to Section 01025 before
preparing their bids for these items.

SECTION 00010
SUPPLIES OR SERVICES AND PRICES/COSTS

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>ESTIMATED QUANTITY</u>	<u>U/M</u>	<u>U/P</u>	<u>AMOUNT</u>
-------------	--------------------	-------------------------------	------------	------------	---------------

NOTE: Bidders shall furnish unit prices for all items listed on the schedule of bid items which require unit prices. If the bidder fails to insert a unit price in the appropriate blank for required items, but does furnish an extended total or an estimated amount for such items, the Government will deem his unit price to be the quotient obtained by dividing the extended estimated amount for that line item by the quantity. IF THE BIDDER OMITTS BOTH THE UNIT PRICE AND THE EXTENDED ESTIMATED AMOUNT FOR ANY ITEM, HIS BID WILL BE DECLARED NON-RESPONSIVE.

Award will be made as a whole to one bidder.

All quantities are estimated except where unit is given as "LS" or "EA".

If a bid or modification to a bid based on unit prices is submitted and provides for a lump sum adjustment to the total estimated cost, the application of the lump sum adjustment to each unit price, including lump sum units, in bid schedule must be stated, or, if it is not stated, the bidder agrees that the lump sum adjustment shall be applied on a pro rata basis to every unit price in the bid schedule.

Bidders are cautioned to read Contract Clause entitled "Required Central Contractor Registration" (252.204-7004) located in SECTION 00700.

HR = HOUR

INVITATION: DACW66-03-B-0011

PLANT AND EQUIPMENT SCHEDULE

[TO BE ATTACHED TO BID FORM]

AVAILABLE PLANT TO BE USED

* _____

No.	TYPE	CAPACITY	MANUFACTURER	AGE & CONDTION	LOCATION
			* _____		
			* _____		

*PROVIDE SEPARATE TABLE FOR EACH TYPE OF EQUIPMENT SUCH AS CONCRETE PLANT, MATERIAL HANDLING, HAULING, ETC. USE ADDITIONAL PAGE IF NECESSARY.

ENG FORM 1619-R

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY FOR CONSTRUCTION. (FEB 1999)

a. The offeror's attention is called to the Equal Opportunity Clause and the Affirmative Action Compliance Requirements for Construction clause of this solicitation.

b. The goals for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

Goals for minority participation for each trade		:	Goals for female participation for each trade
SMSA Counties	32.3	:	
Non-SMSA Counties	26.5	:	6.9

These goals are applicable to all the Contractor's construction work performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, the Contractor shall apply the goals established for the geographical area where the work is actually performed. Goals are published periodically in the Federal Register in notice form, and these notices may be obtained from any Office of Federal Contract Compliance Programs office.

c. The Contractor's compliance with Executive Order 11246, as amended, and the regulations in 41 CFR 60-4 shall be based on (1) its implementation of the Equal Opportunity clause, (2) specific affirmative action obligations required by the clause entitled "Affirmative Action Compliance Requirements for Construction," and (3) its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade. The Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor, or from project to project, for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, Executive Order 11246, as amended, and the regulations in 41 CFR 60-4. Compliance with the goals will be measured against the total work hours performed.

d. The Contractor shall provide written notification to the Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, within 10 working days following award of any construction subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the -

(1) Name, address and telephone number of the subcontractor;

(i) Employer identification number of the subcontractor:

(2) Estimated dollar amount of the subcontract;

(3) Estimated starting and completion dates of the subcontract; and

(4) Geographical area in which the subcontract is to be performed.

e. As used in this Notice, and in the contract resulting from this Solicitation, the “covered area” is Economic Area 055, Memphis, TN, as follows:

SMSA Counties:

4920 Memphis, TN-AR-MS-----32.3
AR Crittenden; MS DeSoto, TN Shelby, TN Tipton

Non-SMSA Counties.....26.5

AR Clay; AR Craighead; AR Cross, AR Greene; AR Lawrence; AR Lee,
AR Mississippi; AR Phillips, AR Poinsett; AR Randolph; AR St. Francis;
MS Alcorn; MS Benton; MS Bolivar; MS Clahoun; MS Carroll;
MS Chickasaw; MS Clay; MS Coahoma; MS Grenada; MS Itawamba;
MS Lafayette; MS Lee; MS Leflore; MS Marshall; MS Monroe;
MS Montgomery; MS Panola; MS Pontotoc; MS Prentiss; MS Quitman;
MS Sunflower; MS Tallahatchie; MS Tate; MS Tippah; MS Tishomingo;
MS Union; MS Washington; MS Webster; MS Yalobusha; MO Dunklin;
MO New Madrid; MO Pemiscot, TN Benton; TN Carroll, TN Chester;
TN Crockett; TN Decator; TN Dyer; TN Fayette, TN Gibson; TN Hardeman
TN Hardin; TN Haywood; TN Henderson; TN Henry; TN Lake;
TN Lauderdale; TN McNairy; TN Madison; TN Obion;
TN Weakley.

(FAR 52.222-23)

General Decision Number MS020020

General Decision Number MS020020 Superseded General Decision No. MS010020

State: Mississippi

Construction Type:

HEAVY

County(ies):

ADAMS	ISSAQUENA	PERRY
ALCORN	ITAWAMBA	PIKE
AMITE	JASPER	PONTOTOC
ATTALA	JEFFERSON	PRENTISS
BENTON	JEFFERSON DAVIS	QUITMAN
BOLIVAR	JONES	RANKIN
CALHOUN	KEMPER	SCOTT
CARROLL	LAFAYETTE	SHARKEY
CHICKASAW	LAMAR	SIMPSON
CHOCTAW	LAUDERDALE	SMITH
CLAIBORNE	LAWRENCE	STONE
CLARKE	LEAKE	SUNFLOWER
CLAY	LEE	TALLAHATCHIE
COAHOMA	LEFLORE	TATE
COPIAH	LINCOLN	TIPPAH
COVINGTON	LOWNDES	TISHOMINGO
DE SOTO	MADISON	TUNICA
FORREST	MARION	UNION
FRANKLIN	MARSHALL	WALTHALL
GEORGE	MONROE	WARREN
GREENE	MONTGOMERY	WASHINGTON
GRENADA	NESHOBA	WAYNE
HANCOCK	NEWTON	WEBSTER
HARRISON	NOXUBEE	WILKINSON
HINDS	OKTIBBEHA	WINSTON
HOLMES	PANOLA	YALOBUSHA
HUMPHREYS	PEARL RIVER	YAZOO

HEAVY CONSTRUCTION PROJECTS (including Water & Sewer Lines) excluding all work in conjunction with the Tennessee Tombigbee Waterway Project.

Modification Number Publication Date

0 03/01/2002

COUNTY(ies):

ADAMS	ISSAQUENA	PERRY
ALCORN	ITAWAMBA	PIKE
AMITE	JASPER	PONTOTOC
ATTALA	JEFFERSON	PRENTISS
BENTON	JEFFERSON DAVIS	QUITMAN
BOLIVAR	JONES	RANKIN
CALHOUN	KEMPER	SCOTT
CARROLL	LAFAYETTE	SHARKEY
CHICKASAW	LAMAR	SIMPSON
CHOCTAW	LAUDERDALE	SMITH
CLAIBORNE	LAWRENCE	STONE
CLARKE	LEAKE	SUNFLOWER
CLAY	LEE	TALLAHATCHIE

COAHOMA	LEFLORE	TATE
COPIAH	LINCOLN	TIPPAH
COVINGTON	LOWNDES	TISHOMINGO
DE SOTO	MADISON	TUNICA
FORREST	MARION	UNION
FRANKLIN	MARSHALL	WALTHALL
GEORGE	MONROE	WARREN
GREENE	MONTGOMERY	WASHINGTON
GRENADA	NESHOBA	WAYNE
HANCOCK	NEWTON	WEBSTER
HARRISON	NOXUBEE	WILKINSON
HINDS	OKTIBBEHA	WINSTON
HOLMES	PANOLA	YALOBUSHA
HUMPHREYS	PEARL RIVER	YAZOO

SUMS2001A

CONSTRUCTION DESCRIPTION: Heavy Construction (including Water & Sewer Lines) excluding all work in conjunction with the Tennessee Tombigee Waterway Project and Heavy Construction in Jackson County.

SUMS2001A 11/01/1980

	Rates	Fringes
BRICKLAYERS	8.00	
CARPENTERS	6.23	
CEMENT MASONS	5.15	
ELECTRICIANS	9.84	
IRONWORKERS	8.15	
LABORERS:		
Unskilled	5.15	
Pipelayers	5.15	
Drillers	5.15	
PAINTERS	7.00	
PLUMBERS	7.81	
POWER EQUIPMENT OPERATORS:		
Backhoe	5.56	
Bulldozer	5.38	
Crane	6.61	
Dragline	5.94	
Front End Loader	5.40	
Mechanic	8.15	
Motor Grader	5.25	
Scraper	5.15	
Oiler	5.51	

WELDERS - receive rate prescribed for craft performing operation to which welding is incidental.

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

=====

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29 CFR 5.5(a)(1)(v)).

In the listing above, the "SU" designation means that rates listed under that identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations
Wage and Hour Division
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U. S. Department of Labor
200 Constitution Avenue, N. W.
Washington, D. C. 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

SECTION 00100
INSTRUCTIONS TO BIDDERS
TABLE OF CONTENTS

52.0-4019	PREAWARD INFORMATION.....	3
52.0-4047	SITE OF THE WORK.....	3
52.0-4048	QUANTITY ESTIMATES	4
52.0-4049	CONDITIONS AFFECTING THE WORK.....	4
52.0-4055	NEGOTIATIONS AFTER SEALED BIDDING.....	4
52.0-4058	PROGRAM DATA	5
52.0-4060	REVISION AND AMENDMENT TO SOLICITATION FOR BIDS... 5	
	(FAR 52.236-27) SITE VISIT (CONSTRUCTION) (ALTERNATE I) (FEB 1995). 6	
52.204-6	DATA UNIVERSAL NUMBERING SYSTEM (DUNS) NUMBER (JUN 99).....	6
52.211-2	AVAILABILITY OF SPECIFICATIONS LISTED IN THE DOD INDEX OF SPECIFICATIONS AND STANDARDS (DODISS) AND DESCRIPTIONS LISTED IN THE ACQUISITION MANAGEMENT SYSTEMS AND DATA REQUIREMENTS CONTROL LIST, DOD 5010.12-L (DEC 1999)	7
52.214-3	AMENDMENTS TO INVITATIONS FOR BIDS (DEC 1989)	8
52.214-4	FALSE STATEMENTS IN BIDS (APR 1984)	8
52.214-5	SUBMISSION OF BIDS (MAR 1997).....	8
52.214-6	EXPLANATION TO PROSPECTIVE BIDDERS (APR 1984).....	9
52.214-7	LATE SUBMISSIONS, MODIFICATIONS, AND WITHDRAWALS OF BIDS (NOV 1999).....	9
52.214-18	PREPARATION OF BIDS—CONSTRUCTION (APR 1984).....	10
52.214-19	CONTRACT AWARD—SEALED BIDDING—CONSTRUCTION (AUG 1996)	11

52.214-34	SUBMISSION OF OFFERS IN THE ENGLISH LANGUAGE (APR 1991)	11
52.214-35	SUBMISSION OF OFFERS IN U.S. CURRENCY (APR 1991).....	12
52.214-5000	APPARENT CLERICAL MISTAKES (MAR 1995)—EFARS.....	12
52.216-1	TYPE OF CONTRACT (APR 1984).....	12
52.225-10	NOTICE OF BUY AMERICAN ACT REQUIREMENT— CONSTRUCTION MATERIALS (MAY 2002).....	13
52.225-12	NOTICE OF BUY AMERICAN ACT REQUIREMENT— CONSTRUCTION MATERIALS UNDER TRADE AGREEMENTS (MAY 2002).	14
52.228-1	BID GUARANTEE (SEP 1996)	15
52.232-15	PROGRESS PAYMENTS NOT INCLUDED (APR 1984)	16
52.232-38	SUBMISSION OF ELECTRONIC FUNDS TRANSFER INFORMATION WITH OFFER (MAY 1999).....	16
52.233-2	SERVICE OF PROTEST (AUG 1996).....	17
52.252-1	SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998).....	17
252.236-7008	CONTRACT PRICES – BIDDING SCHEDULES. (DEC 1991)	18

SECTION 00100
INSTRUCTIONS TO BIDDERS

52.0-4019 *PREAWARD INFORMATION*

Each bidder shall, upon request of the Contracting Officer, furnish a statement of whether he is now or ever has been engaged in any work similar to that covered by the specifications herein, the dollar value thereof, the year in which such work was performed, and the manner of its execution and giving such other information as will tend to show the bidder's ability to prosecute the required work. The "such other information" referred to above shall include but is not limited to the following:

- (a) The name and address of the office or firm under which such similar work was performed.
- (b) A list of key personnel available for the instant project and their qualifications.
- (c) A copy of bidder's latest financial statement, including the names of banks or other financial institutions with which the bidder conducts business. If the financial statement is more than 60 days old, a certificate should be attached stating that financial condition is substantially the same, or if not the same, the changes that have taken place. Such statement will be treated as confidential.
- (d) A list of present commitments, including the dollar value thereof, and name of office under which work is being performed.

52.0-4047 *SITE OF THE WORK*

Bidders are advised that for the purpose of applicability of the Davis-Bacon Act and other contract labor standards provisions, "the site of the work" under the contract to be awarded pursuant to the solicitation may not be limited to the physical place(s) where the construction called for in the contract will remain when work on it has been completed. The "site of the work" may include other adjacent or nearby property used by the contractor or subcontractors during such construction. For example, fabrication plants, mobile factories, batch plants, borrow pits, job headquarters, tool yards, etc., will be considered part of the site of the work, provided they are dedicated exclusively or nearly so to performance on the contract and are located in proximity to the actual construction location that it would be reasonable to include them.

52.0-4048 *QUANTITY ESTIMATES*

Estimates of quantities involved in certain items of work for which bids are being solicited on a lump sum or job basis have been made for the use of the Government. Copies of these quantity estimates may be obtained from the U S Army Engineer District Memphis, 167 North Main Street, Room 762, Memphis, Tennessee 38103-1894, telephone 901/544-3236, or visit our website at <http://www.mvm.usace.army.mil/>

It is to be expressly understood that the accuracy of these estimates is in no way warranted and that the furnishing of this information to a bidder will not relieve him of his responsibility to estimate the quantities involved. It is further to be expressly understood that in no case will such estimate be used as a basis of claim against the Government.

52.0-4049 *CONDITIONS AFFECTING THE WORK*

Bidders should visit the site and take such other steps as may be reasonably necessary to ascertain the nature and location of the work, and the general and local conditions which can affect the work or the cost thereof. Failure to do so will not relieve bidders from responsibility for estimating properly the difficulty or cost of successfully performing the work. The Government will assume no responsibility for any understanding or representations concerning conditions made by any of its officers or agents prior to the execution of the contract, unless included in the Solicitation, the specifications, or related documents.

52.0-4055 *NEGOTIATIONS AFTER SEALED BIDDING*

(a) This clause applies if after bid opening the Contracting Officer determines that all otherwise acceptable bids received are at unreasonable prices, or only one bid is received and the Contracting Officer cannot determine the reasonableness of the bid price, or no responsive bid has been received from a responsible bidder; or the bids were not independently arrived at in open competition, were collusive, or were submitted in bad faith.

(b) The Government has the option to reject all bids received in response to the sealed bid advertisement and initiate negotiation. Negotiations will include soliciting offers from each responsible bidder that submits a bid in response to the solicitation.

(c) If after bid opening the Contracting Officer determines under (a) above that negotiations are in the best interest of the Government, the following steps will be followed:

(1) An amendment to the sealed bid advertisement will be issued to each responsible bidder changing the solicitation number to a request for proposal number. The amendment will also make any necessary changes to the scope of work.

(2) A cover letter signed by the negotiator will accompany the amendment explaining the procedures to be followed during negotiations.

(3) In the event there is only one responsible bidder under the initial sealed bid solicitation, cost or pricing data requirements set forth in FAR 15.804 will apply as will clause FAR 52.215-2, "Audit and Records - Negotiation".

52.0-4058 *PROGRAM DATA*

AUTHORITY: The work provided for herein is authorized by the Flood Control Act approved 15 JUN 1936, as amended.

52.0-4060 *REVISION AND AMENDMENT TO SOLICITATION FOR BIDS*

The right is reserved, as the interest of the Government may require, to revise or amend the specifications or drawings or both prior to the date set for opening bids. Such revisions and amendments, if any, will be announced by an amendment or amendments to this Solicitation for Bids. If revisions and amendments are of a nature which requires material changes in quantities or prices bid or both, the date set for opening bids may be postponed by such number of days as in the opinion of the issuing officer will enable bidders to revise their bids. In such cases, the amendment will include an announcement of new date for opening bids.

(FAR 52.236-27) SITE VISIT (CONSTRUCTION)
(ALTERNATE I) (FEB 1995)

(a) The clauses at 52.236-2, Differing Site Conditions, and 52.236-3, Site Investigations and Conditions Affecting the Work, will be included in any contract awarded as a result of this solicitation. Accordingly, bidders are urged and expected to inspect the site where the work will be performed.

(b) Two organized site visits have been scheduled for **22 May 2003 and 29 May 2003**.

(c) Bidders desiring a site visit shall contact the Area Engineer at least one day prior to the scheduled site visit.

NAME: Donald R. Tutor
Area Engineer

ADDRESS: Wynne Area Office
1932 N. Falls Boulevard
P. O. Box 729
Wynne, Arkansas 72396-0729

TELEPHONE: 901/544-3851 or 870/238-7983

COLLECT TELEPHONE CALLS WILL NOT BE ACCEPTED.

(End of Provision)

52.204-6 DATA UNIVERSAL NUMBERING SYSTEM (DUNS)
NUMBER (JUN 99)

(a) The offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation "DUNS" followed by the DUNS number that identifies the offeror's name and address exactly as stated in the offer.

(b) If the offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one. A DUNS number will be provided immediately by telephone at no

charge to the offeror. For information on obtaining a DUNS number, the offeror, if located within the United States, should call Dun and Bradstreet at 1-800-333-0505. The offeror should be prepared to provide the following information:

- (1) Company name.
- (2) Company address.
- (3) Company telephone number.
- (4) Line of business.
- (5) Chief executive officer/key manager.
- (6) Date the company was started.
- (7) Number of people employed by the company.
- (8) Company affiliation.

(c) Offerors located outside the United States may obtain the location and phone number of the local Dun and Bradstreet Information Services office from the Internet Home Page at <http://www.customerservice@dnb.com>. If an offeror is unable to locate a local service center, it may send an e-mail to Dun and Bradstreet at globalinfo@mail.dnb.com.

(End of provision)

**52.211-2 AVAILABILITY OF SPECIFICATIONS LISTED IN THE
DOD INDEX OF SPECIFICATIONS AND STANDARDS (DODISS)
AND DESCRIPTIONS LISTED IN THE ACQUISITION
MANAGEMENT SYSTEMS AND DATA REQUIREMENTS
CONTROL LIST, DOD 5010.12-L (DEC 1999)**

Copies of specifications, standards, and data item descriptions cited in this solicitation may be obtained--

- (a) From the ASSIST database via the Internet at <http://assist.daps.mil>; or
- (b) By submitting a request to the--Department of Defense Single Stock Point (DoDSSP), Building 4, Section D, 700 Robbins Avenue, Philadelphia, PA 19111-5094, Telephone (215) 697-2667/2179, Facsimile (215) 697-1462.

(End of provision)

52.214-3 *AMENDMENTS TO INVITATIONS FOR BIDS (DEC 1989)*

(a) If this solicitation is amended, then all terms and conditions which are not modified remain unchanged.

(b) Bidders shall acknowledge receipt of any amendment to this solicitation (1) by signing and returning the amendment, (2) by identifying the amendment number and date in the space provided for this purpose on the form for submitting a bid, (3) by letter or telegram, or (4) by facsimile, if facsimile bids are authorized in the solicitation. The Government must receive the acknowledgment by the time and at the place specified for receipt of bids.

(End of provision)

52.214-4 *FALSE STATEMENTS IN BIDS (APR 1984)*

Bidders must provide full, accurate, and complete information as required by this solicitation and its attachments. The penalty for making false statements in bids is prescribed in 18 U.S.C. 1001.

(End of provision)

52.214-5 *SUBMISSION OF BIDS (MAR 1997)*

(a) Bids and bid modifications shall be submitted in sealed envelopes or packages (unless submitted by electronic means) (1) addressed to the office specified in the solicitation, and (2) showing the time and date specified for receipt, the solicitation number, and the name and address of the bidder.

(b) Bidders using commercial carrier services shall ensure that the bid is addressed and marked on the outermost envelope or wrapper as prescribed in subparagraphs (a)(1) and (2) of this provision when delivered to the office specified in the solicitation.

(c) Telegraphic bids will not be considered unless authorized by the solicitation; however, bids may be modified or withdrawn by written or telegraphic notice.

(d) Facsimile bids, modifications, or withdrawals, will not be considered unless authorized by the solicitation.

(e) Bids submitted by electronic commerce shall be considered only if the electronic commerce method was specifically stipulated or permitted by the solicitation.

(End of provision)

52.214-6 EXPLANATION TO PROSPECTIVE BIDDERS (APR 1984)

Any prospective bidder desiring an explanation or interpretation of the solicitation, drawings, specifications, etc., must request it in writing soon enough to allow a reply to reach all prospective bidders before the submission of their bids. Oral explanations or instructions given before the award of a contract will not be binding. Any information given a prospective bidder concerning a solicitation will be furnished promptly to all other prospective bidders as an amendment to the solicitation, if that information is necessary in submitting bids or if the lack of it would be prejudicial to other prospective bidders.

(End of provision)

52.214-7 LATE SUBMISSIONS, MODIFICATIONS, AND WITHDRAWALS OF BIDS (NOV 1999)

(a) Bidders are responsible for submitting bids, and any modifications or withdrawals, so as to reach the Government office designated in the invitation for bids (IFB) by the time specified in the IFB. If no time is specified in the IFB, the time for receipt is 4:30 p.m., local time, for the designated Government office on the date that bids are due.

(b)(1) Any bid, modification, or withdrawal received at the Government office designated in the IFB after the exact time specified for receipt of bids is "late" and will not be considered unless it is received before award is made, the Contracting Officer determines that accepting the late bid would not unduly delay the acquisition; and--

(i) If it was transmitted through an electronic commerce method authorized by the IFB, it was received at the initial point of entry to the Government infrastructure not later than 5:00 p.m. one working day prior to the date specified for receipt of bids; or

(ii) There is acceptable evidence to establish that it was received at the Government installation designated for receipt of bids and was under the Government's control prior to the time set for receipt of bids.

(2) However, a late modification of an otherwise successful bid that makes its terms more favorable to the Government, will be considered at any time it is received and may be accepted.

(c) Acceptable evidence to establish the time of receipt at the Government installation includes the time/date stamp of that installation on the bid wrapper, other documentary evidence of receipt maintained by the installation, or oral testimony or statements of Government personnel.

(d) If an emergency or unanticipated event interrupts normal Government processes so that bids cannot be received at the Government office designated for receipt of bids by the exact time specified in the IFB and urgent Government requirements preclude amendment of the IFB, the time specified for receipt of bids will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal Government processes resume.

(e) Bids may be withdrawn by written notice received at any time before the exact time set for receipt of bids. If the IFB authorizes facsimile bids, bids may be withdrawn via facsimile received at any time before the exact time set for receipt of bids, subject to the conditions specified in the provision at 52.214-31, Facsimile Bids. A bid may be withdrawn in person by a bidder or its authorized representative if, before the exact time set for receipt of bids, the identity of the person requesting withdrawal is established and the person signs a receipt for the bid.

(End of provision)

52.214-18 *PREPARATION OF BIDS--CONSTRUCTION (APR 1984)*

(a) Bids must be (1) submitted on the forms furnished by the Government or on copies of those forms, and (2) manually signed. The person signing a bid must initial each erasure or change appearing on any bid form.

(b) The bid form may require bidders to submit bid prices for one or more items on various bases, including--

(1) Lump sum bidding;

(2) Alternate prices;

(3) Units of construction; or

(4) Any combination of subparagraphs (1) through (3) above.

(c) If the solicitation requires bidding on all items, failure to do so will disqualify the bid. If bidding on all items is not required, bidders should insert the words "no bid" in the space provided for any item on which no price is submitted.

(d) Alternate bids will not be considered unless this solicitation authorizes their submission.

(End of provision)

**52.214-19 CONTRACT AWARD--SEALED BIDDING--
CONSTRUCTION (AUG 1996)**

(a) The Government will evaluate bids in response to this solicitation without discussions and will award a contract to the responsible bidder whose bid, conforming to the solicitation, will be most advantageous to the Government, considering only price and the price-related factors specified elsewhere in the solicitation.

(b) The Government may reject any or all bids, and waive informalities or minor irregularities in bids received.

(c) The Government may accept any item or combination of items, unless doing so is precluded by a restrictive limitation in the solicitation or the bid.

(d) The Government may reject a bid as nonresponsive if the prices bid are materially unbalanced between line items or subline items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid will result in the lowest overall cost to the Government even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.

(End of provision)

**52.214-34 SUBMISSION OF OFFERS IN THE ENGLISH
LANGUAGE (APR 1991)**

Offers submitted in response to this solicitation shall be in the English language. Offers received in other than English shall be rejected.

(End of provision)

52.214-35 SUBMISSION OF OFFERS IN U.S. CURRENCY (APR 1991)

Offers submitted in response to this solicitation shall be in terms of U.S. dollars. Offers received in other than U.S. dollars shall be rejected.

(End of provision)

**52.214-5000 APPARENT CLERICAL MISTAKES (MAR 1995)—
EFARS**

(a) For the purpose of initial evaluations of bids, the following will be utilized in the resolving arithmetic discrepancies found on the face of bidding schedule as submitted by the bidder:

- (1) Obviously misplaced decimal points will be corrected;
- (2) Discrepancy between unit price and extended price, the unit price will govern;
- (3) Apparent errors in extension of unit prices will be corrected;
- (4) Apparent errors in addition of lump-sum and extended prices will be corrected.

(b) For the purpose of bid evaluation, the government will proceed on the assumption that the bidder intends his bid to be evaluated on basis of the unit prices, the totals arrived at by resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.

(c) These correction procedures shall not be used to resolve any ambiguity concerning which bid is low.

(End of statement)

52.216-1 TYPE OF CONTRACT (APR 1984)

The Government contemplates award of a firm, fixed-price construction contract resulting from this solicitation.

(End of clause)

52.225-10 NOTICE OF BUY AMERICAN ACT REQUIREMENT-- CONSTRUCTION MATERIALS (MAY 2002)

(a) Definitions. Construction material, domestic construction material, and foreign construction material, as used in this provision, are defined in the clause of this solicitation entitled "Buy American Act --Construction Materials" (Federal Acquisition Regulation (FAR) clause 52.225-9).

(b) Requests for determinations of inapplicability. An offeror requesting a determination regarding the inapplicability of the Buy American Act should submit the request to the Contracting Officer in time to allow a determination before submission of offers. The offeror shall include the information and applicable supporting data required by paragraphs (c) and (d) of the clause at FAR 52.225-9 in the request. If an offeror has not requested a determination regarding the inapplicability of the Buy American Act before submitting its offer, or has not received a response to a previous request, the offeror shall include the information and supporting data in the offer.

(c) Evaluation of offers. (1) The Government will evaluate an offer requesting exception to the requirements of the Buy American Act, based on claimed unreasonable cost of domestic construction material, by adding to the offered price the appropriate percentage of the cost of such foreign construction material, as specified in paragraph (b)(3)(i) of the clause at FAR 52.225-9.

(2) If evaluation results in a tie between an offeror that requested the substitution of foreign construction material based on unreasonable cost and an offeror that did not request an exception, the Contracting Officer will award to the offeror that did not request an exception based on unreasonable cost.

(d) Alternate offers.

(1) When an offer includes foreign construction material not listed by the Government in this solicitation in paragraph (b)(2) of the clause at FAR 52.225-9, the offeror also may submit an alternate offer based on use of equivalent domestic construction material.

(2) If an alternate offer is submitted, the offeror shall submit a separate Standard Form 1442 for the alternate offer, and a separate price comparison table prepared in accordance with paragraphs (c) and (d) of the clause at FAR 52.225-9 for the offer that is based on the use of any foreign construction material for which the Government has not yet determined an exception applies.

(3) If the Government determines that a particular exception requested in accordance with paragraph (c) of the clause at FAR 52.225-9 does not apply, the Government will evaluate only those offers based on use of the equivalent domestic construction material, and the offeror shall be required to furnish such domestic construction material. An offer based on use of the foreign construction material for which an exception was requested--

- (i) Will be rejected as nonresponsive if this acquisition is conducted by sealed bidding; or
- (ii) May be accepted if revised during negotiations.

(End of provision)

**52.225-12 NOTICE OF BUY AMERICAN ACT REQUIREMENT--
CONSTRUCTION MATERIALS UNDER TRADE AGREEMENTS
(MAY 2002)**

(a) Definitions. Construction material, designated country construction material, domestic construction material, foreign construction material, and NAFTA country construction material, as used in this provision, are defined in the clause of this solicitation entitled "Buy American Act --Construction Materials under Trade Agreements" (Federal Acquisition Regulation (FAR) clause 52.225-11).

(b) Requests for determination of inapplicability. An offeror requesting a determination regarding the inapplicability of the Buy American Act should submit the request to the Contracting Officer in time to allow a determination before submission of offers. The offeror shall include the information and applicable supporting data required by paragraphs (c) and (d) of FAR clause 52.225-11 in the request. If an offeror has not requested a determination regarding the inapplicability of the Buy American Act before submitting its offer, or has not received a response to a previous request, the offeror shall include the information and supporting data in the offer.

(c) Evaluation of offers. (1) The Government will evaluate an offer requesting exception to the requirements of the Buy American Act, based on claimed unreasonable cost of domestic construction materials, by adding to the offered price the appropriate percentage of the cost of such foreign construction material, as specified in paragraph (b)(4)(i) of FAR clause 52.225-11.

(2) If evaluation results in a tie between an offeror that requested the substitution of foreign construction material based on unreasonable cost and an offeror that did not request an exception, the Contracting Officer will award to the offeror that did not request an exception based on unreasonable cost.

(d) Alternate offers. (1) When an offer includes foreign construction material, other than designated country or NAFTA country construction material, that is not listed by the Government in this solicitation in paragraph (b)(3) of FAR clause 52.225-11, the offeror also may submit an alternate offer based on use of equivalent domestic, designated country, or NAFTA country construction material.

(2) If an alternate offer is submitted, the offeror shall submit a separate Standard Form 1442 for the alternate offer, and a separate price comparison table prepared in accordance with paragraphs (c) and (d) of FAR clause 52.225-11 for the offer that is based on the use of any foreign construction material for which the Government has not yet determined an exception applies.

(3) If the Government determines that a particular exception requested in accordance with paragraph (c) of FAR clause 52.225-11 does not apply, the Government will evaluate only those offers based on use of the equivalent domestic, designated country, or NAFTA country construction material, and the offeror shall be required to furnish such domestic, designated country, or NAFTA country construction material. An offer based on use of the foreign construction material for which an exception was requested--

(i) Will be rejected as nonresponsive if this acquisition is conducted by sealed bidding; or

(ii) May be accepted if revised during negotiations.

(End of provision)

52.228-1 BID GUARANTEE (SEP 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.

(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds, (1) to unsuccessful bidders as soon as practicable after the opening of bids, and (2) to the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.-

(c) The amount of the bid guarantee shall be **(20%)** twenty percent of the bid price or **\$3,000,000.00**, whichever is less.-

(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.-

(e) In the event the contract is terminated for default, the bidder is liable for any cost of

acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.

(End of clause)

52.232-15 *PROGRESS PAYMENTS NOT INCLUDED (APR 1984)*

A progress payments clause is not included in this solicitation, and will not be added to the resulting contract at the time of award. Bids conditioned upon inclusion of a progress payment clause in the resulting contract will be rejected as nonresponsive.

(End of clause)

52.232-38 *SUBMISSION OF ELECTRONIC FUNDS TRANSFER INFORMATION WITH OFFER (MAY 1999)*

The offeror shall provide, with its offer, the following information that is required to make payment by electronic funds transfer (EFT) under any contract that results from this solicitation. This submission satisfies the requirement to provide EFT information under paragraphs (b)(1) and (j) of the clause at 52.232-34, Payment by Electronic Funds Transfer--Other than Central Contractor Registration.

- (1) The solicitation number (or other procurement identification number).
- (2) The offeror's name and remittance address, as stated in the offer.
- (3) The signature (manual or electronic, as appropriate), title, and telephone number of the offeror's official authorized to provide this information.
- (4) The name, address, and 9-digit Routing Transit Number of the offeror's financial agent.
- (5) The offeror's account number and the type of account (checking, savings, or lockbox).
- (6) If applicable, the Fedwire Transfer System telegraphic abbreviation of the offeror's financial agent.
- (7) If applicable, the offeror shall also provide the name, address, telegraphic abbreviation, and 9-digit Routing Transit Number of the correspondent financial institution receiving the wire transfer payment if the offeror's financial agent is not

directly on-line to the Fedwire and, therefore, not the receiver of the wire transfer payment.

(End of provision)

52.233-2 SERVICE OF PROTEST (AUG 1996)

(a) Protests, as defined in section 33.101 of the Federal Acquisition Regulation, that are filed directly with an agency, and copies of any protests that are filed with the General Accounting Office (GAO), shall be served on the Contracting Officer (addressed as follows) by obtaining written and dated acknowledgment of receipt from

Chief, Contracting Division
ATTN: CEMVM-CT-Room 681
U.S. Army Engineer District, Memphis
167 North Main Street B202
Memphis, Tennessee 38103-1894

(b) The copy of any protest shall be received in the office designated above within one day of filing a protest with the GAO.

(End of provision)

52.252-1 SOLICITATION PROVISIONS INCORPORATED BY REFERENCE (FEB 1998)

This solicitation incorporates one or more solicitation provisions by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. The offeror is cautioned that the listed provisions may include blocks that must be completed by the offeror and submitted with its quotation or offer. In lieu of submitting the full text of those provisions, the offeror may identify the provision by paragraph identifier and provide the appropriate information with its quotation or offer. Also, the full text of a solicitation provision may be accessed electronically at this/these address(es):

<http://www.arnet.gov/far>
<http://farsite.hill.af.mil>
<http://www.dtic.mil/dfars>

(End of provision)

252.236-7008 *CONTRACT PRICES - BIDDING SCHEDULES.*
(DEC 1991)

(a) The Government's payment for the items listed in the Bidding Schedule shall constitute full compensation to the Contractor for --

(1) Furnishing all plant, labor, equipment, appliances, and materials; and

(2) Performing all operations required to complete the work in conformity with the drawings and specifications.

(b) The Contractor shall include in the prices for the items listed in the Bidding Schedule all costs for work in the specifications, whether or not specifically listed in the Bidding Schedule.

SECTION 00600
REPRESENTATIONS & CERTIFICATIONS
TABLE OF CONTENTS

52.0-4031	CORPORATE CERTIFICATION	1
52.203-2	CERTIFICATE OF INDEPENDENT PRICE DETERMINATION (APR 1985)	2
52.203-11	CERTIFICATION AND DISCLOSURE REGARDING PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (APR 1991).....	3
52.204-3	TAXPAYER IDENTIFICATION (OCT 1998)	4
52.209-5	CERTIFICATION REGARDING DEBARMENT, SUSPENSION, PROPOSED DEBARMENT, AND OTHER RESPONSIBILITY MATTERS (DEC 2001)	5
52.219-1	SMALL BUSINESS PROGRAM REPRESENTATIONS (APR 2002)	7
52.219-2	EQUAL LOW BIDS. (OCT 1995).....	9
52.219-19	SMALL BUSINESS CONCERN REPRESENTATION FOR THE SMALL BUSINESS COMPETITIVENESS DEMONSTRATION PROGRAM (OCT 2000)	10
52.219-21	SMALL BUSINESS SIZE REPRESENTATION FOR TARGETED INDUSTRY CATEGORIES UNDER THE SMALL BUSINESS COMPETITIVENESS DEMONSTRATION PROGRAM (MAY 1999).....	11
52.222-22	PREVIOUS CONTRACTS AND COMPLIANCE REPORTS (FEB 1999)	12
52.223-13	CERTIFICATION OF TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)	12
252.204-7001	COMMERCIAL AND GOVERNMENT ENTITY (CAGE) CODE REPORTING (AUG 1999).....	13
252.247-7022	REPRESENTATION OF EXTENT OF TRANSPORTATION BY SEA (AUG 1992)	15

52.0-4031 CORPORATE CERTIFICATION

IF A BIDDER IS A CORPORATION OR IF CORPORATION IS PARTICIPATING IN A JOINT VENTURE, PLEASE COMPLETE THE FOLLOWING CERTIFICATION:

I, _____, certify that I am secretary of the corporation named as Contractor herein; that _____ who signed this contract on behalf of the Contractor; was then _____ of said corporation; that said contract was duly signed for and on behalf of said corporation by authority of its governing body and is within the scope of its corporate powers.

(CORPORATE SEAL)

(Secretary)

IF A CORPORATION IS PARTICIPATING AS A JOINT VENTURE, ITS SECRETARY MUST SUBMIT A CERTIFICATE STATING THE CORPORATION IS AUTHORIZED TO PARTICIPATE.

**52.203-2 CERTIFICATE OF INDEPENDENT PRICE
DETERMINATION (APR 1985)**

(a) The offeror certifies that --

(1) The prices in this offer have been arrived at independently, without, for the purpose of restricting competition, any consultation, communication, or agreement with any other offeror or competitor relating to --

(i) Those prices,

(ii) The intention to submit an offer, or

(iii) The methods of factors used to calculate the prices offered:

(2) The prices in this offer have not been and will not be knowingly disclosed by the offeror, directly or indirectly, to any other offeror or competitor before bid opening (in the case of a sealed bid solicitation) or contract award (in the case of a negotiated solicitation) unless otherwise required by law; and

(3) No attempt has been made or will be made by the offeror to induce any other concern to submit or not to submit an offer for the purpose of restricting competition.

(b) Each signature on the offer is considered to be a certification by the signatory that the signatory --

(1) Is the person in the offeror's organization responsible for determining the prices offered in this bid or proposal, and that the signatory has not participated and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision; or

(2) (i) Has been authorized, in writing, to act as agent for the following principals in certifying that those principals have not participated, and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision

_____ (insert full name of person(s) in the offeror's organization responsible for determining the prices offered in this bid or proposal, and the title of his or her position in the offeror's organization);

(ii) As an authorized agent, does certify that the principals named in subdivision (b)(2)(i) above have not participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) above; and

(iii) As an agent, has not personally participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision.

(c) If the offeror deletes or modifies subparagraph (a)(2) of this provision, the offeror must furnish with its offer a signed statement setting forth in detail the circumstances of the disclosure.

(End of clause)

**52.203-11 CERTIFICATION AND DISCLOSURE REGARDING
PAYMENTS TO INFLUENCE CERTAIN FEDERAL
TRANSACTIONS (APR 1991)**

(a) The definitions and prohibitions contained in the clause, at FAR 52.203-12, Limitation on Payments to Influence Certain Federal Transactions, included in this solicitation, are hereby incorporated by reference in paragraph (b) of this Certification.

(b) The offeror, by signing its offer, hereby certifies to the best of his or her knowledge and belief that on or after December 23, 1989,--

(1) No Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress on his or her behalf in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment or modification of any Federal contract, grant, loan, or cooperative agreement;

(2) If any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress or an employee of a Member of Congress on his or her behalf in connection with this solicitation, the offeror shall complete and submit, with its offer, OMB standard form LLL, Disclosure of Lobbying Activities, to the Contracting Officer; and

(3) He or she will include the language of this certification in all subcontract awards at any tier and require that all recipients of subcontract awards in excess of \$100,000 shall certify and disclose accordingly.

(c) Submission of this certification and disclosure is a prerequisite for making or entering into this contract imposed by section 1352, title 31, United States Code. Any person who makes an expenditure prohibited under this provision, shall be subject to a civil penalty

of not less than \$10,000, and not more than \$100,000, for each such failure.

(End of provision)

52.204-3 *TAXPAYER IDENTIFICATION (OCT 1998)*

(a) Definitions.

“Common parent,” as used in this provision, means that corporate entity that owns or controls an affiliated group of corporations that files its Federal income tax returns on a consolidated basis, and of which the offeror is a member.

“Taxpayer Identification Number (TIN),” as used in this provision, means the number required by the Internal Revenue Service (IRS) to be used by the offeror in reporting income tax and other returns. The TIN may be either a Social Security Number or an Employer Identification Number.

(b) All offerors must submit the information required in paragraphs (d) through (f) of this provision to comply with debt collection requirements of 31 U.S.C. 7701(c) and 3325(d), reporting requirements of 26 U.S.C. 6041, 6041A, and 6050M, and implementing regulations issued by the IRS. If the resulting contract is subject to the payment reporting requirements described in Federal Acquisition Regulation (FAR) 4.904, the failure or refusal by the offeror to furnish the information may result in a 31 percent reduction of payments otherwise due under the contract.

(c) The TIN may be used by the Government to collect and report on any delinquent amounts arising out of the offeror's relationship with the Government (31 U.S.C. 7701(c)(3)). If the resulting contract is subject to the payment reporting requirements described in FAR 4.904, the TIN provided hereunder may be matched with IRS records to verify the accuracy of the offeror's TIN.

(d) Taxpayer Identification Number (TIN).

___ TIN: _____

___ TIN has been applied for.

___ TIN is not required because:

___ Offeror is a nonresident alien, foreign corporation, or foreign partnership that does not have income effectively connected with the conduct of a trade or business in the United States and does not have an office or place of business or a fiscal paying agent in the United States;

___ Offeror is an agency or instrumentality of a foreign government;

___ Offeror is an agency or instrumentality of the Federal Government.

(e) Type of organization.

___ Sole proprietorship;

___ Partnership;

___ Corporate entity (not tax-exempt);

___ Corporate entity (tax-exempt);

___ Government entity (Federal, State, or local);

___ Foreign government;

___ International organization per 26 CFR 1.6049-4;

___ Other _____

(f) Common parent.

___ Offeror is not owned or controlled by a common parent as defined in paragraph (a) of this provision.

___ Name and TIN of common parent:

Name _____

TIN _____

(End of provision)

**52.209-5 CERTIFICATION REGARDING DEBARMENT,
SUSPENSION, PROPOSED DEBARMENT, AND OTHER
RESPONSIBILITY MATTERS (DEC 2001)**

(a)(1) The Offeror certifies, to the best of its knowledge and belief, that--

(i) The Offeror and/or any of its Principals--

(A) Are () are not () presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any Federal agency;

(B) Have () have not (), within a three-year period preceding this offer, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, state, or local) contract or subcontract; violation of Federal or state antitrust statutes relating to the submission of offers; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, or receiving stolen property; and

(C) Are () are not () presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in subdivision (a)(1)(i)(B) of this provision.

(ii) The Offeror has () has not (), within a three-year period preceding this offer, had one or more contracts terminated for default by any Federal agency.

(2) "Principals," for the purposes of this certification, means officers; directors; owners; partners; and, persons having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a subsidiary, division, or business segment, and similar positions).

THIS CERTIFICATION CONCERNS A MATTER WITHIN THE JURISDICTION OF AN AGENCY OF THE UNITED STATES AND THE MAKING OF A FALSE, FICTITIOUS, OR FRAUDULENT CERTIFICATION MAY RENDER THE MAKER SUBJECT TO PROSECUTION UNDER SECTION 1001, TITLE 18, UNITED STATES CODE.

(b) The Offeror shall provide immediate written notice to the Contracting Officer if, at any time prior to contract award, the Offeror learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

(c) A certification that any of the items in paragraph (a) of this provision exists will not necessarily result in withholding of an award under this solicitation. However, the certification will be considered in connection with a determination of the Offeror's responsibility. Failure of the Offeror to furnish a certification or provide such additional information as requested by the Contracting Officer may render the Offeror nonresponsible.

(d) Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by paragraph (a) of this provision. The knowledge and information of an Offeror is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

(e) The certification in paragraph (a) of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Offeror knowingly rendered an erroneous certification, in addition to other remedies available to the Government, the Contracting Officer may terminate the contract resulting from this solicitation for default.

(End of provision)

52.219-1 SMALL BUSINESS PROGRAM REPRESENTATIONS (APR 2002)

(a)(1) The North American Industry Classification System (NAICS) code for this acquisition is **237990**.

(2) The small business size standard is **\$28,500,000.00**.

(3) The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is 500 employees.

(b) Representations. (1) The offeror represents as part of its offer that it () is, () is not a small business concern.

(2) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, for general statistical purposes, that it () is, () is not a small disadvantaged business concern as defined in 13 CFR 124.1002.

(3) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it () is, () is not a women-owned small business concern.

(4) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it () is, () is not a veteran-owned small business concern.

(5) (Complete only if the offeror represented itself as a veteran-owned small business concern in paragraph (b)(4) of this provision.) The offeror represents as part of its offer that it () is, () is not a service-disabled veteran-owned small business concern.

(6) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, as part of its offer, that--

(i) It () is, () is not a HUBZone small business concern listed, on the date of this representation, on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration, and no material change in ownership and control, principal office, or HUBZone employee percentage has occurred since it was certified by the Small Business Administration in accordance with 13 CFR part 126; and

(ii) It () is, () is not a joint venture that complies with the requirements of 13 CFR part 126, and the representation in paragraph (b)(6)(i) of this provision is accurate for the HUBZone small business concern or concerns that are participating in the joint venture. (The offeror shall enter the name or names of the HUBZone small business concern or concerns that are participating in the joint venture: _____.) Each HUBZone small business concern participating in the joint venture shall submit a separate signed copy of the HUBZone representation.

(c) Definitions. As used in this provision--

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

"Small business concern," means a concern, including its affiliates, that is independently owned and operated, not dominant in the field of operation in which it is bidding on Government contracts, and qualified as a small business under the criteria in 13 CFR Part 121 and the size standard in paragraph (a) of this provision.

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

"Women-owned small business concern," means a small business concern --

(1) That is at least 51 percent owned by one or more women; in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Notice.

(1) If this solicitation is for supplies and has been set aside, in whole or in part, for small business concerns, then the clause in this solicitation providing notice of the set-aside contains restrictions on the source of the end items to be furnished.

(2) Under 15 U.S.C. 645(d), any person who misrepresents a firm's status as a small, HUBZone small, small disadvantaged, or women-owned small business concern in order to obtain a contract to be awarded under the preference programs established pursuant to section 8(a), 8(d), 9, or 15 of the Small Business Act or any other provision of Federal law that specifically references section 8(d) for a definition of program eligibility, shall--

(i) Be punished by imposition of fine, imprisonment, or both;

(ii) Be subject to administrative remedies, including suspension and debarment; and

(iii) Be ineligible for participation in programs conducted under the authority of the Act.

(End of provision)

52.219-2 *EQUAL LOW BIDS. (OCT 1995)*

(a) This provision applies to small business concerns only.

(b) The bidder's status as a labor surplus area (LSA) concern may affect entitlement to award in case of tie bids. If the bidder wishes to be considered for this priority, the bidder must identify, in the following space, the LSA in which the costs to be incurred on account of manufacturing or production (by the bidder or the first-tier subcontractors) amount to more than 50 percent of the contract price.

(c) Failure to identify the labor surplus area as specified in paragraph (b) of this provision will preclude the bidder from receiving priority consideration. If the bidder is awarded a contract as a result of receiving priority consideration under this provision and would not have otherwise received award, the bidder shall perform the contract or cause the contract to be performed in accordance with the obligations of an LSA concern.

**52.219-19 SMALL BUSINESS CONCERN REPRESENTATION
FOR THE SMALL BUSINESS COMPETITIVENESS
DEMONSTRATION PROGRAM (OCT 2000)**

(a) Definition.

"Emerging small business" as used in this solicitation, means a small business concern whose size is no greater than 50 percent of the numerical size standard applicable to the North American Industry Classification System (NAICS) code assigned to a contracting opportunity.

(b) [Complete only if the Offeror has represented itself under the provision at 52.219-1 as a small business concern under the size standards of this solicitation.] The Offeror [] is, [] is not an emerging small business.

(c) (Complete only if the Offeror is a small business or an emerging small business, indicating its size range.)

Offeror's number of employees for the past 12 months (check this column if size standard stated in solicitation is expressed in terms of number of employees) or Offeror's average annual gross revenue for the last 3 fiscal years (check this column if size standard stated in solicitation is expressed in terms of annual receipts). (Check one of the following.)

No. of Employees Avg. Annual Gross Revenues

_____ 50 or fewer	_____ \$1 million or less
_____ 51 - 100	_____ \$1,000,001 - \$2 million
_____ 101 - 250	_____ \$2,000,001 - \$3.5 million
_____ 251 - 500	_____ \$3,500,001 - \$5 million
_____ 501 - 750	_____ \$5,000,001 - \$10 million

____ 751 - 1,000 ____ \$10,000,001 - \$17 million

____ Over 1,000 ____ Over \$17 million

(End of provision)

**52.219-21 SMALL BUSINESS SIZE REPRESENTATION FOR
TARGETED INDUSTRY CATEGORIES UNDER THE SMALL
BUSINESS COMPETITIVENESS DEMONSTRATION PROGRAM
(MAY 1999)**

(Complete only if the Offeror has represented itself under the provision at 52.219-1 as a small business concern under the size standards of this solicitation.)

Offeror's number of employees for the past 12 months (check this column if size standard stated in solicitation is expressed in terms of number of employees) or Offeror's average annual gross revenue for the last 3 fiscal years (check this column if size standard stated in solicitation is expressed in terms of annual receipts). (Check one of the following.)

No. of Employees Avg. Annual Gross Revenues

____ 50 or fewer ____ \$1 million or less

____ 51 - 100 ____ \$1,000,001 - \$2 million

____ 101 - 250 ____ \$2,000,001 - \$3.5 million

____ 251 - 500 ____ \$3,500,001 - \$5 million

____ 501 - 750 ____ \$5,000,001 - \$10 million

____ 751 - 1,000 ____ \$10,000,001 - \$17 million

____ 17 million

(End of provision)

**52.222-22 PREVIOUS CONTRACTS AND COMPLIANCE
REPORTS (FEB 1999)**

The offeror represents that --

(a) ☐ It has, ☐ has not participated in a previous contract or subcontract subject to the Equal Opportunity clause of this solicitation;

(b) ☐ It has, ☐ has not, filed all required compliance reports; and

(c) Representations indicating submission of required compliance reports, signed by proposed subcontractors, will be obtained before subcontract awards.

(End of provision)

**52.223-13 CERTIFICATION OF TOXIC CHEMICAL RELEASE
REPORTING (OCT 2000)**

(a) Submission of this certification is a prerequisite for making or entering into this contract imposed by Executive Order 12969, August 8, 1995.

(b) By signing this offer, the offeror certifies that--

(1) As the owner or operator of facilities that will be used in the performance of this contract that are subject to the filing and reporting requirements described in section 313 of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023) and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106), the offeror will file and continue to file for such facilities for the life of the contract the Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of EPCRA and section 6607 of PPA; or

(2) None of its owned or operated facilities to be used in the performance of this contract is subject to the Form R filing and reporting requirements because each such facility is exempt for at least one of the following reasons: (Check each block that is applicable.)

☐ (i) The facility does not manufacture, process or otherwise use any toxic chemicals listed under section 313(c) of EPCRA, 42 U.S.C. 11023(c);

☐ (ii) The facility does not have 10 or more full-time employees as specified in section 313.(b)(1)(A) of EPCRA 42 U.S.C. 11023(b)(1)(A);

() (iii) The facility does not meet the reporting thresholds of toxic chemicals established under section 313(f) of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

() (iv) The facility does not fall within Standard Industrial Classification Code (SIC) major groups 20 through 39 or their corresponding North American Industry Classification System (NAICS) sectors 31 through 33; or

() (v) The facility is not located within any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the United States Virgin Islands, the Northern Mariana Islands, or any other territory or possession over which the United States has jurisdiction.

(End of clause)

**252.204-7001 COMMERCIAL AND GOVERNMENT ENTITY
(CAGE) CODE REPORTING (AUG 1999)**

(a) The offeror is requested to enter its CAGE code on its offer in the block with its name and address. The CAGE code entered must be for that name and address. Enter "CAGE" before the number.

(b) If the offeror does not have a CAGE code, it may ask the Contracting Officer to request one from the Defense Logistics Information Service (DLIS). The Contracting Officer will--

(1) Ask the Contractor to complete section B of a DD Form 2051, Request for Assignment of a Commercial and Government Entity (CAGE) Code;

(2) Complete section A and forward the form to DLIS; and

(3) Notify the Contractor of its assigned CAGE code.

(c) Do not delay submission of the offer pending receipt of a CAGE code.

(End of provision)

**252.209-7001 DISCLOSURE OF OWNERSHIP OR CONTROL BY
THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998)**

(a) "Definitions."

As used in this provision --

(a) "Government of a terrorist country" includes the state and the government of a terrorist country, as well as any political subdivision, agency, or instrumentality thereof.

(2) "Terrorist country" means a country determined by the Secretary of State, under section 6(j)(1)(A) of the Export Administration Act of 1979 (50 U.S.C. App. 2405(j)(i)(A)), to be a country the government of which has repeatedly provided support for such acts of international terrorism. As of the date of this provision, terrorist countries include: Cuba, Iran, Iraq, Libya, North Korea, Sudan, and Syria.

(3) "Significant interest" means --

(i) Ownership of or beneficial interest in 5 percent or more of the firm's or subsidiary's securities. Beneficial interest includes holding 5 percent or more of any class of the firm's securities in "nominee shares," "street names," or some other method of holding securities that does not disclose the beneficial owner;

(ii) Holding a management position in the firm, such as a director or officer;

(iii) Ability to control or influence the election, appointment, or tenure of directors or officers in the firm;

(iv) Ownership of 10 percent or more of the assets of a firm such as equipment, buildings, real estate, or other tangible assets of the firm; or

(v) Holding 50 percent or more of the indebtedness of a firm.

(b) "Prohibition on award."

In accordance with 10 U.S.C. 2327, no contract may be awarded to a firm or a subsidiary of a firm if the government of a terrorist country has a significant interest in the firm or subsidiary or, in the case of a subsidiary, the firm that owns the subsidiary, unless a waiver is granted by the Secretary of Defense.

(c) "Disclosure."

If the government of a terrorist country has a significant interest in the Offeror or a subsidiary of the Offeror, the Offeror shall disclose such interest in an attachment to its offer. If the Offeror is a subsidiary, it shall also disclose any significant interest the government of a terrorist country has in any firm that owns or controls the subsidiary. The disclosure shall include --

(1) Identification of each government holding a significant interest; and

(2) A description of the significant interest held by each government.

(End of provision)

**252.247-7022 REPRESENTATION OF EXTENT OF
TRANSPORTATION BY SEA (AUG 1992)**

(a) The Offeror shall indicate by checking the appropriate blank in paragraph (b) of this provision whether transportation of supplies by sea is anticipated under the resultant contract. The term supplies is defined in the Transportation of Supplies by Sea clause of this solicitation.

(b) Representation. The Offeror represents that it:

____ (1) Does anticipate that supplies will be transported by sea in the performance of any contract or subcontract resulting from this solicitation.

____ (2) Does not anticipate that supplies will be transported by sea in the performance of any contract or subcontract resulting from this solicitation.

(c) Any contract resulting from this solicitation will include the Transportation of Supplies by Sea clause. If the Offeror represents that it will not use ocean transportation, the resulting contract will also include the Defense FAR Supplement clause at 252.247-7024, Notification of Transportation of Supplies by Sea.

(End of provision)

**SECTION 00700
CONTRACT CLAUSES
TABLE OF CONTENTS**

52.202-1	DEFINITIONS (DEC 2001).....	1
52.203-3	GRATUITIES (APR 1984)	3
52.203-5	COVENANT AGAINST CONTINGENT FEES (APR 1984).....	4
52.203-7	ANTI-KICKBACK PROCEDURES. (JUL 1995).....	4
52.203-8	CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)	6
52.203-12	LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (JUN 1997)	7
52.204-4	PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000)	12
52.209-6	PROTECTING THE GOVERNMENT’S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JUL 1995).....	13
52.211-18	VARIATION IN ESTIMATED QUANTITY (APR 1984).....	14
52.214-26	AUDIT AND RECORDS—SEALED BIDDING. (OCT 1997).....	14
52.214-27	PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA - MODIFICATIONS - SEALED BIDDING. (OCT 1997).....	16
52.214-28	SUBCONTRACTOR COST OR PRICING DATA - MODIFICATIONS - SEALED BIDDING. (OCT 1997).....	18
52.214-29	ORDER OF PRECEDENCE--SEALED BIDDING (JAN 1986).....	19
52.219-8	UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000)	19
52.219-14	LIMITATIONS ON SUBCONTRACTING (DEC 1996)	21
52.219-18	NOTIFICATION OF COMPETITION LIMITED TO ELIGIBLE 8(A) CONCERNS (JUN 1999)--ALTERNATE I (NOV 1989)	21

52.222-3	CONVICT LABOR (AUG 1996)	22
52.222-4	CONTRACT WORK HOURS AND SAFETY STANDARDS ACT - OVERTIME COMPENSATION. (SEP 2000)	23
52.222-6	DAVIS-BACON ACT (FEB 1995).....	24
52.222-7	WITHHOLDING OF FUNDS (FEB 1988)	26
52.222-8	PAYROLLS AND BASIC RECORDS (FEB 1988).....	26
52.222-9	APPRENTICES AND TRAINEES (FEB 1988).....	28
52.222-10	COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988) ...	29
52.222-11	SUBCONTRACTS (LABOR STANDARDS (FEB 1988).....	29
52.222-12	CONTRACT TERMINATION--DEBARMENT (FEB 1988)	30
52.222-13	COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988).....	30
52.222-14	DISPUTES CONCERNING LABOR STANDARDS (FEB 1988).....	31
52.222-15	CERTIFICATION OF ELIGIBILITY (FEB 1988)	31
52.222-21	PROHIBITION OF SEGREGATED FACILITIES (FEB 1999).....	31
52.222-26	EQUAL OPPORTUNITY (APR 2002)	32
52.222-27	AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (FEB 1999).....	34
52.222-35	EQUAL OPPORTUNITY FOR SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)	39
52.222-36	AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)	43
52.222-37	EMPLOYMENT REPORTS ON SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)	44

52.223-3	HAZARDOUS MATERIAL IDENTIFICATION AND MATERIAL SAFETY DATA (JAN 1997)	45
52.223-6	DRUG-FREE WORKPLACE (MAY 2001).....	47
52.223-14	TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)	49
52.225-9	BUY AMERICAN ACT—CONSTRUCTION MATERIALS (MAY 2002).....	50
52.225-13	RESTRICTIONS ON CERTAIN FOREIGN PURCHASES (JUL 2000).....	53
52.226-1	UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES (JUN 2000)	54
52.227-1	AUTHORIZATION AND CONSENT (JUL 1995).....	55
52.227-2	NOTICE AND ASSISTANCE REGARDING PATENT AND COPYRIGHT INFRINGEMENT (AUG 1996)	56
52.227-4	PATENT INDEMNITY--CONSTRUCTION CONTRACTS (APR 1984)	56
52.228-2	ADDITIONAL BOND SECURITY (OCT 1997).....	57
52.228-11	PLEDGES OF ASSETS (FEB 1992).....	57
52.228-12	PROSPECTIVE SUBCONTRACTOR REQUEST FOR BONDS. (OCT 1995)	58
52.228-14	IRREVOCABLE LETTER OF CREDIT (DEC 1999).....	58
52.228-15	PERFORMANCE AND PAYMENT BONDS—CONSTRUCTION (JUL 2000)-	63
52.229-3	FEDERAL, STATE, AND LOCAL TAXES (JAN 1991).....	64
52.229-5	TAXES--CONTRACTS PERFORMED IN U.S. POSSESSIONS OR PUERTO RICO (APR 1984).....	65
52.232-5	PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (SEP 2002)	65
52.232-17	INTEREST (JUNE 1996).....	68
52.232-23	ASSIGNMENT OF CLAIMS (JAN 1986)	69
52.232-27	PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (FEB 2002)	69

52.232-33	PAYMENT BY ELECTRONIC FUNDS TRANSFER—CENTRAL CONTRACTOR REGISTRATION (MAY 1999)	77
52.233-1	DISPUTES. (JUL 2002).....	79
52.233-3	PROTEST AFTER AWARD (AUG. 1996).....	81
52.236-2	DIFFERING SITE CONDITIONS (APR 1984).....	82
52.236-3	SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)	83
52.236-5	MATERIAL AND WORKMANSHIP (APR 1984)	84
52.236-6	SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)	84
52.236-7	PERMITS AND RESPONSIBILITIES (NOV 1991)	85
52.236-8	OTHER CONTRACTS (APR 1984).....	85
52.236-9	PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984).....	85
52.236-10	OPERATIONS AND STORAGE AREAS (APR 1984).....	86
52.236-11	USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)	87
52.236-12	CLEANING UP (APR 1984).....	87
52.236-13	ACCIDENT PREVENTION (NOV 1991) – ALTERNATE I (NOV 1991)	87
52.236-15	SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)	89
52.236-17	LAYOUT OF WORK (APR 1984).....	89
52.236-21	SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)	90
52.236-26	PRECONSTRUCTION CONFERENCE (FEB 1995).....	91
52.242-13	BANKRUPTCY (JUL 1995)	91
52.242-14	SUSPENSION OF WORK (APR 1984)	92
52.243-4	CHANGES (AUG 1987).....	92
52.244-6	SUBCONTRACTS FOR COMMERCIAL ITEMS (MAY 2002).....	94

52.245-2	GOVERNMENT PROPERTY (FIXED-PRICE CONTRACTS) (DEC 1989) ..	94
52.245-4	GOVERNMENT-FURNISHED PROPERTY (SHORT FORM) (APR 1984) ..	98
52.246-12	INSPECTION OF CONSTRUCTION (AUG 1996)	99
52.246-13	INSPECTION--DISMANTLING, DEMOLITION, OR REMOVAL OF IMPROVEMENTS (AUG 1996).....	100
52.247-34	F.O.B. DESTINATION (NOV 1991)	101
52.248-3	VALUE ENGINEERING--CONSTRUCTION (FEB 2000).....	102
52.249-2	TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (SEP 1996) - ALTERNATE I (SEP 1996)	105
52.249-3	TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (DISMANTLING, DEMOLITION, OR REMOVAL OF IMPROVEMENTS) (SEP 1996)	109
52.249-10	DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)	113
52.252-2	CLAUSES INCORPORATED BY REFERENCE (FEB 1998).....	114
52.252-4	ALTERATIONS IN CONTRACT (APR 1984)	115
52.252-6	AUTHORIZED DEVIATIONS IN CLAUSES (APR 1984).....	115
52.253-1	COMPUTER GENERATED FORMS (JAN 1991).....	115
252.201-7000	CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991).....	116
252.203-7001	PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (MAR 1999).....	116
252.204-7003	CONTROL OF GOVERNMENT PERSONNEL WORK PRODUCT (APR 1992)	118
252.204-7004	REQUIRED CENTRAL CONTRACTOR REGISTRATION (NOV 2001)	118
252.209-7000ACQUISITION FROM SUBCONTRACTORS SUBJECT TO ONSITE INSPECTION UNDER THE INTERMEDIATE-RANGE NUCLEAR FORCES (INF) TREATY (NOV 1995)	119

252.209-7004	SUBCONTRACTING WITH FIRMS THAT ARE OWNED OR CONTROLLED BY THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998)	119
252.219-7009	SECTION 8(A) DIRECT AWARD (MAR 2002)	120
252.223-7001	HAZARD WARNING LABELS (DEC 1991)	121
252.223-7004	DRUG-FREE WORK FORCE (SEP 1988)	122
252.225-7012	PREFERENCE FOR CERTAIN DOMESTIC COMMODITIES (FEB 2003)	123
252.225-7031	SECONDARY ARAB BOYCOTT OF ISRAEL (JUN 1992)	125
252.227-7033	RIGHTS IN SHOP DRAWINGS (APR 1966)	126
252.231-7000	SUPPLEMENTAL COST PRINCIPLES (DEC 1991)	126
252.236-7000	MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)	126
252.243-7001	PRICING OF CONTRACT MODIFICATIONS (DEC 1991)	127
252.247-7023	TRANSPORTATION OF SUPPLIES BY SEA (MAY 2002)	127
252.247-7024	NOTIFICATION OF TRANSPORTATION OF SUPPLIES BY SEA (MAR 2000)	131

SECTION 00700

CONTRACT CLAUSES

52.202-1 DEFINITIONS (DEC 2001)

(a) Agency head or head of the agency means the Secretary (Attorney General, Administrator, Governor, Chairperson, or other chief official, as appropriate) of the agency, unless otherwise indicated, including any deputy or assistant chief official of the executive agency.

(b) Commercial component means any component that is a commercial item.

(c) Commercial item means--

(1) Any item, other than real property, that is of a type customarily used by the general public or by non-governmental entities for purposes other than governmental purposes, and that--

(i) Has been sold, leased, or licensed to the general public; or

(ii) Has been offered for sale, lease, or license to the general public;

(2) Any item that evolved from an item described in paragraph (c)(1) of this clause through advances in technology or performance and that is not yet available in the commercial marketplace, but will be available in the commercial marketplace in time to satisfy the delivery requirements under a Government solicitation;

(3) Any item that would satisfy a criterion expressed in paragraphs (c)(1) or (c)(2) of this clause, but for--

(i) Modifications of a type customarily available in the commercial marketplace; or

(ii) Minor modifications of a type not customarily available in the commercial marketplace made to meet Federal Government requirements. "Minor" modifications means modifications that do not significantly alter the nongovernmental function or essential physical characteristics of an item or component, or change the purpose of a process. Factors to be considered in determining whether a modification is minor include the value and size of the modification and the comparative value and size of the final product. Dollar values and percentages may be used as guideposts, but are not conclusive evidence that a modification is minor;

(4) Any combination of items meeting the requirements of paragraphs (c)(1), (2), (3), or (5) of this clause that are of a type customarily combined and sold in combination to the general public;

(5) Installation services, maintenance services, repair services, training services, and other services if--

(i) Such services are procured for support of an item referred to in paragraph (c)(1), (2), (3), or (4) of this definition, regardless of whether such services are provided by the same source or at the same time as the item; and

(ii) The source of such services provides similar services contemporaneously to the general public under terms and conditions similar to those offered to the Federal Government;

(6) Services of a type offered and sold competitively in substantial quantities in the commercial marketplace based on established catalog or market prices for specific tasks performed under standard commercial terms and conditions. This does not include services that are sold based on hourly rates without an established catalog or market price for a specific service performed. For purposes of these services--

(i) Catalog price means a price included in a catalog, price list, schedule, or other form that is regularly maintained by the manufacturer or vendor, is either published or otherwise available for inspection by customers, and states prices at which sales are currently, or were last, made to a significant number of buyers constituting the general public; and

(ii) Market prices means current prices that are established in the course of ordinary trade between buyers and sellers free to bargain and that can be substantiated through competition or from sources independent of the offerors.

(7) Any item, combination of items, or service referred to in subparagraphs (c)(1) through (c)(6), notwithstanding the fact that the item, combination of items, or service is transferred between or among separate divisions, subsidiaries, or affiliates of a Contractor; or

(8) A nondevelopmental item, if the procuring agency determines the item was developed exclusively at private expense and sold in substantial quantities, on a competitive basis, to multiple State and local Governments.

(d) Component means any item supplied to the Government as part of an end item or of another component, except that for use in 52.225-9, and 52.225-11 see the definitions in 52.225-9(a) and 52.225-11(a).

(e) Contracting Officer means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.

(f) Nondevelopmental item means--

(1) Any previously developed item of supply used exclusively for governmental purposes by a Federal agency, a State or local government, or a foreign government with which the United States has a mutual defense cooperation agreement;

(2) Any item described in paragraph (f)(1) of this definition that requires only minor modification or modifications of a type customarily available in the commercial marketplace in order to meet the requirements of the procuring department or agency; or

(3) Any item of supply being produced that does not meet the requirements of paragraph (f)(1) or (f)(2) solely because the item is not yet in use.

(g) "Contracting Officer" means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.

(h) Except as otherwise provided in this contract, the term "subcontracts" includes, but is not limited to, purchase orders and changes and modifications to purchase orders under this contract.

(End of clause)

52.203-3 GRATUITIES (APR 1984)

(a) The right of the Contractor to proceed may be terminated by written notice if, after notice and hearing, the agency head or a designee determines that the Contractor, its agent, or another representative--

(1) Offered or gave a gratuity (e.g., an entertainment or gift) to an officer, official, or employee of the Government; and

(2) Intended, by the gratuity, to obtain a contract or favorable treatment under a contract.

(b) The facts supporting this determination may be reviewed by any court having lawful jurisdiction.

(c) If this contract is terminated under paragraph (a) of this clause, the Government is entitled--

(1) To pursue the same remedies as in a breach of the contract; and

(2) In addition to any other damages provided by law, to exemplary damages of not less than 3 nor more than 10 times the cost incurred by the Contractor in giving gratuities to the person concerned, as determined by the agency head or a designee. (This subparagraph (c)(2) is applicable only if this contract uses money appropriated to the Department of Defense.)

(d) The rights and remedies of the Government provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-5 COVENANT AGAINST CONTINGENT FEES (APR 1984)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover, the full amount of the contingent fee.

(b) "Bona fide agency," as used in this clause, means an established commercial or selling agency, maintained by a contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a contractor and subject to the contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

(End of clause)

52.203-7 ANTI-KICKBACK PROCEDURES. (JUL 1995)

(a) Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided, directly or indirectly, to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contract or in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any

kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

(b) The Anti-Kickback Act of 1986 (41 U.S.C. 51-58) (the Act), prohibits any person from -

(1) Providing or attempting to provide or offering to provide any kickback;

(2) Soliciting, accepting, or attempting to accept any kickback; or

(3) Including, directly or indirectly, the amount of any kickback in the contract price charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

(c)(1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.

(2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Department of Justice.

(3) The Contractor shall cooperate fully with any Federal agency investigating a possible

violation described in paragraph (b) of this clause.

(4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold, from sums owed a subcontractor under the prime contract, the amount of any kickback. The Contracting Officer may order the monies withheld under subdivision (c)(4)(ii) of this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.

(5) The Contractor agrees to incorporate the substance of this clause, including this subparagraph (c)(5) but excepting subparagraph (c)(1), in all subcontracts under this contract which exceed \$100,000.

52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) If the Government receives information that a contractor or a person has engaged in conduct constituting a violation of subsection (a), (b), (c), or (d) of Section 27 of the Office of Federal Procurement Policy Act (41 U.S.C. 423) (the Act), as amended by section 4304 of the 1996 National Defense Authorization Act for Fiscal Year 1996 (Pub. L. 104-106), the Government may--

(1) Cancel the solicitation, if the contract has not yet been awarded or issued; or

(2) Rescind the contract with respect to which--

(i) The Contractor or someone acting for the Contractor has been convicted for an offense where the conduct constitutes a violation of subsection 27(a) or (b) of the Act for the purpose of either--

(A) Exchanging the information covered by such subsections for anything of value; or

(B) Obtaining or giving anyone a competitive advantage in the award of a Federal agency procurement contract; or

(ii) The head of the contracting activity has determined, based upon a preponderance of the evidence, that the Contractor or someone acting for the Contractor has engaged in conduct constituting an offense punishable under subsections 27(e)(1) of the Act.

(b) If the Government rescinds the contract under paragraph (a) of this clause, the Government is

entitled to recover, in addition to any penalty prescribed by law, the amount expended under the contract.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law, regulation, or under this contract.

(End of clause)

**52.203-12 *LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN
FEDERAL TRANSACTIONS (JUN 1997)***

(a) Definitions.

"Agency," as used in this clause, means executive agency as defined in 2.101.

"Covered Federal action," as used in this clause, means any of the following Federal actions:

- (1) The awarding of any Federal contract.
- (2) The making of any Federal grant.
- (3) The making of any Federal loan.
- (4) The entering into of any cooperative agreement.
- (5) The extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

"Indian tribe" and "tribal organization," as used in this clause, have the meaning provided in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450B) and include Alaskan Natives.

"Influencing or attempting to influence," as used in this clause, means making, with the intent to influence, any communication to or appearance before an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal action.

"Local government," as used in this clause, means a unit of government in a State and, if chartered, established, or otherwise recognized by a State for the performance of a governmental duty, including a local public authority, a special district, an intrastate district, a council of governments, a sponsor group representative organization, and any other instrumentality of a local government.

"Officer or employee of an agency," as used in this clause, includes the following individuals who are employed by an agency:

- (1) An individual who is appointed to a position in the Government under Title 5, United States Code, including a position under a temporary appointment.
- (2) A member of the uniformed services, as defined in subsection 101(3), Title 37, United States Code.
- (3) A special Government employee, as defined in section 202, Title 18, United States Code.
- (4) An individual who is a member of a Federal advisory committee, as defined by the Federal Advisory Committee Act, Title 5, United States Code, appendix 2.

"Person," as used in this clause, means an individual, corporation, company, association, authority, firm, partnership, society, State, and local government, regardless of whether such entity is operated for profit, or not for profit. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Reasonable compensation," as used in this clause, means, with respect to a regularly employed officer or employee of any person, compensation that is consistent with the normal compensation for such officer or employee for work that is not furnished to, not funded by, or not furnished in cooperation with the Federal Government.

"Reasonable payment," as used in this clause, means, with respect to professional and other technical services, a payment in an amount that is consistent with the amount normally paid for such services in the private sector.

"Recipient," as used in this clause, includes the Contractor and all subcontractors. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Regularly employed," as used in this clause, means, with respect to an officer or employee of a person requesting or receiving a Federal contract, an officer or employee who is employed by such person for at least 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person for receipt of such contract. An officer or employee who is employed by such person for less than 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person shall be considered to be regularly employed as soon as he or she is employed by such person for 130 working days.

"State," as used in this clause, means a State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, a territory or possession of the United States, an agency or instrumentality of a State, and multi-State, regional, or interstate entity having governmental duties and powers.

(b) Prohibitions.

(1) Section 1352 of Title 31, United States Code, among other things, prohibits a recipient of a Federal contract, grant, loan, or cooperative agreement from using appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any of the following covered Federal actions: the awarding of any Federal contract; the making of any Federal grant; the making of any Federal loan; the entering into of any cooperative agreement; or the modification of any Federal contract, grant, loan, or cooperative agreement.

(2) The Act also requires Contractors to furnish a disclosure if any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with a Federal contract, grant, loan, or cooperative agreement.

(3) The prohibitions of the Act do not apply under the following conditions:

(i) Agency and legislative liaison by own employees.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of a payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action if the payment is for agency and legislative liaison activities not directly related to a covered Federal action.

(B) For purposes of subdivision (b)(3)(i)(A) of this clause, providing any information specifically requested by an agency or Congress is permitted at any time.

(C) The following agency and legislative liaison activities are permitted at any time where they are not related to a specific solicitation for any covered Federal action:

(1) Discussing with an agency the qualities and characteristics (including individual demonstrations) of the person's products or services, conditions or terms of sale, and service capabilities.

(2) Technical discussions and other activities regarding the application or adaptation of the person's products or services for an agency's use.

(D) The following agency and legislative liaison activities are permitted where they are prior to formal solicitation of any covered Federal action--

(1) Providing any information not specifically requested but necessary for an agency to make an informed decision about initiation of a covered Federal action;

(2) Technical discussions regarding the preparation of an unsolicited proposal prior to its official submission; and

(3) Capability presentations by persons seeking awards from an agency pursuant to the provisions of the Small Business Act, as amended by Pub. L. 95-507, and subsequent amendments.

(E) Only those services expressly authorized by subdivision (b)(3)(i)(A) of this clause are permitted under this clause.

(ii) Professional and technical services.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of--

(1) A payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action, if payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action.

(2) Any reasonable payment to a person, other than an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action if the payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action. Persons other than officers or employees of a person requesting or receiving a covered Federal action include consultants and trade associations.

(B) For purposes of subdivision (b)(3)(ii)(A) of this clause, "professional and technical services" shall be limited to advice and analysis directly applying any professional or technical discipline. For example, drafting of a legal document accompanying a bid or proposal by a lawyer is allowable. Similarly, technical advice provided by an engineer on the performance or operational capability of a piece of equipment rendered directly in the negotiation of a contract is allowable. However, communications with the intent to influence made by a professional (such as a licensed lawyer) or a technical person (such as a licensed accountant) are not allowable under this section unless they provide advice and analysis directly applying their professional or technical expertise and unless the advice or analysis is rendered directly and solely in the preparation, submission or negotiation of a covered Federal action. Thus, for example, communications with the intent to influence made by a lawyer that do not provide legal advice or analysis directly and solely related to the legal aspects of his or her client's proposal, but generally advocate one proposal over another are not allowable under this section because the lawyer is not providing professional legal services. Similarly, communications with the intent to

influence made by an engineer providing an engineering analysis prior to the preparation or submission of a bid or proposal are not allowable under this section since the engineer is providing technical services but not directly in the preparation, submission or negotiation of a covered Federal action.

(C) Requirements imposed by or pursuant to law as a condition for receiving a covered Federal award include those required by law or regulation and any other requirements in the actual award documents.

(D) Only those services expressly authorized by subdivisions (b)(3)(ii)(A)(1) and (2) of this clause are permitted under this clause.

(E) The reporting requirements of FAR 3.803(a) shall not apply with respect to payments of reasonable compensation made to regularly employed officers or employees of a person.

(c) Disclosure.

(1) The Contractor who requests or receives from an agency a Federal contract shall file with that agency a disclosure form, OMB standard form LLL, Disclosure of Lobbying Activities, if such person has made or has agreed to make any payment using nonappropriated funds (to include profits from any covered Federal action), which would be prohibited under subparagraph (b)(1) of this clause, if paid for with appropriated funds.

(2) The Contractor shall file a disclosure form at the end of each calendar quarter in which there occurs any event that materially affects the accuracy of the information contained in any disclosure form previously filed by such person under subparagraph (c)(1) of this clause. An event that materially affects the accuracy of the information reported includes--

(i) A cumulative increase of \$25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or

(ii) A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or

(iii) A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

(3) The Contractor shall require the submittal of a certification, and if required, a disclosure form by any person who requests or receives any subcontract exceeding \$100,000 under the Federal contract.

(4) All subcontractor disclosure forms (but not certifications) shall be forwarded from tier to tier until received by the prime Contractor. The prime Contractor shall submit all disclosures to the Contracting Officer at the end of the calendar quarter in which the disclosure form is submitted by the subcontractor. Each subcontractor certification shall be retained in the subcontract file of the awarding Contractor.

(d) Agreement. The Contractor agrees not to make any payment prohibited by this clause.

(e) Penalties.

(1) Any person who makes an expenditure prohibited under paragraph (a) of this clause or who fails to file or amend the disclosure form to be filed or amended by paragraph (b) of this clause shall be subject to civil penalties as provided for by 31 U.S.C. 1352. An imposition of a civil penalty does not prevent the Government from seeking any other remedy that may be applicable.

(2) Contractors may rely without liability on the representation made by their subcontractors in the certification and disclosure form.

(f) Cost allowability. Nothing in this clause makes allowable or reasonable any costs which would otherwise be unallowable or unreasonable. Conversely, costs made specifically unallowable by the requirements in this clause will not be made allowable under any other provision.

(End of clause)

52.204-4 *PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000)*

(a) Definitions. As used in this clause--

“Postconsumer material” means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of “recovered material.” For paper and paper products, postconsumer material means “postconsumer fiber” defined by the U.S. Environmental Protection Agency (EPA) as--

(1) Paper, paperboard, and fibrous materials from retail stores, office buildings, homes, and so forth, after they have passed through their end-usage as a consumer item, including: used corrugated boxes; old newspapers; old magazines; mixed waste paper; tabulating cards; and used cordage; or

(2) All paper, paperboard, and fibrous materials that enter and are collected from municipal solid waste; but not

(3) Fiber derived from printers' over-runs, converters' scrap, and over-issue publications.

“Printed or copied double-sided” means printing or reproducing a document so that information is on both sides of a sheet of paper.

“Recovered material,” for paper and paper products, is defined by EPA in its Comprehensive Procurement Guideline as “recovered fiber” and means the following materials:

(1) Postconsumer fiber; and

(2) Manufacturing wastes such as--

(i) Dry paper and paperboard waste generated after completion of the papermaking process (that is, those manufacturing operations up to and including the cutting and trimming of the paper machine reel into smaller rolls or rough sheets) including: envelope cuttings, bindery trimmings, and other paper and paperboard waste resulting from printing, cutting, forming, and other converting operations; bag, box, and carton manufacturing wastes; and butt rolls, mill wrappers, and rejected unused stock; and

(ii) Repulped finished paper and paperboard from obsolete inventories of paper and paperboard manufacturers, merchants, wholesalers, dealers, printers, converters, or others.

(b) In accordance with Section 101 of Executive Order 13101 of September 14, 1998, Greening the Government through Waste Prevention, Recycling, and Federal Acquisition, the Contractor is encouraged to submit paper documents, such as offers, letters, or reports, that are printed or copied double-sided on recycled paper that meet minimum content standards specified in Section 505 of Executive Order 13101, when not using electronic commerce methods to submit information or data to the Government.

(c) If the Contractor cannot purchase high-speed copier paper, offset paper, forms bond, computer printout paper, carbonless paper, file folders, white wove envelopes, writing and office paper, book paper, cotton fiber paper, and cover stock meeting the 30 percent postconsumer material standard for use in submitting paper documents to the Government, it should use paper containing no less than 20 percent postconsumer material. This lesser standard should be used only when paper meeting the 30 percent postconsumer material standard is not obtainable at a reasonable price or does not meet reasonable performance standards.

(End of clause)

52.209-6 *Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, or Proposed for Debarment (JUL 1995)*

(a) The Government suspends or debars Contractors to protect the Government's interests. The Contractor shall not enter into any subcontract in excess of the \$25,000 with a Contractor that is debarred, suspended, or proposed for debarment unless there is a compelling reason to do so.

(b) The Contractor shall require each proposed first-tier subcontractor, whose subcontract will

exceed \$25,000, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principles, is or is not debarred, suspended, or proposed for debarment by the Federal Government.

(c) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs). The notice must include the following:

(1) The name of the subcontractor.

(2) The Contractor's knowledge of the reasons for the subcontractor being on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs.

(3) The compelling reason(s) for doing business with the subcontractor notwithstanding its inclusion on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs.

(4) The systems and procedures the Contractor has established to ensure that it is fully protecting the Government's interests when dealing with such subcontractor in view of the specific basis for the party's debarment, suspension, or proposed debarment.

(End of clause)

52.211-18 *VARIATION IN ESTIMATED QUANTITY (APR 1984)*

If the quantity of a unit-priced item in this contract is an estimated quantity and the actual quantity of the unit-priced item varies more than 15 percent above or below the estimated quantity, an equitable adjustment in the contract price shall be made upon demand of either party. The equitable adjustment shall be based upon any increase or decrease in costs due solely to the variation above 115 percent or below 85 percent of the estimated quantity. If the quantity variation is such as to cause an increase in the time necessary for completion, the Contractor may request, in writing, an extension of time, to be received by the Contracting Officer within 10 days from the beginning of the delay, or within such further period as may be granted by the Contracting Officer before the date of final settlement of the contract. Upon the receipt of a written request for an extension, the Contracting Officer shall ascertain the facts and make an adjustment for extending the completion date as, in the judgement of the Contracting Officer, is justified.

52.214-26 *Audit and Records--Sealed Bidding. (OCT 1997)*

(a) As used in this clause, records includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.

(b) Cost or pricing data. If the Contractor has been required to submit cost or pricing data in connection with the pricing of any modification to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to--

(1) The proposal for the modification;

(2) The discussions conducted on the proposal(s), including those related to negotiating;

(3) Pricing of the modification; or

(4) Performance of the modification.

(c) Comptroller General. In the case of pricing any modification, the Comptroller General of the United States, or an authorized representative, shall have the same rights as specified in paragraph (b) of this clause.

(d) Availability. The Contractor shall make available at its office at all reasonable times the materials described in reproduction, until 3 years after final payment under this contract, or for any other period specified in Subpart 4.7 of the Federal Acquisition Regulation (FAR). FAR Subpart 4.7, Contractor Records Retention, in effect on the date of this contract, is incorporated by reference in its entirety and made a part of this contract.

(1) If this contract is completely or partially terminated, the records relating to the work terminated shall be made available for 3 years after any resulting final termination settlement.

(2) Records pertaining to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to the performance of this contract shall be made available until disposition of such appeals, litigation, or claims.

(e) The Contractor shall insert a clause containing all the provisions of this clause, including this paragraph (e), in all subcontracts expected to exceed the threshold in FAR 15.403-4(a)(1) for submission of cost or pricing data.

(End of clause)

52.214-27 Price Reduction for Defective Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997)

(a) This clause shall become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for the submission of cost or pricing data at FAR 15.403-4(a)(1), except that this clause does not apply to a modification if an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(b) If any price, including profit, negotiated in connection with any modification under this clause, was increased by any significant amount because

(1) the Contractor or a subcontractor furnished cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Current Cost or Pricing Data;

(2) a subcontractor or prospective subcontractor furnished the Contractor cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data; or

(3) any of these parties furnished data of any description that were not accurate, the price shall be reduced accordingly and the contract shall be modified to reflect the reduction. This right to a price reduction is limited to that resulting from defects in data relating to modifications for which this clause becomes operative under paragraph (a) above.

(c) Any reduction in the contract price under paragraph (b) above due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which:

(1) the actual subcontract; or

(2) the actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective cost or pricing data.

(d) If the Contracting Officer determines under paragraph (b) of this clause that a price or cost reduction should be made:

(1) the Contractor agrees not to raise the following matters as a defense:

- (i) The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current cost or pricing data had been submitted;
- (ii) The Contracting Officer should have known that the cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer;
- (iii) The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract; or
- (iv) The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.

(2) Except as prohibited by subdivision (d)(2)(ii) of this clause:

(i) an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if:

(A) The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the cost or pricing data were available before the date of agreement on the price of the contract (or price of the modification) and that the data were not submitted before such date.

(ii) An offset shall not be allowed if:

(A) The understated data was known by the Contractor to be understated when the Certificate of Current Cost or Pricing Data was signed; or (B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the available data had been submitted before the date of agreement on price.

(e) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid:

(1) Simple interest on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and

(2) A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted cost or pricing data which were incomplete, inaccurate, or noncurrent.

(End of clause)

52.214-28 Subcontractor Cost or Pricing Data - Modifications - Sealed Bidding. (OCT 1997)

(a) The requirements of paragraphs (b) and (c) of this clause shall:

(1) become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at (FAR) 48 CFR 15.403-4(a)(1); and

(2) be limited to such modifications.

(b) Before awarding any subcontract expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), on the date of agreement on price or the date of award, whichever is later; or before pricing any subcontract modifications involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), the Contractor shall require the subcontractor to submit cost or pricing data (actually or by specific identification in writing), unless an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(c) The Contractor shall require the subcontractor to certify in substantially the form prescribed in subsection 15.406-2 of the Federal Acquisition Regulation that, to the best of its knowledge and belief, the data submitted under paragraph (b) above were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.

(d) The Contractor shall insert the substance of this clause, including this paragraph (d), in each subcontract that, when entered into, exceeds the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1).

(End of clause)

52.214-29 ORDER OF PRECEDENCE--SEALED BIDDING (JAN 1986)

Any inconsistency in this solicitation or contract shall be resolved by giving precedence in the following order: (a) the Schedule (excluding the specifications); (b) representations and other instructions; (c) contract clauses; (d) other documents, exhibits, and attachments; and (e) the specifications.

(End of clause)

52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2000)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern means a small business concern that represents, as part of its offer that--

(1) It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, subpart B;

(2) No material change in disadvantaged ownership and control has occurred since its certification;

(3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed \$750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(End of clause)

52.219-14 *LIMITATIONS ON SUBCONTRACTING (DEC 1996)*

(a) This clause does not apply to the unrestricted portion of a partial set-aside.

(b) By submission of an offer and execution of a contract, the Offeror/Contractor agrees that in performance of the contract in the case of a contract for--

(1) Services (except construction). At least 50 percent of the cost of contract performance incurred for personnel shall be expended for employees of the concern.

(2) Supplies (other than procurement from a nonmanufacturer of such supplies). The concern shall perform work for at least 50 percent of the cost of manufacturing the supplies, not including the cost of materials.

(3) General construction. The concern will perform at least 15 percent of the cost of the contract, not including the cost of materials, with its own employees.

(4) Construction by special trade contractors. The concern will perform at least 25 percent of the cost of the contract, not including the cost of materials, with its own employees.

52.219-18 *NOTIFICATION OF COMPETITION LIMITED TO ELIGIBLE 8(A) CONCERNS (JUN 1999)--ALTERNATE I (NOV 1989)*

(a) Offers are solicited only from small business concerns expressly certified by the Small Business Administration (SBA) for participation in the SBA's 8(a) Program and which meet the following criteria at the time of submission of offer--

(1) The Offeror is in conformance with the 8(a) support limitation set forth in its approved business plan; and

(2) The Offeror is in conformance with the Business Activity Targets set forth in its approved business plan or any remedial action directed by the SBA.

(4) The offeror's approved business plan is on the file and serviced by **all states that encompass the Memphis District: Missouri, Illinois, Kentucky, Tennessee, Mississippi and Arkansas.**

(b) By submission of its offer, the Offeror certifies that it meets all of the criteria set forth in paragraph (a) of this clause.

(c) Any award resulting from this solicitation will be made to the Small Business Administration, which will subcontract performance to the successful 8(a) offeror selected through the evaluation criteria set forth in this solicitation.

(d)(1) Agreement. A small business concern submitting an offer in its own name agrees to furnish, in performing the contract, only end items manufactured or produced by small business concerns in the United States. The term "United States" includes its territories and possessions, the Commonwealth of Puerto Rico, the trust territory of the Pacific Islands, and the District of Columbia. If this procurement is processed under simplified acquisition procedures and the total amount of this contract does not exceed \$25,000, a small business concern may furnish the product of any domestic firm. This paragraph does not apply in connection with construction or service contracts.

(c) The **contractor** will notify the **Department of the Army, Corps of Engineers' Contracting Officer** in writing immediately upon entering an agreement (either oral or written) to transfer all or part of its stock or other ownership interest to any other party.

(End of clause)

52.222-3 *Convict Labor (Aug 1996)*

The Contractor agrees not to employ in the performance of this contract any person undergoing a sentence of imprisonment which has been imposed by any court of a State, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands. This limitation, however, shall not prohibit the employment by the Contractor in the performance of this contract of persons on parole or probation to work at paid employment during the term of their sentence or persons who have been pardoned or who have served their terms. Nor shall it prohibit the employment by the Contractor in the performance of this contract of persons confined for violation of the laws of any of the States, the District of Columbia, the Commonwealth of Puerto Rico, the Virgin Islands, Guam, American Samoa, the Commonwealth of the Northern Mariana Islands, or the Trust Territory of the Pacific Islands who are authorized to work at paid employment in the community under the laws of such jurisdiction, if--

(a)(1) The worker is paid or is in an approved work training program on a voluntary basis;

(2) Representatives of local union central bodies or similar labor union organizations have been consulted;

(3) Such paid employment will not result in the displacement of employed workers, or be applied in skills, crafts, or trades in which there is a surplus of available gainful labor in the locality, or impair existing contracts for services; and

(4) The rates of pay and other conditions of employment will not be less than those paid or provided for work of a similar nature in the locality in which the work is being performed; and

(b) The Attorney General of the United States has certified that the work-release laws or regulations of the jurisdiction involved are in conformity with the requirements of Executive Order 11755, as amended by Executive Orders 12608 and 12943.

(End of clause)

52.222-4 Contract Work Hours and Safety Standards Act - Overtime Compensation. (SEP 2000)

(a) Overtime requirements. No Contractor or subcontractor employing laborers or mechanics (see Federal Acquisition Regulation 22.300) shall require or permit them to work over 40 hours in any workweek unless they are paid at least 1 and 1/2 times the basic rate of pay for each hour worked over 40 hours.

(b) Violation; liability for unpaid wages; liquidated damages. The responsible Contractor and subcontractor are liable for unpaid wages if they violate the terms in paragraph (a) of this clause. In addition, the Contractor and subcontractor are liable for liquidated damages payable to the Government. The Contracting Officer will assess liquidated damages at the rate of \$10 per affected employee for each calendar day on which the employer required or permitted the employee to work in excess of the standard workweek of 40 hours without paying overtime wages required by the Contract Work Hours and Safety Standards Act.

(c) Withholding for unpaid wages and liquidated damages. The Contracting Officer will withhold from payments due under the contract sufficient funds required to satisfy any Contractor or subcontractor liabilities for unpaid wages and liquidated damages. If amounts withheld under the contract are insufficient to satisfy Contractor or subcontractor liabilities, the Contracting Officer will withhold payments from other Federal or Federally assisted contracts held by the same Contractor that are subject to the Contract Work Hours and Safety Standards Act.

(d) Payrolls and basic records.

(1) The Contractor and its subcontractors shall maintain payrolls and basic payroll records for all laborers and mechanics working on the contract during the contract and shall make them available to the Government until 3 years after contract completion. The records shall contain the name and address of each employee, social security number, labor classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. The records need not duplicate those required for construction work by Department of Labor regulations at 29 CFR 5.5(a)(3) implementing the Davis-Bacon Act.

(2) The Contractor and its subcontractors shall allow authorized representatives of the Contracting Officer or the Department of Labor to inspect, copy, or transcribe records maintained under paragraph (d)(1) of this clause. The Contractor or subcontractor also shall allow authorized representatives of the Contracting Officer or Department of Labor to interview employees in the workplace during working hours.

(e) Subcontracts. The Contractor shall insert the provisions set forth in paragraphs (a) through (d) of this clause in subcontracts exceeding \$100,000 and require subcontractors to include these provisions in any lower tier subcontracts. The Contractor shall be responsible for compliance by any subcontractor or lower-tier subcontractor with the provisions set forth in paragraphs (a) through (d) of this clause.

(End of clause)

52.222-6 *DAVIS-BACON ACT (FEB 1995)*

(a) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (d) of this clause; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such period. Such laborers and mechanics shall be paid not less than the appropriate wage rate and fringe benefits in the wage determination for the classification of work actually performed, without regard to skill, except as provided in the clause entitled Apprentices and Trainees. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein; provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph (b) of this clause) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

(b)(1) The Contracting Officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be

classified in conformance with the wage determination. The Contracting Officer shall approve an additional classification and wage rate and fringe benefits therefor only when all the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination.

(ii) The classification is utilized in the area by the construction industry.

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the Contracting Officer agree on the classification and wage rate (including the amount designated for fringe benefits, where appropriate), a report of the action taken shall be sent by the Contracting Officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator or an authorized representative will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(3) In the event the Contractor, the laborers or mechanics to be employed in the classification, or their representatives, and the Contracting Officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the Contracting Officer shall refer the questions, including the views of all interested parties and the recommendation of the Contracting Officer, to the Administrator of the Wage and Hour Division for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits, where appropriate) determined pursuant to subparagraphs (b)(2) and (b)(3) of this clause shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(c) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(d) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program; provided, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the

Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

(End of clause)

52.222-7 WITHHOLDING OF FUNDS (FEB 1988)

The Contracting Officer shall, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same Prime Contractor, or any other Federally assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same Prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

(End of clause)

52.222-8 PAYROLLS AND BASIC RECORDS (FEB 1988)

(a) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of 3 years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made, and actual wages paid. Whenever the Secretary of Labor has found, under paragraph (d) of the clause entitled Davis-Bacon Act, that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits.

Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the

registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

(b)(1) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Contracting Officer. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph (a) of this clause. This information may be submitted in any form desired. Optional Form WH-347 (Federal Stock Number 029-005-00014-1) is available for this purpose and may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402. The Prime Contractor is responsible for the submission of copies of payrolls by all subcontractors.

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify--

(i) That the payroll for the payroll period contains the information required to be maintained under paragraph (a) of this clause and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR Part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph (b)(2) of this clause.

(4) The falsification of any of the certifications in this clause may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 3729 of Title 31 of the United States Code.

(c) The Contractor or subcontractor shall make the records required under paragraph (a) of this clause available for inspection, copying, or transcription by the Contracting Officer or authorized representatives of the Contracting Officer or the Department of Labor. The Contractor or subcontractor shall permit the Contracting Officer or representatives of the Contracting Officer or the Department of Labor to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit required records or to make them available, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment

action pursuant to 29 CFR 5.12.

(End of clause)

52.222-9 APPRENTICES AND TRAINEES (FEB 1988)

(a) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in this paragraph, shall be paid not less than the applicable wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(b) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan

approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed in the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate in the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate in the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate in the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(c) Equal employment opportunity. The utilization of apprentices, trainees, and journeymen under this clause shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

(End of clause)

52.222-10 COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988)

The Contractor shall comply with the requirements of 29 CFR Part 3, which are hereby incorporated by reference in this contract.

(End of clause)

52.222-11 SUBCONTRACTS (LABOR STANDARDS (FEB 1988))

(a) The Contractor or subcontractor shall insert in any subcontracts the clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act-Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Withholding of Funds, Subcontracts (Labor Standards), Contract Termination-Debarment, Disputes Concerning Labor Standards, Compliance with Davis-Bacon and Related Act Regulations, and Certification of Eligibility, and such other clauses as the Contracting

Officer may, by appropriate instructions, require, and also a clause requiring subcontractors to include these clauses in any lower tier subcontracts. The Prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with all the contract clauses cited in this paragraph.

(b)(1) Within 14 days after award of the contract, the Contractor shall deliver to the Contracting Officer a completed Statement and Acknowledgment Form (SF 1413) for each subcontract, including the subcontractor's signed and dated acknowledgment that the clauses set forth in paragraph (a) of this clause have been included in the subcontract.

(2) Within 14 days after the award of any subsequently awarded subcontract the Contractor shall deliver to the Contracting Officer an updated completed SF 1413 for such additional subcontract.

(End of clause)

52.222-12 CONTRACT TERMINATION--DEBARMENT (FEB 1988)

A breach of the contract clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act--Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Subcontracts (Labor Standards), Compliance with Davis-Bacon and Related Act Regulations, or Certification of Eligibility may be grounds for termination of the contract, and for debarment as a Contractor and subcontractor as provided in 29 CFR 5.12.

(End of clause)

52.222-13 COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988)

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are hereby incorporated by reference in this contract.

(End of clause)

52.222-14 *DISPUTES CONCERNING LABOR STANDARDS (FEB 1988)*

The United States Department of Labor has set forth in 29 CFR Parts 5, 6, and 7 procedures for resolving disputes concerning labor standards requirements. Such disputes shall be resolved in accordance with those procedures and not the Disputes clause of this contract. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

(End of clause)

52.222-15 *CERTIFICATION OF ELIGIBILITY (FEB 1988)*

(a) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(b) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

(c) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

(End of clause)

52.222-21 *PROHIBITION OF SEGREGATED FACILITIES (FEB 1999)*

(a) Segregated facilities, as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.

(b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.

(c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

(End of clause)

52.222-26 *EQUAL OPPORTUNITY (APR 2002)*

(a) Definition. United States, as used in this clause, means the 50 States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, the U.S. Virgin Islands, and Wake Island.

(b) If, during any 12-month period (including the 12 months preceding the award of this contract), the Contractor has been or is awarded nonexempt Federal contracts and/or subcontracts that have an aggregate value in excess of \$10,000, the Contractor shall comply with paragraphs (b)(1) through (b)(11) of this clause, except for work performed outside the United States by employees who were not recruited within the United States. Upon request, the Contractor shall provide information necessary to determine the applicability of this clause.

(1) The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. However, it shall not be a violation of this clause for the Contractor to extend a publicly announced preference in employment to Indians living on or near an Indian reservation, in connection with employment opportunities on or near an Indian reservation, as permitted by 41 CFR 60-1.5.

(2) The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, or national origin. This shall include, but not be limited to, (i) employment, (ii) upgrading, (iii) demotion, (iv) transfer, (v) recruitment or recruitment advertising, (vi) layoff or termination, (vii) rates of pay or other forms of compensation, and (viii) selection for training, including apprenticeship.

(3) The Contractor shall post in conspicuous places available to employees and applicants for employment the notices to be provided by the Contracting Officer that explain this clause.

(4) The Contractor shall, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, or national origin.

(5) The Contractor shall send, to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, the notice to be provided by the Contracting Officer advising the labor union or workers' representative of the Contractor's commitments under this clause, and post copies of the notice in conspicuous places available to employees and applicants for employment.

(6) The Contractor shall comply with Executive Order 11246, as amended, and the rules, regulations, and orders of the Secretary of Labor.

(7) The Contractor shall furnish to the contracting agency all information required by Executive Order 11246, as amended, and by the rules, regulations, and orders of the Secretary of Labor. The Contractor shall also file Standard Form 100 (EEO-1), or any successor form, as prescribed in 41 CFR part 60-1. Unless the Contractor has filed within the 12 months preceding the date of contract award, the Contractor shall, within 30 days after contract award, apply to either the regional Office of Federal Contract Compliance Programs (OFCCP) or the local office of the Equal Employment Opportunity Commission for the necessary forms.

(8) The Contractor shall permit access to its premises, during normal business hours, by the contracting agency or the OFCCP for the purpose of conducting on-site compliance evaluations and complaint investigations. The Contractor shall permit the Government to inspect and copy any books, accounts, records (including computerized records), and other material that may be relevant to the matter under investigation and pertinent to compliance with Executive Order 11246, as amended, and rules and regulations that implement the Executive Order.

(9) If the OFCCP determines that the Contractor is not in compliance with this clause or any rule, regulation, or order of the Secretary of Labor, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts, under the procedures authorized in Executive Order 11246, as amended. In addition, sanctions may be imposed and remedies invoked against the Contractor as provided in Executive Order 11246, as amended; in the rules, regulations, and orders of the Secretary of Labor; or as otherwise provided by law.

(10) The Contractor shall include the terms and conditions of subparagraphs (b)(1) through (11) of this clause in every subcontract or purchase order that is not exempted by the rules, regulations, or orders of the Secretary of Labor issued under Executive Order 11246, as amended, so that these terms and conditions will be binding upon each subcontractor or vendor.

(11) The Contractor shall take such action with respect to any subcontract or purchase order as the contracting officer may direct as a means of enforcing these terms and conditions, including sanctions for noncompliance; provided, that if the Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of any direction, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

(c) Notwithstanding any other clause in this contract, disputes relative to this clause will be

governed by the procedures in 41 CFR 60-1.1.

(End of clause)

52.222-27 AFFIRMATIVE ACTION COMPLIANCE REQUIREMENTS FOR CONSTRUCTION (FEB 1999)

(a) Definitions. "Covered area," as used in this clause, means the geographical area described in the solicitation for this contract.

"Deputy Assistant Secretary," as used in this clause, means Deputy Assistant Secretary for Federal Contract Compliance, U.S. Department of Labor, or a designee.

"Employer's identification number," as used in this clause, means the Federal Social Security number used on the employer's quarterly federal tax return, U.S. Treasury Department Form 941.

"Minority," as used in this clause, means--

(1) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).

(2) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands);

(3) Black (all persons having origins in any of the black African racial groups not of Hispanic origin); and

(4) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race).

(b) If the Contractor, or a subcontractor at any tier, subcontracts a portion of the work involving any construction trade, each such subcontract in excess of \$10,000 shall include this clause and the Notice containing the goals for minority and female participation stated in the solicitation for this contract.

(c) If the Contractor is participating in a Hometown Plan (41 CFR 60-4) approved by the U.S. Department of Labor in a covered area, either individually or through an association, its affirmative action obligations on all work in the plan area (including goals) shall comply with the plan for those trades that have unions participating in the plan. Contractors must be able to demonstrate participation in, and compliance with, the provisions of the plan. Each Contractor or subcontractor participating in an approved plan is also required to comply with its obligations under the Equal Opportunity clause, and to make a good faith effort to achieve each goal under

the plan in each trade in which it has employees. The overall good-faith performance by other Contractors or subcontractors toward a goal in an approved plan does not excuse any Contractor's or subcontractor's failure to make good-faith efforts to achieve the plan's goals.

(d) The Contractor shall implement the affirmative action procedures in subparagraphs (g)(1) through (16) of this clause. The goals stated in the solicitation for this contract are expressed as percentages of the total hours of employment and training of minority and female utilization that the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for the geographical area where that work is actually performed. The Contractor is expected to make substantially uniform progress toward its goals in each craft.

(e) Neither the terms and conditions of any collective bargaining agreement, nor the failure by a union with which the Contractor has a collective bargaining agreement, to refer minorities or women shall excuse the Contractor's obligations under this clause, Executive Order 11246, as amended, or the regulations thereunder.

(f) In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.

(g) The Contractor shall take affirmative action to ensure equal employment opportunity. The evaluation of the Contractor's compliance with this clause shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully and implement affirmative action steps at least as extensive as the following:

(1) Ensure a working environment free of harassment, intimidation, and coercion at all sites and in all facilities where the Contractor's employees are assigned to work. The Contractor, if possible, will assign two or more women to each construction project. The Contractor shall ensure that foremen, superintendents, and other onsite supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at these sites or facilities.

(2) Establish and maintain a current list of sources for minority and female recruitment. Provide written notification to minority and female recruitment sources and community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

(3) Establish and maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant, referrals of minorities or females from unions, recruitment sources, or community organizations, and the action taken with respect to each individual. If an individual was sent to the union hiring hall for referral and not referred back to

the Contractor by the union or, if referred back, not employed by the Contractor, this shall be documented in the file, along with whatever additional actions the Contractor may have taken.

(4) Immediately notify the Deputy Assistant Secretary when the union or unions with which the Contractor has a collective bargaining agreement has not referred back to the Contractor a minority or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

(5) Develop on-the-job training opportunities and/or participate in training programs for the area that expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under subparagraph (g)(2) of this clause.

(6) Disseminate the Contractor's equal employment policy by--

(i) Providing notice of the policy to unions and to training, recruitment, and outreach programs, and requesting their cooperation in assisting the Contractor in meeting its contract obligations;

(ii) Including the policy in any policy manual and in collective bargaining agreements;

(iii) Publicizing the policy in the company newspaper, annual report, etc.;

(iv) Reviewing the policy with all management personnel and with all minority and female employees at least once a year; and

(v) Posting the policy on bulletin boards accessible to employees at each location where construction work is performed.

(7) Review, at least annually, the Contractor's equal employment policy and affirmative action obligations with all employees having responsibility for hiring, assignment, layoff, termination, or other employment decisions. Conduct review of this policy with all on-site supervisory personnel before initiating construction work at a job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

(8) Disseminate the Contractor's equal employment policy externally by including it in any advertising in the news media, specifically including minority and female news media. Provide written notification to, and discuss this policy with, other Contractors and subcontractors with which the Contractor does or anticipates doing business.

(9) Direct recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than 1 month before the date for acceptance of applications for apprenticeship or

training by any recruitment source, send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

(10) Encourage present minority and female employees to recruit minority persons and women. Where reasonable, provide after-school, summer, and vacation employment to minority and female youth both on the site and in other areas of the Contractor's workforce.

(11) Validate all tests and other selection requirements where required under 41 CFR 60-3.

(12) Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities. Encourage these employees to seek or to prepare for, through appropriate training, etc., opportunities for promotion.

(13) Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment-related activities to ensure that the Contractor's obligations under this contract are being carried out.

(14) Ensure that all facilities and company activities are nonsegregated except that separate or single-user rest rooms and necessary dressing or sleeping areas shall be provided to assure privacy between the sexes.

(15) Maintain a record of solicitations for subcontracts for minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

(16) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's equal employment policy and affirmative action obligations.

(h) The Contractor is encouraged to participate in voluntary associations that may assist in fulfilling one or more of the affirmative action obligations contained in subparagraphs (g)(1) through (16) of this clause. The efforts of a contractor association, joint contractor-union, contractor-community, or similar group of which the contractor is a member and participant may be asserted as fulfilling one or more of its obligations under subparagraphs (g)(1) through (16) of this clause, provided the Contractor--

(1) Actively participates in the group;

(2) Makes every effort to ensure that the group has a positive impact on the employment of minorities and women in the industry;

(3) Ensures that concrete benefits of the program are reflected in the Contractor's minority and female workforce participation;

(4) Makes a good-faith effort to meet its individual goals and timetables; and

(5) Can provide access to documentation that demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply is the Contractor's, and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

(i) A single goal for minorities and a separate single goal for women shall be established. The Contractor is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and nonminority. Consequently, the Contractor may be in violation of Executive Order 11246, as amended, if a particular group is employed in a substantially disparate manner.

(j) The Contractor shall not use goals or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

(k) The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts under Executive Order 11246, as amended.

(l) The Contractor shall carry out such sanctions and penalties for violation of this clause and of the Equal Opportunity clause, including suspension, termination, and cancellation of existing subcontracts, as may be imposed or ordered under Executive Order 11246, as amended, and its implementing regulations, by the OFCCP. Any failure to carry out these sanctions and penalties as ordered shall be a violation of this clause and Executive Order 11246, as amended.

(m) The Contractor in fulfilling its obligations under this clause shall implement affirmative action procedures at least as extensive as those prescribed in paragraph (g) of this clause, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of Executive Order 11246, as amended, the implementing regulations, or this clause, the Deputy Assistant Secretary shall take action as prescribed in 41 CFR 60-4.8.

(n) The Contractor shall designate a responsible official to--

(1) Monitor all employment-related activity to ensure that the Contractor's equal employment policy is being carried out;

(2) Submit reports as may be required by the Government; and

(3) Keep records that shall at least include for each employee the name, address, telephone number, construction trade, union affiliation (if any), employee identification number, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, separate records are not required to be maintained.

Nothing contained herein shall be construed as a limitation upon the application of other laws that establish different standards of compliance or upon the requirements for the hiring of local

or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

(End of clause)

52.222-35 EQUAL OPPORTUNITY FOR SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Definitions. As used in this clause--

All employment openings means all positions except executive and top management, those positions that will be filled from within the Contractor's organization, and positions lasting 3 days or less. This term includes full-time employment, temporary employment of more than 3 days duration, and part-time employment.

Executive and top management means any employee--

(1) Whose primary duty consists of the management of the enterprise in which the individual is employed or of a customarily recognized department or subdivision thereof;

(2) Who customarily and regularly directs the work of two or more other employees;

(3) Who has the authority to hire or fire other employees or whose suggestions and recommendations as to the hiring or firing and as to the advancement and promotion or any other change of status of other employees will be given particular weight;

(4) Who customarily and regularly exercises discretionary powers; and

(5) Who does not devote more than 20 percent or, in the case of an employee of a retail or service establishment, who does not devote more than 40 percent of total hours of work in the work week to activities that are not directly and closely related to the performance of the work described in paragraphs (1) through (4) of this definition. This paragraph (5) does not apply in the case of an employee who is in sole charge of an establishment or a physically separated branch establishment, or who owns at least a 20 percent interest in the enterprise in which the individual is employed.

Other eligible veteran means any other veteran who served on active duty during a war or in a campaign or expedition for which a campaign badge has been authorized.

Positions that will be filled from within the Contractor's organization means employment openings for which the Contractor will give no consideration to persons outside the Contractor's

organization (including any affiliates, subsidiaries, and parent companies) and includes any openings the Contractor proposes to fill from regularly established “recall” lists. The exception does not apply to a particular opening once an employer decides to consider applicants outside of its organization.

Qualified special disabled veteran means a special disabled veteran who satisfies the requisite skill, experience, education, and other job-related requirements of the employment position such veteran holds or desires, and who, with or without reasonable accommodation, can perform the essential functions of such position.

Special disabled veteran means--

(1) A veteran who is entitled to compensation (or who but for the receipt of military retired pay would be entitled to compensation) under laws administered by the Department of Veterans Affairs for a disability--

(i) Rated at 30 percent or more; or

(ii) Rated at 10 or 20 percent in the case of a veteran who has been determined under 38 U.S.C. 3106 to have a serious employment handicap (i.e., a significant impairment of the veteran's ability to prepare for, obtain, or retain employment consistent with the veteran's abilities, aptitudes, and interests); or

(2) A person who was discharged or released from active duty because of a service-connected disability.

Veteran of the Vietnam era means a person who--

(1) Served on active duty for a period of more than 180 days and was discharged or released from active duty with other than a dishonorable discharge, if any part of such active duty occurred--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases; or

(2) Was discharged or released from active duty for a service-connected disability if any part of the active duty was performed--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases.

(b) General. (1) The Contractor shall not discriminate against the individual because the individual is a special disabled veteran, a veteran of the Vietnam era, or other eligible veteran, regarding any position for which the employee or applicant for employment is qualified. The Contractor shall take affirmative action to employ, advance in employment, and otherwise treat

qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans without discrimination based upon their disability or veterans' status in all employment practices such as--

- (i) Recruitment, advertising, and job application procedures;
- (ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff and rehiring;
- (iii) Rate of pay or any other form of compensation and changes in compensation;
- (iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;
- (v) Leaves of absence, sick leave, or any other leave;
- (vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;
- (vii) Selection and financial support for training, including apprenticeship, and on-the-job training under 38 U.S.C. 3687, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;
- (viii) Activities sponsored by the Contractor including social or recreational programs; and
- (ix) Any other term, condition, or privilege of employment.

(2) The Contractor shall comply with the rules, regulations, and relevant orders of the Secretary of Labor issued under the Vietnam Era Veterans' Readjustment Assistance Act of 1972 (the Act), as amended (38 U.S.C. 4211 and 4212).

(c) Listing openings. (1) The Contractor shall immediately list all employment openings that exist at the time of the execution of this contract and those which occur during the performance of this contract, including those not generated by this contract, and including those occurring at an establishment of the Contractor other than the one where the contract is being performed, but excluding those of independently operated corporate affiliates, at an appropriate local public employment service office of the State wherein the opening occurs. Listing employment openings with the U.S. Department of Labor's America's Job Bank shall satisfy the requirement to list jobs with the local employment service office.

(2) The Contractor shall make the listing of employment openings with the local employment service office at least concurrently with using any other recruitment source or effort and shall involve the normal obligations of placing a bona fide job order, including accepting referrals of veterans and nonveterans. This listing of employment openings does not require hiring any particular job applicant or hiring from any particular group of job applicants and is not intended

to relieve the Contractor from any requirements of Executive orders or regulations concerning nondiscrimination in employment.

(3) Whenever the Contractor becomes contractually bound to the listing terms of this clause, it shall advise the State public employment agency in each State where it has establishments of the name and location of each hiring location in the State. As long as the Contractor is contractually bound to these terms and has so advised the State agency, it need not advise the State agency of subsequent contracts. The Contractor may advise the State agency when it is no longer bound by this contract clause.

(d) Applicability. This clause does not apply to the listing of employment openings that occur and are filled outside the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, American Samoa, Guam, the Virgin Islands of the United States, and Wake Island.

(e) Postings. (1) The Contractor shall post employment notices in conspicuous places that are available to employees and applicants for employment.

(2) The employment notices shall--

(i) State the rights of applicants and employees as well as the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified employees and applicants who are special disabled veterans, veterans of the Vietnam era, and other eligible veterans; and

(ii) Be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance Programs, Department of Labor (Deputy Assistant Secretary of Labor), and provided by or through the Contracting Officer.

(3) The Contractor shall ensure that applicants or employees who are special disabled veterans are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled veteran, or may lower the posted notice so that it can be read by a person in a wheelchair).

(4) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement, or other contract understanding, that the Contractor is bound by the terms of the Act and is committed to take affirmative action to employ, and advance in employment, qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans.

(f) Noncompliance. If the Contractor does not comply with the requirements of this clause, the Government may take appropriate actions under the rules, regulations, and relevant orders of the Secretary of Labor issued pursuant to the Act.

(g) Subcontracts. The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of \$25,000 or more unless exempted by rules, regulations, or orders of the

Secretary of Labor. The Contractor shall act as specified by the Deputy Assistant Secretary of Labor to enforce the terms, including action for noncompliance.

(End of clause)

52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)

(a) General. (1) Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against any employee or applicant because of physical or mental disability. The Contractor agrees to take affirmative action to employ, advance in employment, and otherwise treat qualified individuals with disabilities without discrimination based upon their physical or mental disability in all employment practices such as--

- (i) Recruitment, advertising, and job application procedures;
- (ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff, and rehiring;
- (iii) Rates of pay or any other form of compensation and changes in compensation;
- (iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;
- (v) Leaves of absence, sick leave, or any other leave;
- (vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;
- (vii) Selection and financial support for training, including apprenticeships, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;
- (viii) Activities sponsored by the Contractor, including social or recreational programs; and
- (ix) Any other term, condition, or privilege of employment.

(2) The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Rehabilitation Act of 1973 (29 U.S.C. 793) (the Act), as amended.

(b) Postings. (1) The Contractor agrees to post employment notices stating--

(i) The Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified individuals with disabilities; and

(ii) The rights of applicants and employees.

(2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. The Contractor shall ensure that applicants and employees with disabilities are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled individual, or may lower the posted notice so that it might be read by a person in a wheelchair). The notices shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance of the U.S. Department of Labor (Deputy Assistant Secretary) and shall be provided by or through the Contracting Officer.

(3) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of Section 503 of the Act and is committed to take affirmative action to employ, and advance in employment, qualified individuals with physical or mental disabilities.

(c) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.

(d) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of \$10,000 unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

(End of clause)

52.222-37 EMPLOYMENT REPORTS ON SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on--

(1) The number of disabled veterans and the number of veterans of the Vietnam era in the workforce of the contractor by job category and hiring location; and

(2) The total number of new employees hired during the period covered by the report, and of that total, the number of disabled veterans, and the number of veterans of the Vietnam era.

(b) The above items shall be reported by completing the form entitled "Federal Contractor Veterans' Employment Report VETS-100."

(c) Reports shall be submitted no later than September 30 of each year beginning September 30, 1988.

(d) The employment activity report required by paragraph (a)(2) of this clause shall reflect total hires during the most recent 12-month period as of the ending date selected for the employment profile report required by paragraph (a)(1) of this clause. Contractors may select an ending date: (1) As of the end of any pay period during the period January through March 1st of the year the report is due, or (2) as of December 31, if the contractor has previous written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).

(e) The count of veterans reported according to paragraph (a) of this clause shall be based on voluntary disclosure. Each Contractor subject to the reporting requirements at 38 U.S.C. 4212 shall invite all disabled veterans and veterans of the Vietnam era who wish to benefit under the affirmative action program at 38 U.S.C. 4212 to identify themselves to the Contractor. The invitation shall state that the information is voluntarily provided; that the information will be kept confidential; that disclosure or refusal to provide the information will not subject the applicant or employee to any adverse treatment; and that the information will be used only in accordance with the regulations promulgated under 38 U.S.C. 4212.

(f) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order of \$10,000 or more unless exempted by rules, regulations, or orders of the Secretary.

(End of clause)

52.223-3 HAZARDOUS MATERIAL IDENTIFICATION AND MATERIAL SAFETY DATA (JAN 1997)

(a) "Hazardous material", as used in this clause, includes any material defined as hazardous under the latest version of Federal Standard No. 313 (including revisions adopted during the term of the contract).

(b) The offeror must list any hazardous material, as defined in paragraph (a) of this clause, to be delivered under this contract. The hazardous material shall be properly identified and include any applicable identification number, such as National Stock Number or Special Item Number. This information shall also be included on the Material Safety Data Sheet submitted under this contract.

Material

Identification No.

(If none,
insert "None")

(c) This list must be updated during performance of the contract whenever the Contractor determines that any other material to be delivered under this contract is hazardous.

(d) The apparently successful offeror agrees to submit, for each item as required prior to award, a Material Safety Data Sheet, meeting the requirements of 29 CFR 1910.1200(g) and the latest version of Federal Standard No. 313, for all hazardous material identified in paragraph (b) of this clause. Data shall be submitted in accordance with Federal Standard No. 313, whether or not the apparently successful offeror is the actual manufacturer of these items. Failure to submit the Material Safety Data Sheet prior to award may result in the apparently successful offeror being considered nonresponsible and ineligible for award.

(e) If, after award, there is a change in the composition of the item(s) or a revision to Federal Standard No. 313, which renders incomplete or inaccurate the data submitted under paragraph (d) of this clause, the Contractor shall promptly notify the Contracting Officer and resubmit the data.

(f) Neither the requirements of this clause nor any act or failure to act by the Government shall relieve the Contractor of any responsibility or liability for the safety of Government, Contractor, or subcontractor personnel or property.

(g) Nothing contained in this clause shall relieve the Contractor from complying with applicable Federal, State, and local laws, codes, ordinances, and regulations (including the obtaining of licenses and permits) in connection with hazardous material.

(h) The Government's rights in data furnished under this contract with respect to hazardous material are as follows:

(1) To use, duplicate and disclose any data to which this clause is applicable. The purposes of this right are to--

(i) Apprise personnel of the hazards to which they may be exposed in using, handling, packaging, transporting, or disposing of hazardous materials;

(ii) Obtain medical treatment for those affected by the material; and

(iii) Have others use, duplicate, and disclose the data for the Government for these purposes.

(2) To use, duplicate, and disclose data furnished under this clause, in accordance with subparagraph (h)(1) of this clause, in precedence over any other clause of this contract providing for rights in data.

(3) The Government is not precluded from using similar or identical data acquired from other sources.

(End of clause)

52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause --

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C. 812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of nolo contendere) or imposition of sentence, or both, by any judicial body charged with the responsibility to determine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract at which employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who has other than a minimal impact or involvement in contract performance.

"Individual" means an offeror/contractor that has no more than one employee including the offeror/contractor.

(b) The Contractor, if other than an individual, shall-- within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration--

(1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such

prohibition;

(2) Establish an ongoing drug-free awareness program to inform such employees about--

- (i) The dangers of drug abuse in the workplace;
- (ii) The Contractor's policy of maintaining a drug-free workplace;
- (iii) Any available drug counseling, rehabilitation, and employee assistance programs; and
- (iv) The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace;

(3) Provide all employees engaged in performance of the contract with a copy of the statement required by subparagraph (b)(1) of this clause;

(4) Notify such employees in writing in the statement required by subparagraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will--

- (i) Abide by the terms of the statement; and
- (ii) Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction.

(5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;

(6) Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:

- (i) Taking appropriate personnel action against such employee, up to and including termination; or
- (ii) Require such employee to satisfactorily participate in a drug abuse assistance or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and

(7) Make a good faith effort to maintain a drug-free workplace through implementation of subparagraphs (b)(1) through (b)(6) of this clause.

(c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.

(d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to suspension of contract payments, termination of the contract for default, and suspension or debarment.

(End of clause)

52.223-14 *TOXIC CHEMICAL RELEASE REPORTING (OCT 2000)*

(a) Unless otherwise exempt, the Contractor, as owner or operator of a facility used in the performance of this contract, shall file by July 1 for the prior calendar year an annual Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023(a) and (g)), and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106). The Contractor shall file, for each facility subject to the Form R filing and reporting requirements, the annual Form R throughout the life of the contract.

(b) A Contractor owned or operated facility used in the performance of this contract is exempt from the requirement to file an annual Form R if--

(1) The facility does not manufacture, process, or otherwise use any toxic chemicals listed under section 313(c) of EPCRA, 42 U.S.C. 11023(c);

(2) The facility does not have 10 or more full-time employees as specified in section 313(b)(1)(A) of EPCRA, 42 U.S.C. 11023(b)(1)(A);

(3) The facility does not meet the reporting thresholds of toxic chemicals established under of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

(4) The facility does not fall within Standard Industrial Classification Code (SIC) major groups 20 through 39 or their corresponding North American Industry Classification System (NAICS) sectors 31 through 33; or

(5) The facility is not located within any State of the United States, the District of Columbia, the Commonwealth of Puerto Rico, Guam, American Samoa, the United States Virgin Islands, the Northern Mariana Islands, or any other territory or possession over which the United States has jurisdiction.

(c) If the Contractor has certified to an exemption in accordance with one or more of the criteria in paragraph (b) of this clause, and after award of the contract circumstances change so that any of its owned or operated facilities used in the performance of this contract is no longer exempt--

(1) The Contractor shall notify the Contracting Officer; and

(2) The Contractor, as owner or operator of a facility used in the performance of this contract that is no longer exempt, shall (i) submit a Toxic Chemical Release Inventory Form (Form R) on or before July 1 for the prior calendar year during which the facility becomes eligible; and (ii) continue to file the annual Form R for the life of the contract for such facility.

(d) The Contracting Officer may terminate this contract or take other action as appropriate, if the Contractor fails to comply accurately and fully with the EPCRA and PPA toxic chemical release filing and reporting requirements.

(e) Except for acquisitions of commercial items, as defined in FAR Part 2, the Contractor shall--

(1) For competitive subcontracts expected to exceed \$100,000 (including all options), include a solicitation provision substantially the same as the provision at FAR 52.223-13, Certification of Toxic Chemical Release Reporting; and

(2) Include in any resultant subcontract exceeding \$100,000 (including all options), the substance of this clause, except this paragraph (e).

(End of clause)

52.225-9 BUY AMERICAN ACT—CONSTRUCTION MATERIALS (MAY 2002)

(a) Definitions. As used in this clause--

Component means an article, material, or supply incorporated directly into a construction material.

Construction material means an article, material, or supply brought to the construction site by the Contractor or a subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means--

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the construction material (whether or not such costs are

paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the end product.

Domestic construction material means--

(1) An unmanufactured construction material mined or produced in the United States; or

(2) A construction material manufactured in the United States, if the cost of its components mined, produced, or manufactured in the United States exceeds 50 percent of the cost of all its components. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic.

Foreign construction material means a construction material other than a domestic construction material.

United States means the 50 States and the District of Columbia, U.S. territories and possessions, Puerto Rico, the Northern Mariana Islands, and any other place subject to U.S. jurisdiction, but does not include leased bases.

(b) Domestic preference. (1) This clause implements the Buy American Act (41 U.S.C. 10a-10d) by providing a preference for domestic construction material. The Contractor shall use only domestic construction material in performing this contract, except as provided in paragraphs (b)(2) and (b)(3) of this clause.

(2) This requirement does not apply to the construction material or components listed by the Government as follows: **NONE**.

(3) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(2) of this clause if the Government determines that

(i) The cost of domestic construction material would be unreasonable. The cost of a particular domestic construction material subject to the requirements of the Buy American Act is unreasonable when the cost of such material exceeds the cost of foreign material by more than 6 percent;

(ii) The application of the restriction of the Buy American Act to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American Act. (1)(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(3) of this clause shall include adequate information for Government evaluation of the request, including--

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American Act applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(3)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American Act applies, use of foreign construction material is noncompliant with the Buy American Act.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison

Construction material description	Unit of measure	Quantity	Price (dollars)
\1\			

Item 1

Foreign construction material....

Domestic construction material...

Item 2

Foreign construction material....

Domestic construction material...

Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued).

List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.

Include other applicable supporting information.

(End of clause)

52.225-13 *RESTRICTIONS ON CERTAIN FOREIGN PURCHASES* **(JUL 2000)**

(a) The Contractor shall not acquire, for use in the performance of this contract, any supplies or services originating from sources within, or that were located in or transported from or through, countries whose products are banned from importation into the United States under regulations of the Office of Foreign Assets Control, Department of the Treasury. Those countries are Cuba, Iran, Iraq, Libya, North Korea, Sudan, the territory of Afghanistan controlled by the Taliban, and Serbia (excluding the territory of Kosovo).

(b) The Contractor shall not acquire for use in the performance of this contract any supplies or services from entities controlled by the government of Iraq.

(c) The Contractor shall insert this clause, including this paragraph (c), in all subcontracts.

(End of clause)

52.226-1 UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES (JUN 2000)

(a) Definitions. As used in this clause:

"Indian" means any person who is a member of any Indian tribe, band, group, pueblo or community that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs (BIA) in accordance with 25 U.S.C. 1452(c) and any "Native" as defined in the Alaska Native Claims Settlement Act (43 U.S.C. 1601).

"Indian organization" means the governing body of any Indian tribe or entity established or recognized by the governing body of an Indian tribe for the purposes of 25 U.S.C., chapter 17.

"Indian-owned economic enterprise" means any Indian-owned (as determined by the Secretary of the Interior) commercial, industrial, or business activity established or organized for the purpose of profit, provided that Indian ownership constitute not less than 51 percent of the enterprise.

"Indian tribe" means any Indian tribe, band, group, pueblo or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act, that is recognized by the Federal Government as eligible for services from BIA in accordance with 25 U.S.C. 1542(c).

"Interested party" means a prime contractor or an actual or prospective offeror whose direct economic interest would be affected by the award of a subcontract or by the failure to award a subcontract.

(b) The Contractor shall use its best efforts to give Indian organizations and Indian-owned economic enterprises (25 U.S.C. 1544) the maximum practicable opportunity to participate in the subcontracts it awards to the fullest extent consistent with efficient performance of its contract.

(1) The Contracting Officer and the Contractor, acting in good faith, may rely on the representation of an Indian organization or Indian-owned economic enterprise as to its eligibility, unless an interested party challenges its status or the Contracting Officer has independent reason to question that status. In the event of a challenge to the representation of a subcontractor, the Contracting Officer will refer the matter to the U.S. Department of the Interior, Bureau of Indian Affairs (BIA), Attn: Chief, Division of Contracting and Grants Administration, 1849 C Street, NW., MS 2626-MIB, Washington, DC 20240-4000.

The BIA will determine the eligibility and notify the Contracting Officer. No incentive payment will be made within 50 working days of subcontract award or while a challenge is pending. If a subcontractor is determined to be an ineligible participant, no incentive payment will be made under the Indian Incentive Program.

(2) The Contractor may request an adjustment under the Indian Incentive Program to the following:

(i) The estimated cost of a cost-type contract.

(ii) The target cost of a cost-plus-incentive-fee prime contract.

(iii) The target cost and ceiling price of a fixed-price incentive prime contract.

(iv) The price of a firm-fixed-price prime contract.

(3) The amount of the adjustment to the prime contract is 5 percent of the estimated cost, target cost, or firm-fixed-price included in the subcontract initially awarded to the Indian organization or Indian-owned economic enterprise.

(4) The Contractor has the burden of proving the amount claimed and must assert its request for an adjustment prior to completion of contract performance.

(c) The Contracting Officer, subject to the terms and conditions of the contract and the availability of funds, will authorize an incentive payment of 5 percent of the amount paid to the subcontractor. The Contracting Officer will seek funding in accordance with agency procedures.

(End of clause)

52.227-1 AUTHORIZATION AND CONSENT (JUL 1995)

(a) The Government authorizes and consents to all use and manufacture, in performing this contract or any subcontract at any tier, of any invention described in and covered by a United States patent (1) embodied in the structure or composition of any article the delivery of which is accepted by the Government under this contract or (2) used in machinery, tools, or methods whose use necessarily results from compliance by the Contractor or a subcontractor with (i) specifications or written provisions forming a part of this contract or (ii) specific written instructions given by the Contracting Officer directing the manner of performance. The entire liability to the Government for infringement of a patent of the United States shall be determined solely by the provisions of the indemnity clause, if any, included in this contract or any subcontract hereunder (including any lower-tier subcontract), and the Government assumes liability for all other infringement to the extent of the authorization and consent hereinabove granted.

(b) The Contractor agrees to include, and require inclusion of, this clause, suitably modified to identify the parties, in all subcontracts at any tier for supplies or services (including construction,

architect-engineer services, and materials, supplies, models, samples, and design or testing services expected to exceed the simplified acquisition threshold (however, omission of this clause from any subcontract, including those at or below the simplified acquisition threshold, does not affect this authorization and consent.)

(End of clause)

52.227-2 NOTICE AND ASSISTANCE REGARDING PATENT AND COPYRIGHT INFRINGEMENT (AUG 1996)

(a) The Contractor shall report to the Contracting Officer, promptly and in reasonable written detail, each notice or claim of patent or copyright infringement based on the performance of this contract of which the Contractor has knowledge.

(b) In the event of any claim or suit against the Government on account of any alleged patent or copyright infringement arising out of the performance of this contract or out of the use of any supplies furnished or work or services performed under this contract, the Contractor shall furnish to the Government, when requested by the Contracting Officer, all evidence and information in possession of the Contractor pertaining to such suit or claim. Such evidence and information shall be furnished at the expense of the Government except where the Contractor has agreed to indemnify the Government.

(f) The Contractor agrees to include, and require inclusion of, this clause in all subcontracts at any tier for supplies or services (including construction and architect-engineer subcontracts and those for material, supplies, models, samples, or design or testing services) expected to exceed the simplified acquisition threshold at (FAR) 2.101. to exceed the dollar amount set forth in 13.000 of the Federal Acquisition Regulation (FAR).

(End of clause)

52.227-4 PATENT INDEMNITY--CONSTRUCTION CONTRACTS (APR 1984)

Except as otherwise provided, the Contractor agrees to indemnify the Government and its officers, agents, and employees against liability, including costs and expenses, for infringement upon any United States patent (except a patent issued upon an application that is now or may hereafter be withheld from issue pursuant to a Secrecy Order under 35 U.S.C. 181) arising out of performing this contract or out of the use or disposal by or for the account of the Government of supplies furnished or work performed under this contract.

(End of clause)

52.228-2 *ADDITIONAL BOND SECURITY (OCT 1997)*

The Contractor shall promptly furnish additional security required to protect the Government and persons supplying labor or materials under this contract if--

- (a) Any surety upon any bond, or issuing financial institution for other security, furnished with this contract becomes unacceptable to the Government.
- (b) Any surety fails to furnish reports on its financial condition as required by the Government;
- (c) The contract price is increased so that the penal sum of any bond becomes inadequate in the opinion of the Contracting Officer; or
- (d) An irrevocable letter of credit (ILC) used as security will expire before the end of the period of required security. If the Contractor does not furnish an acceptable extension or replacement ILC, or other acceptable substitute, at least 30 days before an ILC's scheduled expiration, the Contracting officer has the right to immediately draw on the ILC.

(End of clause)

52.228-11 *PLEDGES OF ASSETS (FEB 1992)*

(a) Offerors shall obtain from each person acting as an individual surety on a bid guarantee, a performance bond, or a payment bond--

(1) Pledge of assets; and

(2) Standard Form 28, Affidavit of Individual Surety.

(b) Pledges of assets from each person acting as an individual surety shall be in the form of--

(1) Evidence of an escrow account containing cash, certificates of deposit, commercial or Government securities, or other assets described in FAR 28.203-2 (except see 28.203-2(b)(2) with respect to Government securities held in book entry form) and/or;

(2) A recorded lien on real estate. The offeror will be required to provide--

(i) Evidence of title in the form of a certificate of title prepared by a title insurance company

approved by the United States Department of Justice. This title evidence must show fee simple title vested in the surety along with any concurrent owners; whether any real estate taxes are due and payable; and any recorded encumbrances against the property, including the lien filed in favor of the Government as required by FAR 28.203-3(d);

(ii) Evidence of the amount due under any encumbrance shown in the evidence of title;

(iii) A copy of the current real estate tax assessment of the property or a current appraisal dated no earlier than 6 months prior to the date of the bond, prepared by a professional appraiser who certifies that the appraisal has been conducted in accordance with the generally accepted appraisal standards as reflected in the Uniform Standards of Professional Appraisal Practice, as promulgated by the Appraisal Foundation.

(End of clause)

52.228-12 *Prospective Subcontractor Requests for Bonds. (OCT 1995)*

In accordance with Section 806(a)(3) of Pub. L. 102-190, as amended by Sections 2091 and 8105 of Pub. L. 103-355, upon the request of a prospective subcontractor or supplier offering to furnish labor or material for the performance of this contract for which a payment bond has been furnished to the Government pursuant to the Miller Act, the Contractor shall promptly provide a copy of such payment bond to the requester.

(End of clause)

52.228-14 *IRREVOCABLE LETTER OF CREDIT (DEC 1999)*

(a) “Irrevocable letter of credit” (ILC), as used in this clause, means a written commitment by a federally insured financial institution to pay all or part of a stated amount of money, until the expiration date of the letter, upon presentation by the Government (the beneficiary) of a written demand therefor. Neither the financial institution nor the offeror/Contractor can revoke or condition the letter of credit.

(b) If the offeror intends to use an ILC in lieu of a bid bond, or to secure other types of bonds such as performance and payment bonds, the letter of credit and letter of confirmation formats in paragraphs (e) and (f) of this clause shall be used.

(c) The letter of credit shall be irrevocable, shall require presentation of no document other than a written demand and the ILC (including confirming letter, if any), shall be issued/confirmed by an acceptable federally insured financial institution as provided in paragraph (d) of this clause,

and--

(1) If used as a bid guarantee, the ILC shall expire no earlier than 60 days after the close of the bid acceptance period;

(2) If used as an alternative to corporate or individual sureties as security for a performance or payment bond, the offeror/Contractor may submit an ILC with an initial expiration date estimated to cover the entire period for which financial security is required or may submit an ILC with an initial expiration date that is a minimum period of one year from the date of issuance. The ILC shall provide that, unless the issuer provides the beneficiary written notice of non-renewal at least 60 days in advance of the current expiration date, the ILC is automatically extended without amendment for one year from the expiration date, or any future expiration date, until the period of required coverage is completed and the Contracting Officer provides the financial institution with a written statement waiving the right to payment. The period of required coverage shall be:

(i) For contracts subject to the Miller Act, the later of--

(A) One year following the expected date of final payment;

(B) For performance bonds only, until completion of any warranty period; or

(C) For payment bonds only, until resolution of all claims filed against the payment bond during the one-year period following final payment.

(ii) For contracts not subject to the Miller Act, the later of--

(A) 90 days following final payment; or

(B) For performance bonds only, until completion of any warranty period.

(d) Only federally insured financial institutions rated investment grade or higher shall issue or confirm the ILC. The offeror/Contractor shall provide the Contracting Officer a credit rating that indicates the financial institution has the required rating(s) as of the date of issuance of the ILC. Unless the financial institution issuing the ILC had letter of credit business of less than \$25 million in the past year, ILCs over \$5 million must be confirmed by another acceptable financial institution that had letter of credit business of less than \$25 million in the past year.

(e) The following format shall be used by the issuing financial institution to create an ILC:

[Issuing Financial Institution's Letterhead or Name and Address]

Issue Date _____

IRREVOCABLE LETTER OF CREDIT NO. _____

Account party's name _____

Account party's address _____

For Solicitation No. _____ (for reference only)

TO: [U.S. Government agency]

[U.S. Government agency's address]

1. We hereby establish this irrevocable and transferable Letter of Credit in your favor for one or more drawings up to United States \$ _____. This Letter of Credit is payable at [issuing financial institution's and, if any, confirming financial institution's] office at [issuing financial institution's address and, if any, confirming financial institution's address] and expires with our close of business on _____, or any automatically extended expiration date.

2. We hereby undertake to honor your or the transferee's sight draft(s) drawn on the issuing or, if any, the confirming financial institution, for all or any part of this credit if presented with this Letter of Credit and confirmation, if any, at the office specified in paragraph 1 of this Letter of Credit on or before the expiration date or any automatically extended expiration date.

3. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this Letter of Credit that it is deemed to be automatically extended without amendment for one year from the expiration date hereof, or any future expiration date, unless at least 60 days prior to any expiration date, we notify you or the transferee by registered mail, or other receipted means of delivery, that we elect not to consider this Letter of Credit renewed for any such additional period. At the time we notify you, we also agree to notify the account party (and confirming financial institution, if any) by the same means of delivery.

4. This Letter of Credit is transferable. Transfers and assignments of proceeds are to be effected without charge to either the beneficiary or the transferee/assignee of proceeds. Such transfer or assignment shall be only at the written direction of the Government (the beneficiary) in a form satisfactory to the issuing financial institution and the confirming financial institution, if any.

5. This Letter of Credit is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution, if any, otherwise state of issuing financial institution].

6. If this credit expires during an interruption of business of this financial institution as described in Article 17 of the UCP, the financial institution specifically agrees to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

[Issuing financial institution]

(f) The following format shall be used by the financial institution to confirm an ILC:

[Confirming Financial Institution's Letterhead or Name and Address]

(Date) _____

Our Letter of Credit Advice Number _____

Beneficiary: _____ [U.S. Government agency]

Issuing Financial Institution: _____

Issuing Financial Institution's LC No.: _____

Gentlemen:

1. We hereby confirm the above indicated Letter of Credit, the original of which is attached, issued by _____ [name of issuing financial institution] for drawings of up to United States dollars _____/U.S. \$_____ and expiring with our close of business on _____ [the expiration date], or any automatically extended expiration date.

2. Draft(s) drawn under the Letter of Credit and this Confirmation are payable at our office located at _____.

3. We hereby undertake to honor sight draft(s) drawn under and presented with the Letter of Credit and this Confirmation at our offices as specified herein.

4. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this confirmation that it be deemed automatically extended without amendment for one year from the expiration date hereof, or any automatically extended expiration date, unless:

(a) At least 60 days prior to any such expiration date, we shall notify the Contracting Officer, or the transferee and the issuing financial institution, by registered mail or other receipted means of delivery, that we elect not to consider this confirmation extended for any such additional period; or

(b) The issuing financial institution shall have exercised its right to notify you or the transferee, the account party, and ourselves, of its election not to extend the expiration date of the Letter of

Credit.

5. This confirmation is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution].

6. If this confirmation expires during an interruption of business of this financial institution as described in Article 17 of the UCP, we specifically agree to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

[Confirming financial institution]

(g) The following format shall be used by the Contracting Officer for a sight draft to draw on the Letter of Credit:

SIGHT DRAFT

[City, State]

(Date) _____

[Name and address of financial institution]

Pay to the order of _____ [Beneficiary Agency] _____ the sum of United States \$ _____. This draft is drawn under Irrevocable Letter of Credit No.

_____.

[Beneficiary Agency]

By: _____

(End of clause)

52.228-15 *Performance and Payment Bonds--Construction (JUL 2000)-*

(a) Definitions. As used in this clause--

Original contract price means the award price of the contract; or, for requirements contracts, the price payable for the estimated total quantity; or, for indefinite-quantity contracts, the price payable for the specified minimum quantity. Original contract price does not include the price of any options, except those options exercised at the time of contract award.

(b) Amount of required bonds. Unless the resulting contract price is \$100,000 or less, the successful offeror shall furnish performance and payment bonds to the Contracting Officer as follows:

(1) Performance bonds (Standard Form 25). The penal amount of performance bonds at the time of contract award shall be 100 percent of the original contract price.

(2) Payment Bonds (Standard Form 25-A). The penal amount of payment bonds at the time of contract award shall be 100 percent of the original contract price.

(3) Additional bond protection. (i) The Government may require additional performance and payment bond protection if the contract price is increased. The increase in protection generally will equal 100 percent of the increase in contract price.

(ii) The Government may secure the additional protection by directing the Contractor to increase the penal amount of the existing bond or to obtain an additional bond.

(c) Furnishing executed bonds. The Contractor shall furnish all executed bonds, including any necessary reinsurance agreements, to the Contracting Officer, within the time period specified in the Bid Guarantee provision of the solicitation, or otherwise specified by the Contracting Officer, but in any event, before starting work.

(d) Surety or other security for bonds. The bonds shall be in the form of firm commitment, supported by corporate sureties whose names appear on the list contained in Treasury Department Circular 570, individual sureties, or by other acceptable security such as postal money order, certified check, cashier's check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. Treasury Circular 570 is published in the Federal Register or may be obtained from the U.S. Department of Treasury, Financial Management Service, Surety Bond Branch, 401 14th Street, NW, 2nd Floor, West Wing, Washington, DC 20227.

(e) Notice of subcontractor waiver of protection (40 U.S.C. 270b(c)). Any waiver of the right to sue on the payment bond is void unless it is in writing, signed by the person whose right is waived, and executed after such person has first furnished labor or material for use in the performance of the contract.

(End of clause)

52.229-3 FEDERAL, STATE, AND LOCAL TAXES (JAN 1991)

(a) "Contract date," as used in this clause, means the date set for bid opening or, if this is a negotiated contract or a modification, the effective date of this contract or modification.

"All applicable Federal, State, and local taxes and duties," as used in this clause, means all taxes and duties, in effect on the contract date, that the taxing authority is imposing and collecting on the transactions or property covered by this contract.

"After-imposed Federal tax," as used in this clause, means any new or increased Federal excise tax or duty, or tax that was exempted or excluded on the contract date but whose exemption was later revoked or reduced during the contract period, on the transactions or property covered by this contract that the Contractor is required to pay or bear as the result of legislative, judicial, or administrative action taking effect after the contract date. It does not include social security tax or other employment taxes.

"After-relieved Federal tax," as used in this clause, means any amount of Federal excise tax or duty, except social security or other employment taxes, that would otherwise have been payable on the transactions or property covered by this contract, but which the Contractor is not required to pay or bear, or for which the Contractor obtains a refund or drawback, as the result of legislative, judicial, or administrative action taking effect after the contract date.

(b) The contract price includes all applicable Federal, State, and local taxes and duties.

(c) The contract price shall be increased by the amount of any after-imposed Federal tax, provided the Contractor warrants in writing that no amount for such newly imposed Federal excise tax or duty or rate increase was included in the contract price, as a contingency reserve or otherwise.

(d) The contract price shall be decreased by the amount of any after-relieved Federal tax.

(e) The contract price shall be decreased by the amount of any Federal excise tax or duty, except social security or other employment taxes, that the Contractor is required to pay or bear, or does not obtain a refund of, through the Contractor's fault, negligence, or failure to follow instructions of the Contracting Officer.

(f) No adjustment shall be made in the contract price under this clause unless the amount of the adjustment exceeds \$250.

(g) The Contractor shall promptly notify the Contracting Officer of all matters relating to any Federal excise tax or duty that reasonably may be expected to result in either an increase or decrease in the contract price and shall take appropriate action as the Contracting Officer directs.

(h) The Government shall, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

(End of clause)

52.229-5 TAXES--CONTRACTS PERFORMED IN U.S. POSSESSIONS OR PUERTO RICO (APR 1984)

The term "local taxes," as used in the Federal, State, and local taxes clause of this contract, includes taxes imposed by a possession of the United States or by Puerto Rico.

(End of clause)

52.232-5 PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (SEP 2002)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the

Contractor at locations other than the site also may be taken into consideration if--

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that--

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) All payments due to subcontractors and suppliers from previous payments received under the contract have been made, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

(Name)

(Title)

(Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall--

(1) Notify the Contracting Officer of such performance deficiency; and

(2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until--

(i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or

(ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as--

(1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or

(2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after--

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against

the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C. 3727 and 41 U.S.C. 15).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under subparagraph (d)(2) of this clause shall be--

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

52.232-17 INTEREST (JUNE 1996)

(a) Except as otherwise provided in this contract under a Price Reduction for Defective Cost or Pricing Data clause or a Cost Accounting Standards clause, all amounts that become payable by the Contractor to the Government under this contract (net of any applicable tax credit under the Internal Revenue Code (26 U.S.C. 1481)) shall bear simple interest from the date due until paid unless paid within 30 days of becoming due. The interest rate shall be the interest rate established by the Secretary of the Treasury as provided in Section 12 of the Contract Disputes Act of 1978 (Public Law 95-563), which is applicable to the period in which the amount becomes due, as provided in paragraph (b) of this clause, and then at the rate applicable for each six-month period as fixed by the Secretary until the amount is paid. reproduce, prepare derivative works, distribute copies to the public, and (b) Amounts shall be due at the earliest of the following dates:

(1) The date fixed under this contract.

(2) The date of the first written demand for payment consistent with this contract, including any demand resulting from a default termination.

(3) The date the Government transmits to the Contractor a proposed supplemental agreement to confirm completed negotiations establishing the amount of debt.

(4) If this contract provides for revision of prices, the date of written notice to the Contractor stating the amount of refund payable in connection with a pricing proposal or a negotiated pricing agreement not confirmed by contract modification.

(c) The interest charge made under this clause may be reduced under the procedures prescribed in 32.614-2 of the Federal Acquisition Regulation in effect on the date of this contract.

(End of clause)

52.232-23 ASSIGNMENT OF CLAIMS (JAN 1986)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 15 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

(End of clause)

52.232-27 PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (FEB 2002)

Notwithstanding any other payment terms in this contract, the Government will make invoice payments under the terms and conditions specified in this clause. The Government considers payment as being made on the day a check is dated or the date of an electronic funds transfer. Definitions of pertinent terms are set forth in sections 2.101, 32.001, and 32.902 of the Federal

Acquisition Regulation. All days referred to in this clause are calendar days, unless otherwise specified. (However, see paragraph (a)(3) concerning payments due on Saturdays, Sundays, and legal holidays.)

(a) Invoice payments--(1) Types of invoice payments. For purposes of this clause, there are several types of invoice payments that may occur under this contract, as follows:

(i) Progress payments, if provided for elsewhere in this contract, based on Contracting Officer approval of the estimated amount and value of work or services performed, including payments for reaching milestones in any project.

(A) The due date for making such payments is 14 days after the designated billing office receives a proper payment request. If the designated billing office fails to annotate the payment request with the actual date of receipt at the time of receipt, the payment due date is the 14th day after the date of the Contractor's payment request, provided the designated billing office receives a proper payment request and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) The due date for payment of any amounts retained by the Contracting Officer in accordance with the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts, is as specified in the contract or, if not specified, 30 days after approval by the Contracting Officer for release to the Contractor.

(ii) Final payments based on completion and acceptance of all work and presentation of release of all claims against the Government arising by virtue of the contract, and payments for partial deliveries that have been accepted by the Government (e.g., each separate building, public work, or other division of the contract for which the price is stated separately in the contract).

(A) The due date for making such payments is the later of the following two events:

(1) The 30th day after the designated billing office receives a proper invoice from the Contractor.

(2) The 30th day after Government acceptance of the work or services completed by the Contractor. For a final invoice when the payment amount is subject to contract settlement actions (e.g., release of claims), acceptance is deemed to occur on the effective date of the contract settlement.

(B) If the designated billing office fails to annotate the invoice with the date of actual receipt at the time of receipt, the invoice payment due date is the 30th day after the date of the Contractor's invoice, provided the designated billing office receives a proper invoice and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(2) Contractor's invoice. The Contractor shall prepare and submit invoices to the designated billing office specified in the contract. A proper invoice must include the items listed in paragraphs (a)(2)(i) through (a)(2)(xi) of this clause. If the invoice does not comply with these requirements, the designated billing office must return it within 7 days after receipt, with the

reasons why it is not a proper invoice. When computing any interest penalty owed the Contractor, the Government will take into account if the Government notifies the Contractor of an improper invoice in an untimely manner.

(i) Name and address of the Contractor.

(ii) Invoice date and invoice number. (The Contractor should date invoices as close as possible to the date of mailing or transmission.)

(iii) Contract number or other authorization for work or services performed (including order number and contract line item number).

(iv) Description of work or services performed.

(v) Delivery and payment terms (e.g., discount for prompt payment terms).

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the contract or in a proper notice of assignment).

(vii) Name (where practicable), title, phone number, and mailing address of person to notify in the event of a defective invoice.

(viii) For payments described in paragraph (a)(1)(i) of this clause, substantiation of the amounts requested and certification in accordance with the requirements of the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts.

(ix) Taxpayer Identification Number (TIN). The Contractor shall include its TIN on the invoice only if required elsewhere in this contract.

(x) Electronic funds transfer (EFT) banking information.

(A) The Contractor shall include EFT banking information on the invoice only if required elsewhere in this contract.

(B) If EFT banking information is not required to be on the invoice, in order for the invoice to be a proper invoice, the Contractor shall have submitted correct EFT banking information in accordance with the applicable solicitation provision (e.g., 52.232-38, Submission of Electronic Funds Transfer Information with Offer), contract clause (e.g., 52.232-33, Payment by Electronic Funds Transfer--Central Contractor Registration, or 52.232-34, Payment by Electronic Funds Transfer--Other Than Central Contractor Registration), or applicable agency procedures.

(C) EFT banking information is not required if the Government waived the requirement to pay by EFT.

(xi) Any other information or documentation required by the contract.

(3) Interest penalty. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if payment is not made by the due date and the conditions listed in paragraphs (a)(3)(i) through (a)(3)(iii) of this clause are met, if applicable. However, when the due date falls on a Saturday, Sunday, or legal holiday, the designated payment office may make payment on the following working day without incurring a late payment interest penalty.

(i) The designated billing office received a proper invoice.

(ii) The Government processed a receiving report or other Government documentation authorizing payment and there was no disagreement over quantity, quality, Contractor compliance with any contract term or condition, or requested progress payment amount.

(iii) In the case of a final invoice for any balance of funds due the Contractor for work or services performed, the amount was not subject to further contract settlement actions between the Government and the Contractor.

(4) Computing penalty amount. The Government will compute the interest penalty in accordance with the Office of Management and Budget prompt payment regulations at 5 CFR part 1315.

(i) For the sole purpose of computing an interest penalty that might be due the Contractor for payments described in paragraph (a)(1)(ii) of this clause, Government acceptance or approval is deemed to occur constructively on the 7th day after the Contractor has completed the work or services in accordance with the terms and conditions of the contract. If actual acceptance or approval occurs within the constructive acceptance or approval period, the Government will base the determination of an interest penalty on the actual date of acceptance or approval. Constructive acceptance or constructive approval requirements do not apply if there is a disagreement over quantity, quality, or Contractor compliance with a contract provision. These requirements also do not compel Government officials to accept work or services, approve Contractor estimates, perform contract administration functions, or make payment prior to fulfilling their responsibilities.

(ii) The prompt payment regulations at 5 CFR 1315.10(c) do not require the Government to pay interest penalties if payment delays are due to disagreement between the Government and the Contractor over the payment amount or other issues involving contract compliance, or on amounts temporarily withheld or retained in accordance with the terms of the contract. The Government and the Contractor shall resolve claims involving disputes, and any interest that may be payable in accordance with the clause at FAR 52.233-1, Disputes.

(5) Discounts for prompt payment. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if the Government takes a discount for prompt payment improperly. The Government will calculate the interest penalty in accordance with the prompt payment regulations at 5 CFR part 1315.

(6) Additional interest penalty. (i) The designated payment office will pay a penalty amount, calculated in accordance with the prompt payment regulations at 5 CFR part 1315 in addition to the interest penalty amount only if--

(A) The Government owes an interest penalty of \$1 or more;

(B) The designated payment office does not pay the interest penalty within 10 days after the date the invoice amount is paid; and

(C) The Contractor makes a written demand to the designated payment office for additional penalty payment, in accordance with paragraph (a)(6)(ii) of this clause, postmarked not later than 40 days after the date the invoice amount is paid.

(ii)(A) The Contractor shall support written demands for additional penalty payments with the following data. The Government will not request any additional data. The Contractor shall--

(1) Specifically assert that late payment interest is due under a specific invoice, and request payment of all overdue late payment interest penalty and such additional penalty as may be required;

(2) Attach a copy of the invoice on which the unpaid late payment interest was due; and

(3) State that payment of the principal has been received, including the date of receipt.

(B) If there is no postmark or the postmark is illegible--

(1) The designated payment office that receives the demand will annotate it with the date of receipt provided the demand is received on or before the 40th day after payment was made; or

(2) If the designated payment office fails to make the required annotation, the Government will determine the demand's validity based on the date the Contractor has placed on the demand, provided such date is no later than the 40th day after payment was made.

(b) Contract financing payments. If this contract provides for contract financing, the Government will make contract financing payments in accordance with the applicable contract financing clause.

(c) Subcontract clause requirements. The Contractor shall include in each subcontract for property or services (including a material supplier) for the purpose of performing this contract the following:

(1) Prompt payment for subcontractors. A payment clause that obligates the Contractor to pay the subcontractor for satisfactory performance under its subcontract not later than 7 days from receipt of payment out of such amounts as are paid to the Contractor under this contract.

(2) Interest for subcontractors. An interest penalty clause that obligates the Contractor to pay to the subcontractor an interest penalty for each payment not made in accordance with the payment clause--

(i) For the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and

(ii) Computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(3) Subcontractor clause flowdown. A clause requiring each subcontractor to use:

(i) Include a payment clause and an interest penalty clause conforming to the standards set forth in paragraphs (c)(1) and (c)(2) of this clause in each of its subcontracts; and

(ii) Require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or supplier.

(d) Subcontract clause interpretation. The clauses required by paragraph (c) of this clause shall not be construed to impair the right of the Contractor or a subcontractor at any tier to negotiate, and to include in their subcontract, provisions that--

(1) Retainage permitted. Permit the Contractor or a subcontractor to retain (without cause) a specified percentage of each progress payment otherwise due to a subcontractor for satisfactory performance under the subcontract without incurring any obligation to pay a late payment interest penalty, in accordance with terms and conditions agreed to by the parties to the subcontract, giving such recognition as the parties deem appropriate to the ability of a subcontractor to furnish a performance bond and a payment bond;

(2) Withholding permitted. Permit the Contractor or subcontractor to make a determination that part or all of the subcontractor's request for payment may be withheld in accordance with the subcontract agreement; and

(3) Withholding requirements. Permit such withholding without incurring any obligation to pay a late payment penalty if--

(i) A notice conforming to the standards of paragraph (g) of this clause previously has been furnished to the subcontractor; and

(ii) The Contractor furnishes to the Contracting Officer a copy of any notice issued by a Contractor pursuant to paragraph (d)(3)(i) of this clause.

(e) Subcontractor withholding procedures. If a Contractor, after making a request for payment to the Government but before making a payment to a subcontractor for the subcontractor's

performance covered by the payment request, discovers that all or a portion of the payment otherwise due such subcontractor is subject to withholding from the subcontractor in accordance with the subcontract agreement, then the Contractor shall--

(1) Subcontractor notice. Furnish to the subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon ascertaining the cause giving rise to a withholding, but prior to the due date for subcontractor payment;

(2) Contracting Officer notice. Furnish to the Contracting Officer, as soon as practicable, a copy of the notice furnished to the subcontractor pursuant to paragraph (e)(1) of this clause;

(3) Subcontractor progress payment reduction. Reduce the subcontractor's progress payment by an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (e)(1) of this clause;

(4) Subsequent subcontractor payment. Pay the subcontractor as soon as practicable after the correction of the identified subcontract performance deficiency, and--

(i) Make such payment within--

(A) Seven days after correction of the identified subcontract performance deficiency (unless the funds therefor must be recovered from the Government because of a reduction under paragraph (e)(5)(i)) of this clause; or

(B) Seven days after the Contractor recovers such funds from the Government; or

(ii) Incur an obligation to pay a late payment interest penalty computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty;

(5) Notice to Contracting Officer. Notify the Contracting Officer upon--

(i) Reduction of the amount of any subsequent certified application for payment; or

(ii) Payment to the subcontractor of any withheld amounts of a progress payment, specifying--

(A) The amounts withheld under paragraph (e)(1) of this clause; and

(B) The dates that such withholding began and ended; and

(6) Interest to Government. Be obligated to pay to the Government an amount equal to interest on the withheld payments (computed in the manner provided in 31 U.S.C. 3903(c)(1)), from the 8th day after receipt of the withheld amounts from the Government until--

(i) The day the identified subcontractor performance deficiency is corrected; or

(ii) The date that any subsequent payment is reduced under paragraph (e)(5)(i) of this clause.

(f) Third-party deficiency reports--(1) Withholding from subcontractor. If a Contractor, after making payment to a first-tier subcontractor, receives from a supplier or subcontractor of the first-tier subcontractor (hereafter referred to as a "second-tier subcontractor") a written notice in accordance with section 2 of the Act of August 24, 1935 (40 U.S.C. 270b, Miller Act), asserting a deficiency in such first-tier subcontractor's performance under the contract for which the Contractor may be ultimately liable, and the Contractor determines that all or a portion of future payments otherwise due such first-tier subcontractor is subject to withholding in accordance with the subcontract agreement, the Contractor may, without incurring an obligation to pay an interest penalty under paragraph (e)(6) of this clause--

(i) Furnish to the first-tier subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon making such determination; and

(ii) Withhold from the first-tier subcontractor's next available progress payment or payments an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (f)(1)(i) of this clause.

(2) Subsequent payment or interest charge. As soon as practicable, but not later than 7 days after receipt of satisfactory written notification that the identified subcontract performance deficiency has been corrected, the Contractor shall--

(i) Pay the amount withheld under paragraph (f)(1)(ii) of this clause to such first-tier subcontractor; or

(ii) Incur an obligation to pay a late payment interest penalty to such first-tier subcontractor computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(g) Written notice of subcontractor withholding. The Contractor shall issue a written notice of any withholding to a subcontractor (with a copy furnished to the Contracting Officer), specifying--

(1) The amount to be withheld;

(2) The specific causes for the withholding under the terms of the subcontract; and

(3) The remedial actions to be taken by the subcontractor in order to receive payment of the amounts withheld.

(h) Subcontractor payment entitlement. The Contractor may not request payment from the Government of any amount withheld or retained in accordance with paragraph (d) of this clause

until such time as the Contractor has determined and certified to the Contracting Officer that the subcontractor is entitled to the payment of such amount.

(i) Prime-subcontractor disputes. A dispute between the Contractor and subcontractor relating to the amount or entitlement of a subcontractor to a payment or a late payment interest penalty under a clause included in the subcontract pursuant to paragraph (c) of this clause does not constitute a dispute to which the Government is a party. The Government may not be interpleaded in any judicial or administrative proceeding involving such a dispute.

(j) Preservation of prime-subcontractor rights. Except as provided in paragraph (i) of this clause, this clause shall not limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or a subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or nonperformance by a subcontractor.

(k) Non-recourse for prime contractor interest penalty. The Contractor's obligation to pay an interest penalty to a subcontractor pursuant to the clauses included in a subcontract under paragraph (c) of this clause shall not be construed to be an obligation of the Government for such interest penalty. A cost-reimbursement claim may not include any amount for reimbursement of such interest penalty.

(l) Overpayments. If the Contractor becomes aware of a duplicate payment or that the Government has otherwise overpaid on an invoice payment, the Contractor shall immediately notify the Contracting Officer and request instructions for disposition of the overpayment.

(End of clause)

52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER— CENTRAL CONTRACTOR REGISTRATION (MAY 1999)

(a) Method of payment. (1) All payments by the Government under this contract shall be made by electronic funds transfer (EFT), except as provided in paragraph (a)(2) of this clause. As used in this clause, the term "EFT" refers to the funds transfer and may also include the payment information transfer.

(2) In the event the Government is unable to release one or more payments by EFT, the Contractor agrees to either--

(i) Accept payment by check or some other mutually agreeable method of payment; or

(ii) Request the Government to extend the payment due date until such time as the Government can make payment by EFT (but see paragraph (d) of this clause).

(b) Contractor's EFT information. The Government shall make payment to the Contractor using the EFT information contained in the Central Contractor Registration (CCR) database. In the event that the EFT information changes, the Contractor shall be responsible for providing the updated information to the CCR database.

(c) Mechanisms for EFT payment. The Government may make payment by EFT through either the Automated Clearing House (ACH) network, subject to the rules of the National Automated Clearing House Association, or the Fedwire Transfer System. The rules governing Federal payments through the ACH are contained in 31 CFR part 210.

(d) Suspension of payment. If the Contractor's EFT information in the CCR database is incorrect, then the Government need not make payment to the Contractor under this contract until correct EFT information is entered into the CCR database; and any invoice or contract financing request shall be deemed not to be a proper invoice for the purpose of prompt payment under this contract. The prompt payment terms of the contract regarding notice of an improper invoice and delays in accrual of interest penalties apply.

(e) Contractor EFT arrangements. If the Contractor has identified multiple payment receiving points (i.e., more than one remittance address and/or EFT information set) in the CCR database, and the Contractor has not notified the Government of the payment receiving point applicable to this contract, the Government shall make payment to the first payment receiving point (EFT information set or remittance address as applicable) listed in the CCR database.

(f) Liability for uncompleted or erroneous transfers. (1) If an uncompleted or erroneous transfer occurs because the Government used the Contractor's EFT information incorrectly, the Government remains responsible for--

(i) Making a correct payment;

(ii) Paying any prompt payment penalty due; and

(iii) Recovering any erroneously directed funds.

(2) If an uncompleted or erroneous transfer occurs because the Contractor's EFT information was incorrect, or was revised within 30 days of Government release of the EFT payment transaction instruction to the Federal Reserve System, and--

(i) If the funds are no longer under the control of the payment office, the Government is deemed to have made payment and the Contractor is responsible for recovery of any erroneously directed funds; or

(ii) If the funds remain under the control of the payment office, the Government shall not make payment, and the provisions of paragraph (d) of this clause shall apply.

(g) EFT and prompt payment. A payment shall be deemed to have been made in a timely manner in accordance with the prompt payment terms of this contract if, in the EFT payment transaction instruction released to the Federal Reserve System, the date specified for settlement of the payment is on or before the prompt payment due date, provided the specified payment date is a valid date under the rules of the Federal Reserve System.

(h) EFT and assignment of claims. If the Contractor assigns the proceeds of this contract as provided for in the assignment of claims terms of this contract, the Contractor shall require as a condition of any such assignment, that the assignee shall register in the CCR database and shall be paid by EFT in accordance with the terms of this clause. In all respects, the requirements of this clause shall apply to the assignee as if it were the Contractor. EFT information that shows the ultimate recipient of the transfer to be other than the Contractor, in the absence of a proper assignment of claims acceptable to the Government, is incorrect EFT information within the meaning of paragraph (d) of this clause.

(i) Liability for change of EFT information by financial agent. The Government is not liable for errors resulting from changes to EFT information made by the Contractor's financial agent.

(j) Payment information. The payment or disbursing office shall forward to the Contractor available payment information that is suitable for transmission as of the date of release of the EFT instruction to the Federal Reserve System. The Government may request the Contractor to designate a desired format and method(s) for delivery of payment information from a list of formats and methods the payment office is capable of executing. However, the Government does not guarantee that any particular format or method of delivery is available at any particular payment office and retains the latitude to use the format and delivery method most convenient to the Government. If the Government makes payment by check in accordance with paragraph (a) of this clause, the Government shall mail the payment information to the remittance address contained in the CCR database.

(End of Clause)

52.233-1 Disputes. (JUL 2002)

(a) This contract is subject to the Contract Disputes Act of 1978, as amended (41 U.S.C. 601-613).

(b) Except as provided in the Act, all disputes arising under or relating to this contract shall be resolved under this clause.

(c) Claim, as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. However, a written demand or written assertion by the Contractor seeking the payment

of money exceeding \$100,000 is not a claim under the Act until certified. A voucher, invoice, or other routine request for payment that is not in dispute when submitted is not a claim under the Act. The submission may be converted to a claim under the Act, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

(d)(1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.

(2)(i) The contractors shall provide the certification specified in subparagraph (d)(2)(iii) of this clause when submitting any claim -

(A) Exceeding \$100,000; or

(B) Regardless of the amount claimed, when using -

(1) Arbitration conducted pursuant to 5 U.S.C. 575-580; or

(2) Any other alternative means of dispute resolution (ADR) technique that the agency elects to handle in accordance with the Administrative Dispute Resolution Act (ADRA).

(ii) The certification requirement does not apply to issues in controversy that have not been submitted as all or part of a claim.

(iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am duly authorized to certify the claim on behalf of the Contractor.

(3) The certification may be executed by any person duly authorized to bind the Contractor with respect to the claim.

(e) For Contractor claims of \$100,000 or less, the Contracting Officer must, if requested in writing by the Contractor, render a decision within 60 days of the request. For Contractor-certified claims over \$100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.

(f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in the Act.

(g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use alternative dispute resolution (ADR). If the Contractor refuses an offer for ADR, the Contractor

shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the request.

(h) The Government shall pay interest on the amount found due and unpaid from (1) the date the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in (FAR) 48 CFR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.

(i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under the contract, and comply with any decision of the Contracting Officer.

(End of clause)

52.233-3 *PROTEST AFTER AWARD (AUG. 1996)*

(a) Upon receipt of a notice of protest (as defined in FAR 33.101) or a determination that a protest is likely (see FAR 33.102(d)), the Contracting Officer may, by written order to the Contractor, direct the Contractor to stop performance of the work called for by this contract. The order shall be specifically identified as a stop-work order issued under this clause. Upon receipt of the order, the Contractor shall immediately comply with its terms and take all reasonable steps to minimize the incurrence of costs allocable to the work covered by the order during the period of work stoppage. Upon receipt of the final decision in the protest, the Contracting Officer shall either--

(1) Cancel the stop-work order; or

(2) Terminate the work covered by the order as provided in the Default, or the Termination for Convenience of the Government, clause of this contract.

(b) If a stop-work order issued under this clause is canceled either before or after a final decision in the protest, the Contractor shall resume work. The Contracting Officer shall make an equitable adjustment in the delivery schedule or contract price, or both, and the contract shall be modified, in writing, accordingly, if--

(1) The stop-work order results in an increase in the time required for, or in the Contractor's cost properly allocable to, the performance of any part of this contract; and

(2) The Contractor asserts its right to an adjustment within 30 days after the end of the period of work stoppage; provided, that if the Contracting Officer decides the facts justify the action, the

Contracting Officer may receive and act upon a proposal at any time before final payment under this contract.

(c) If a stop-work order is not canceled and the work covered by the order is terminated for the convenience of the Government, the Contracting Officer shall allow reasonable costs resulting from the stop-work order in arriving at the termination settlement.

(d) If a stop-work order is not canceled and the work covered by the order is terminated for default, the Contracting Officer shall allow, by equitable adjustment or otherwise, reasonable costs resulting from the stop-work order.

(e) The Government's rights to terminate this contract at any time are not affected by action taken under this clause.

(f) If, as the result of the Contractor's intentional or negligent misstatement, misrepresentation, or miscertification, a protest related to this contract is sustained, and the Government pays costs, as provided in FAR 33.102(b)(2) or 33.104(h)(1), the Government may require the Contractor to reimburse the Government the amount of such costs. In addition to any other remedy available, and pursuant to the requirements of Subpart 32.6, the Government may collect this debt by offsetting the amount against any payment due the Contractor under any contract between the Contractor and the Government.

(End of clause)

52.236-2 *DIFFERING SITE CONDITIONS (APR 1984)*

As prescribed in 36.502, insert the following clause in solicitations and contracts when a fixed-price construction contract or a fixed-price dismantling, demolition, or removal of improvements contract is contemplated and the contract amount is expected to exceed the small purchase limitation. The Contracting Officer may insert the clause in solicitations and contracts when a fixed-price construction or a fixed-price contract for dismantling, demolition, or removal of improvements is contemplated and the contract amount is expected to be within the small purchase limitation.

(a) The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Contracting Officer of

(1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or

(2) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

(b) The Contracting Officer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

(c) No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed in (a) above for giving written notice may be extended by the Contracting Officer.

(d) No request by the Contractor for an equitable adjustment to the contract for differing site conditions shall be allowed if made after final payment under this contract.

(End of clause)

52.236-3 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)

(a) The Contractor acknowledges that it has taken steps reasonably necessary to ascertain the nature and location of the work, and that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to

(1) conditions bearing upon transportation, disposal, handling, and storage of materials;

(2) the availability of labor, water, electric power, and roads;

(3) uncertainties of weather, river stages, tides, or similar physical conditions at the site;

(4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Government, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Government.

(b) The Government assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Government. Nor does the

Government assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

(End of clause)

52.236-5 MATERIAL AND WORKMANSHIP (APR 1984)

(a) All equipment, material, and articles incorporated into the work covered by this contract shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in this contract. References in the specifications to equipment, material, articles, or patented processes by trade name, make, or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition. The Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Contracting Officer, is equal to that named in the specifications, unless otherwise specifically provided in this contract.

(b) The Contractor shall obtain the Contracting Officer's approval of the machinery and mechanical and other equipment to be incorporated into the work. When requesting approval, the Contractor shall furnish to the Contracting Officer the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the machinery and mechanical and other equipment. When required by this contract or by the Contracting Officer, the Contractor shall also obtain the Contracting Officer's approval of the material or articles which the Contractor contemplates incorporating into the work. When requesting approval, the Contractor shall provide full information concerning the material or articles. When directed to do so, the Contractor shall submit samples for approval at the Contractor's expense, with all shipping charges prepaid. Machinery, equipment, material, and articles that do not have the required approval shall be installed or used at the risk of subsequent rejection.

(c) All work under this contract shall be performed in a skillful and workmanlike manner. The Contracting Officer may require, in writing, that the Contractor remove from the work any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable.

(End of clause)

52.236-6 SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)

At all times during performance of this contract and until the work is completed and accepted,

the Contractor shall directly superintend the work or assign and have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor.

(End of clause)

52.236-7 PERMITS AND RESPONSIBILITIES (NOV 1991)

The Contractor shall, without additional expense to the Government, be responsible for obtaining any necessary licenses and permits, and for complying with any Federal, State, and municipal laws, codes, and regulations applicable to the performance of the work. The Contractor shall also be responsible for all damages to persons or property that occur as a result of the Contractor's fault or negligence. The Contractor shall also be responsible for all materials delivered and work performed until completion and acceptance of the entire work, except for any completed unit of work which may have been accepted under the contract.

(End of clause)

52.236-8 OTHER CONTRACTS (APR 1984)

The Government may undertake or award other contracts for additional work at or near the site of the work under this contract. The Contractor shall fully cooperate with the other contractors and with Government employees and shall carefully adapt scheduling and performing the work under this contract to accommodate the additional work, heeding any direction that may be provided by the Contracting Officer. The Contractor shall not commit or permit any act that will interfere with the performance of work by any other contractor or by Government employees.

(End of clause)

52.236-9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)

(a) The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract

performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.

(b) The Contractor shall protect from damage all existing improvements and utilities

(1) at or near the work site, and

(2) on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

(End of clause)

52.236-10 OPERATIONS AND STORAGE AREAS (APR 1984)

(a) The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.

(b) Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

(c) The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

(End of clause)

52.236-11 *USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)*

(a) The Government shall have the right to take possession of or use any completed or partially completed part of the work. Before taking possession of or using any work, the Contracting Officer shall furnish the Contractor a list of items of work remaining to be performed or corrected on those portions of the work that the Government intends to take possession of or use. However, failure of the Contracting Officer to list any item of work shall not relieve the Contractor of responsibility for complying with the terms of the contract. The Government's possession or use shall not be deemed an acceptance of any work under the contract.

(b) While the Government has such possession or use, the Contractor shall be relieved of the responsibility for the loss of or damage to the work resulting from the Government's possession or use, notwithstanding the terms of the clause in this contract entitled "Permits and Responsibilities." If prior possession or use by the Government delays the progress of the work or causes additional expense to the Contractor, an equitable adjustment shall be made in the contract price or the time of completion, and the contract shall be modified in writing accordingly.

(End of clause)

52.236-12 *CLEANING UP (APR 1984)*

The Contractor shall at all times keep the work area, including storage areas, free from accumulations of waste materials. Before completing the work, the Contractor shall remove from the work and premises any rubbish, tools, scaffolding, equipment, and materials that are not the property of the Government. Upon completing the work, the Contractor shall leave the work area in a clean, neat, and orderly condition satisfactory to the Contracting Officer.

(End of clause)

52.236-13 *ACCIDENT PREVENTION (NOV 1991) – ALTERNATE I (NOV 1991)*

(a) The Contractor shall provide and maintain work environments and procedures which will

(1) safeguard the public and Government personnel, property, materials, supplies, and equipment exposed to Contractor operations and activities;

(2) avoid interruptions of Government operations and delays in project completion dates; and

(3) control costs in the performance of this contract.

(b) For these purposes on contracts for construction or dismantling, demolition, or removal of improvements, the Contractor shall-

(1) Provide appropriate safety barricades, signs, and signal lights;

(2) Comply with the standards issued by the Secretary of Labor at 29 CFR Part 1926 and 29 CFR Part 1910; and

(3) Ensure that any additional measures the Contracting Officer determines to be reasonably necessary for the purposes are taken.

(g) If this contract is for construction or dismantling, demolition or removal of improvements with any Department of Defense agency or component, the Contractor shall comply with all pertinent provisions of the latest version of U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, in effect on the date of the solicitation.

(2) Whenever the Contracting Officer becomes aware of any noncompliance with these requirements or any condition which poses a serious or imminent danger to the health or safety of the public or Government personnel, the Contracting Officer shall notify the Contractor orally, with written confirmation, and request immediate initiation of corrective action. This notice, when delivered to the Contractor or the Contractor's representative at the work site, shall be deemed sufficient notice of the noncompliance and that corrective action is required. After receiving the notice, the Contractor shall immediately take corrective action. If the Contractor fails or refuses to promptly take corrective action, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall not be entitled to any equitable adjustment of the contract price or extension of the performance schedule on any stop work order issued under this clause.

(e) The Contractor shall insert this clause, including this paragraph (e), with appropriate changes in the designation of the parties, in subcontracts.

(f) Before commencing the work, the Contractor shall-

(1) Submit a written proposed plan for implementing this clause. The plan shall include an analysis of the significant hazards to life, limb, and property inherent in contract work performance and a plan for controlling these hazards; and

(2) Meet with representatives of the Contracting Officer to discuss and develop a mutual understanding relative to administration of the overall safety program.

(End of clause)

52.236-15 SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)

(a) The Contractor shall, within five days after the work commences on the contract or another period of time determined by the Contracting Officer, prepare and submit to the Contracting Officer for approval three copies of a practicable schedule showing the order in which the Contractor proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work (including acquiring materials, plant, and equipment). The schedule shall be in the form of a progress chart of suitable scale to indicate appropriately the percentage of work scheduled for completion by any given date during the period. If the Contractor fails to submit a schedule within the time prescribed, the Contracting Officer may withhold approval of progress payments until the Contractor submits the required schedule.

(b) The Contractor shall enter the actual progress on the chart as directed by the Contracting Officer, and upon doing so shall immediately deliver three copies of the annotated schedule to the Contracting Officer. If, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the Contracting Officer deems necessary to demonstrate how the approved rate of progress will be regained.

(c) Failure of the Contractor to comply with the requirements of the Contracting Officer under this clause shall be grounds for a determination by the Contracting Officer that the Contractor is not prosecuting the work with sufficient diligence to ensure completion within the time specified in the contract. Upon making this determination, the Contracting Officer may terminate the Contractor's right to proceed with the work, or any separable part of it, in accordance with the default terms of this contract.

(End of clause)

52.236-17 LAYOUT OF WORK (APR 1984)

The Contractor shall lay out its work from Government established base lines and bench marks indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at its own expense, all stakes, templates, platforms,

equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through its negligence before their removal is authorized, the Contracting Officer may replace them and deduct the expense of the replacement from any amounts due or to become due to the Contractor.

(End of clause)

52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and

for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

52.236-26 *PRECONSTRUCTION CONFERENCE (FEB 1995)*

If the Contracting Officer decides to conduct a preconstruction conference, the successful offeror will be notified and will be required to attend. The Contracting Officer's notification will include specific details regarding the date, time, and location of the conference, any need for attendance by subcontractors, and information regarding the items to be discussed.

(End of clause)

52.242-13 *BANKRUPTCY (JUL 1995)*

In the event the Contractor enters into proceedings relating to bankruptcy, whether voluntary or involuntary, the Contractor agrees to furnish, by certified mail or electronic commerce method authorized by the contract, written notification of the bankruptcy to the Contracting Officer

responsible for administering the contract. This notification shall be furnished within five days of the initiation of the proceedings relating to bankruptcy filing. This notification shall include the date on which the bankruptcy petition was filed, the identity of the court in which the bankruptcy petition was filed, and a listing of Government contract numbers and contracting offices for all Government contracts against which final payment has not been made. This obligation remains in effect until final payment under this contract.

(End of clause)

52.242-14 *SUSPENSION OF WORK (APR 1984)*

(a) The Contracting Officer may order the Contractor, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the convenience of the Government.

(b) If the performance of all or any part of the work is, for an unreasonable period of time, suspended, delayed, or interrupted (1) by an act of the Contracting Officer in the administration of this contract, or (2) by the Contracting Officer's failure to act within the time specified in this contract (or within a reasonable time if not specified), an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) necessarily caused by the unreasonable suspension, delay, or interruption, and the contract modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay, or interruption to the extent that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the Contractor, or for which an equitable adjustment is provided for or excluded under any other term or condition of this contract. (c) A claim under this clause shall not be allowed (1) for any costs incurred more than 20 days before the Contractor shall have notified the Contracting Officer in writing of the act or failure to act involved (but this requirement shall not apply as to a claim resulting from a suspension order), and (2) unless the claim, in an amount stated, is asserted in writing as soon as practicable after the termination of the suspension, delay, or interruption, but not later than the date of final payment under the contract.

(End of clause)

52.243-4 *CHANGES (AUG 1987)*

(a) The Contracting Officer may, at any time, without notice to the sureties, if any, by written order designated or indicated to be a change order, make changes in the work within the general scope of the contract, including changes--

(1) In the specifications (including drawings and designs);

(2) In the method or manner of performance of the work;

(3) In the Government-furnished facilities, equipment, materials, services, or site; or

(4) Directing acceleration in the performance of the work.

(b) Any other written or oral order (which, as used in this paragraph (b), includes direction, instruction, interpretation, or determination) from the Contracting Officer that causes a change shall be treated as a change order under this clause; provided, that the Contractor gives the Contracting Officer written notice stating

(1) the date, circumstances, and source of the order and

(2) that the Contractor regards the order as a change order.

(c) Except as provided in this clause, no order, statement, or conduct of the Contracting Officer shall be treated as a change under this clause or entitle the Contractor to an equitable adjustment.

(d) If any change under this clause causes an increase or decrease in the Contractor's cost of, or the time required for, the performance of any part of the work under this contract, whether or not changed by any such order, the Contracting Officer shall make an equitable adjustment and modify the contract in writing. However, except for an adjustment based on defective specifications, no adjustment for any change under paragraph (b) of this clause shall be made for any costs incurred more than 20 days before the Contractor gives written notice as required. In the case of defective specifications for which the Government is responsible, the equitable adjustment shall include any increased cost reasonably incurred by the Contractor in attempting to comply with the defective specifications.

(e) The Contractor must assert its right to an adjustment under this clause within 30 days after

(1) receipt of a written change order under paragraph (a) of this clause or (2) the furnishing of a written notice under paragraph (b) of this clause, by submitting to the Contracting Officer a written statement describing the general nature and amount of the proposal, unless this period is extended by the Government. The statement of proposal for adjustment may be included in the notice under paragraph (b) above.

(f) No proposal by the Contractor for an equitable adjustment shall be allowed if asserted after final payment under this contract.

(End of clause)

52.244-6 SUBCONTRACTS FOR COMMERCIAL ITEMS (MAY 2002)

(a) Definitions.

"Commercial item", has the meaning contained in the clause at 52.202-1, Definitions.

"Subcontract", includes a transfer of commercial items between divisions, subsidiaries, or affiliates of the Contractor or subcontractor at any tier.

(b) To the maximum extent practicable, the Contractor shall incorporate, and require its subcontractors at all tiers to incorporate, commercial items or nondevelopmental items as components of items to be supplied under this contract.

(c) (1) The Contractor shall insert the following clauses in subcontracts for commercial items:

(i) 52.219-8, Utilization of Small Business Concerns (OCT 2000) (15 U.S.C. 637(d)(2) and (3)), in all subcontracts that offer further subcontracting opportunities. If the subcontract (except subcontracts to small business concerns) exceeds \$500,000 (\$1,000,000 for construction of any public facility), the subcontractor must include 52.219-8 in lower tier subcontracts that offer subcontracting opportunities.

(ii) 52.222-26, Equal Opportunity (Apr 2002) (E.O. 11246).

(iii) 52.222-35, Equal Opportunity for Special Disabled Veterans, Veterans of the Vietnam Era and Other Eligible Veterans (DEC 2001) (38 U.S.C. 4212(a)).

(iv) 52.222-36, Affirmative Action for Workers with Disabilities (JUN 1998) (29 U.S.C. 793).

(v) 52.247-64, Preference for Privately Owned U.S.-Flag Commercial Vessels (JUN 2000) (46 U.S.C. Appx 1241) (flowdown not required for subcontracts awarded beginning May 1, 1996).

(2) While not required, the Contractor may flow down to subcontracts for commercial items a minimal number of additional clauses necessary to satisfy its contractual obligations.

(d) The Contractor shall include the terms of this clause, including this paragraph (d), in subcontracts awarded under this contract.

(End of clause)

52.245-2 GOVERNMENT PROPERTY (FIXED-PRICE CONTRACTS) (DEC 1989)

(a) Government-furnished property. (1) The Government shall deliver to the Contractor, for use in connection with and under the terms of this contract, the Government-furnished property described in the Schedule or specifications together with any related data and information that the Contractor may request and is reasonably required for the intended use of the property (hereinafter referred to as "Government-furnished property").

(2) The delivery or performance dates for this contract are based upon the expectation that Government-furnished property suitable for use (except for property furnished "as is") will be delivered to the Contractor at the times stated in the Schedule or, if not so stated, in sufficient time to enable the Contractor to meet the contract's delivery or performance dates.

(3) If Government-furnished property is received by the Contractor in a condition not suitable for the intended use, the Contractor shall, upon receipt of it, notify the Contracting Officer, detailing the facts, and, as directed by the Contracting Officer and at Government expense, either repair, modify, return, or otherwise dispose of the property. After completing the directed action and upon written request of the Contractor, the Contracting Officer shall make an equitable adjustment as provided in paragraph (h) of this clause.

(4) If Government-furnished property is not delivered to the Contractor by the required time, the Contracting Officer shall, upon the Contractor's timely written request, make a determination of the delay, if any, caused the Contractor and shall make an equitable adjustment in accordance with paragraph (h) of this clause.

(b) Changes in Government-furnished property. (1) The Contracting Officer may, by written notice, (i) decrease the Government-furnished property provided or to be provided under this contract, or (ii) substitute other Government-furnished property for the property to be provided by the Government, or to be acquired by the Contractor for the Government, under this contract. The Contractor shall promptly take such action as the Contracting Officer may direct regarding the removal, shipment, or disposal of the property covered by such notice.

(2) Upon the Contractor's written request, the Contracting Officer shall make an equitable adjustment to the contract in accordance with paragraph (h) of this clause, if the Government has agreed in the Schedule to make the property available for performing this contract and there is any--

(i) Decrease or substitution in this property pursuant to subparagraph (b)(1) of this clause; or

(ii) Withdrawal of authority to use this property, if provided under any other contract or lease.

(c) Title in Government property. (1) The Government shall retain title to all Government-furnished property.

(2) All Government-furnished property and all property acquired by the Contractor, title to which vests in the Government under this paragraph (collectively referred to as "Government property"), are subject to the provisions of this clause. However, special tooling accountable to this contract is subject to the provisions of the Special Tooling clause and is not subject to the

provisions of this clause. Title to Government property shall not be affected by its incorporation into or attachment to any property not owned by the Government, nor shall Government property become a fixture or lose its identity as personal property by being attached to any real property.

(3) Title to each item of facilities and special test equipment acquired by the Contractor for the Government under this contract shall pass to and vest in the Government when its use in performing this contract commences or when the Government has paid for it, whichever is earlier, whether or not title previously vested in the Government.

(4) If this contract contains a provision directing the Contractor to purchase material for which the Government will reimburse the Contractor as a direct item of cost under this contract--

(i) Title to material purchased from a vendor shall pass to and vest in the Government upon the vendor's delivery of such material; and

(ii) Title to all other material shall pass to and vest in the Government upon--

(A) Issuance of the material for use in contract performance;

(B) Commencement of processing of the material or its use in contract performance; or

(C) Reimbursement of the cost of the material by the Government, whichever occurs first.

(d) Use of Government property. The Government property shall be used only for performing this contract, unless otherwise provided in this contract or approved by the Contracting Officer.

(e) Property administration. (1) The Contractor shall be responsible and accountable for all Government property provided under this contract and shall comply with Federal Acquisition Regulation (FAR) Subpart 45.5, as in effect on the date of this contract.

(2) The Contractor shall establish and maintain a program for the use, maintenance, repair, protection, and preservation of Government property in accordance with sound industrial practice and the applicable provisions of Subpart 45.5 of the FAR.

(3) If damage occurs to Government property, the risk of which has been assumed by the Government under this contract, the Government shall replace the items or the Contractor shall make such repairs as the Government directs. However, if the Contractor cannot effect such repairs within the time required, the Contractor shall dispose of the property as directed by the Contracting Officer. When any property for which the Government is responsible is replaced or repaired, the Contracting Officer shall make an equitable adjustment in accordance with paragraph (h) of this clause.

(4) The Contractor represents that the contract price does not include any amount for repairs or replacement for which the Government is responsible. Repair or replacement of property for which the Contractor is responsible shall be accomplished by the Contractor at its own expense.

(f) Access. The Government and all its designees shall have access at all reasonable times to the premises in which any Government property is located for the purpose of inspecting the Government property.

(g) Risk of loss. Unless otherwise provided in this contract, the Contractor assumes the risk of, and shall be responsible for, any loss or destruction of, or damage to, Government property upon its delivery to the Contractor or upon passage of title to the Government under paragraph (c) of this clause. However, the Contractor is not responsible for reasonable wear and tear to Government property or for Government property properly consumed in performing this contract.

(h) Equitable adjustment. When this clause specifies an equitable adjustment, it shall be made to any affected contract provision in accordance with the procedures of the Changes clause. When appropriate, the Contracting Officer may initiate an equitable adjustment in favor of the Government. The right to an equitable adjustment shall be the Contractor's exclusive remedy. The Government shall not be liable to suit for breach of contract for--

- (1) Any delay in delivery of Government-furnished property;
- (2) Delivery of Government-furnished property in a condition not suitable for its intended use;
- (3) A decrease in or substitution of Government-furnished property; or
- (4) Failure to repair or replace Government property for which the Government is responsible.

(i) Final accounting and disposition of Government property. Upon completing this contract, or at such earlier dates as may be fixed by the Contracting Officer, the Contractor shall submit, in a form acceptable to the Contracting Officer, inventory schedules covering all items of Government property (including any resulting scrap) not consumed in performing this contract or delivered to the Government. The Contractor shall prepare for shipment, deliver f.o.b. origin, or dispose of the Government property as may be directed or authorized by the Contracting Officer. The net proceeds of any such disposal shall be credited to the contract price or shall be paid to the Government as the Contracting Officer directs.

(j) Abandonment and restoration of Contractor's premises. Unless otherwise provided herein, the Government--

- (1) May abandon any Government property in place, at which time all obligations of the Government regarding such abandoned property shall cease; and
- (2) Has no obligation to restore or rehabilitate the Contractor's premises under any circumstances (e.g., abandonment, disposition upon completion of need, or upon contract completion). However, if the Government-furnished property (listed in the Schedule or specifications) is withdrawn or is unsuitable for the intended use, or if other Government property is substituted, then the equitable adjustment under paragraph (h) of this clause may properly include restoration or rehabilitation costs.

(k) Communications. All communications under this clause shall be in writing.

(l) Overseas contracts. If this contract is to be performed outside of the United States of America, its territories, or possessions, the words "Government" and "Government-furnished" (wherever they appear in this clause) shall be construed as "United States Government" and "United States Government-furnished," respectively.

(End of clause)

**52.245-4 GOVERNMENT-FURNISHED PROPERTY (SHORT FORM)
(APR 1984)**

(a) The Government shall deliver to the Contractor, at the time and locations stated in this contract, the Government-furnished property described in the Schedule or specifications. If that property, suitable for its intended use, is not delivered to the Contractor, the Contracting Officer shall equitably adjust affected provisions of this contract in accordance with the Changes clause when--

(1) The Contractor submits a timely written request for an equitable adjustment; and

(2) The facts warrant an equitable adjustment.

(b) Title to Government-furnished property shall remain in the Government. The Contractor shall use the Government-furnished property only in connection with this contract. The Contractor shall maintain adequate property control records in accordance with sound industrial practice and will make such records available for Government inspection at all reasonable times, unless the clause at Federal Acquisition Regulation 52.245-1, Property Records, is included in this contract.

(c) Upon delivery of Government-furnished property to the Contractor, the Contractor assumes the risk and responsibility for its loss or damage, except--

(1) For reasonable wear and tear;

(2) To the extent property is consumed in performing this contract; or

(3) As otherwise provided for by the provisions of this contract.

(d) Upon completing this contract, the Contractor shall follow the instructions of the Contracting Officer regarding the disposition of all Government-furnished property not consumed in performing this contract or previously delivered to the Government. The Contractor shall prepare for shipment, deliver f.o.b. origin, or dispose of the Government property, as may be directed or

authorized by the Contracting Officer. The net proceeds of any such disposal shall be credited to the contract price or shall be paid to the Government as directed by the Contracting Officer.

(e) If this contract is to be performed outside the United States of America, its territories, or possessions, the words "Government" and "Government-furnished" (wherever they appear in this clause) shall be construed as "United States Government" and "United States Government-furnished," respectively.

(End of clause)

52.246-12 INSPECTION OF CONSTRUCTION (AUG 1996)

(a) Definition. "Work" includes, but is not limited to, materials, workmanship, and manufacture and fabrication of components.

(b) The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the work performed under the contract conforms to contract requirements. The Contractor shall maintain complete inspection records and make them available to the Government. All work shall be conducted under the general direction of the Contracting Officer and is subject to Government inspection and test at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the contract.

(c) Government inspections and tests are for the sole benefit of the Government and do not--

(1) Relieve the Contractor of responsibility for providing adequate quality control measures;

(2) Relieve the Contractor of responsibility for damage to or loss of the material before acceptance;

(3) Constitute or imply acceptance; or

(4) Affect the continuing rights of the Government after acceptance of the completed work under paragraph (i) of this section.

(d) The presence or absence of a Government inspector does not relieve the Contractor from any contract requirement, nor is the inspector authorized to change any term or condition of the specification without the Contracting Officer's written authorization.

(e) The Contractor shall promptly furnish, at no increase in contract price, all facilities, labor, and material reasonably needed for performing such safe and convenient inspections and tests as may be required by the Contracting Officer. The Government may charge to the Contractor any additional cost of inspection or test when work is not ready at the time specified by the Contractor for inspection or test, or when prior rejection makes reinspection or retest necessary.

The Government shall perform all inspections and tests in a manner that will not unnecessarily delay the work. Special, full size, and performance tests shall be performed as described in the contract.

(f) The Contractor shall, without charge, replace or correct work found by the Government not to conform to contract requirements, unless in the public interest the Government consents to accept the work with an appropriate adjustment in contract price. The Contractor shall promptly segregate and remove rejected material from the premises.

(g) If the Contractor does not promptly replace or correct rejected work, the Government may (1) by contract or otherwise, replace or correct the work and charge the cost to the Contractor or (2) terminate for default the Contractor's right to proceed.

(h) If, before acceptance of the entire work, the Government decides to examine already completed work by removing it or tearing it out, the Contractor, on request, shall promptly furnish all necessary facilities, labor, and material. If the work is found to be defective or nonconforming in any material respect due to the fault of the Contractor or its subcontractors, the Contractor shall defray the expenses of the examination and of satisfactory reconstruction. However, if the work is found to meet contract requirements, the Contracting Officer shall make an equitable adjustment for the additional services involved in the examination and reconstruction, including, if completion of the work was thereby delayed, an extension of time.

(i) Unless otherwise specified in the contract, the Government shall accept, as promptly as practicable after completion and inspection, all work required by the contract or that portion of the work the Contracting Officer determines can be accepted separately. Acceptance shall be final and conclusive except for latent defects, fraud, gross mistakes amounting to fraud, or the Government's rights under any warranty or guarantee.

(End of clause)

52.246-13 INSPECTION--DISMANTLING, DEMOLITION, OR REMOVAL OF IMPROVEMENTS (AUG 1996)

(a) Unless otherwise designated by the specifications, all workmanship performed under the contract is subject to Government inspection at all times and places where dismantling or demolition work is being performed. The Contractor shall furnish promptly, and at no increase in contract price all reasonable facilities, labor, and materials necessary for safe and convenient inspection by the Government. The Government shall perform inspections in a manner that will not unduly delay the work.

(b) The Contractor is responsible for damage to property caused by defective workmanship. The Contractor shall promptly segregate and remove from the premises any unsatisfactory facilities, materials, and equipment used in contract performance, and promptly replace them with

satisfactory items. If the Contractor fails to proceed at once in a workmanlike manner with performance of the work or with the correction of defective workmanship, the Government may (1) by contract or otherwise, replace the facilities, materials, and equipment or correct the workmanship and charge the cost to the Contractor and (2) terminate for default the Contractor's right to proceed. The Contractor and any surety shall be liable, to the extent specified in the contract for any damage or cost of repair or replacement.

(End of clause)

52.247-34 F.O.B. DESTINATION (NOV 1991)

(a) The term "f.o.b. destination," as used in this clause, means--

(1) Free of expense to the Government, on board the carrier's conveyance, at a specified delivery point where the consignee's facility (plant, warehouse, store, lot, or other location to which shipment can be made) is located; and

(2) Supplies shall be delivered to the destination consignee's wharf (if destination is a port city and supplies are for export), warehouse unloading platform, or receiving dock, at the expense of the Contractor. The Government shall not be liable for any delivery, storage, demurrage, accessorial, or other charges involved before the actual delivery (or "constructive placement" as defined in carrier tariffs) of the supplies to the destination, unless such charges are caused by an act or order of the Government acting in its contractual capacity. If rail carrier is used, supplies shall be delivered to the specified unloading platform of the consignee. If motor carrier (including "piggyback") is used, supplies shall be delivered to truck tailgate at the unloading platform of the consignee, except when the supplies delivered meet the requirements of Item 568 of the National Motor Freight Classification for "heavy or bulky freight." When supplies meeting the requirements of the referenced Item 568 are delivered, unloading (including movement to the tailgate) shall be performed by the consignee, with assistance from the truck driver, if requested. If the contractor uses rail carrier or freight forwarded for less than carload shipments, the contractor shall ensure that the carrier will furnish tailgate delivery, when required, if transfer to truck is required to complete delivery to consignee.

(b) The Contractor shall--

(1)(i) Pack and mark the shipment to comply with contract specifications; or

(ii) In the absence of specifications, prepare the shipment in conformance with carrier requirements;

(2) Prepare and distribute commercial bills of lading;

(3) Deliver the shipment in good order and condition to the point of delivery specified in the contract;

(4) Be responsible for any loss of and/or damage to the goods occurring before receipt of the shipment by the consignee at the delivery point specified in the contract;

(5) Furnish a delivery schedule and designate the mode of delivering carrier; and

(6) Pay and bear all charges to the specified point of delivery.

(End of clause)

52.248-3 VALUE ENGINEERING--CONSTRUCTION (FEB 2000)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) below.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

"Collateral savings," as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

"Contractor's development and implementation costs," as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

"Government costs," as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

"Instant contract savings," as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) below).

"Value engineering change proposal (VECP)" means a proposal that--

(1) Requires a change to this, the instant contract, to implement; and

(2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change--

(i) In deliverable end item quantities only; or

(ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in subparagraphs (1) through (7) below. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

(1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

(2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

(3) A separate, detailed cost estimate for

(i) the affected portions of the existing contract requirement and

(ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) below.

(4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

(5) A prediction of any effects the proposed change would have on collateral costs to the agency.

(6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

(7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it shall not be liable for any delay in acting upon a VECP.

If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing.

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by

(i) 45 percent for fixed-price contracts or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to--

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or estimated cost, at the time the VECP is accepted, or \$100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of \$50,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) above, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

"These data, furnished under the Value Engineering-- Construction clause of contract , shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations." If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in Part 27 of the Federal Acquisition Regulation.)

(End of clause)

52.249-2 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (SEP 1996) - ALTERNATE I (SEP 1996)

(a) The Government may terminate performance of work under this contract in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of any delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

(2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.

- (3) Terminate all subcontracts to the extent they relate to the work terminated.
- (4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.
- (5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.
- (6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract had been completed, would be required to be furnished to the Government.
- (7) Complete performance of the work not terminated.
- (8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.
- (9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.
- (c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.
- (d) After expiration of the plant clearance period as defined in Subpart 45.6 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored, within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid or remaining to be paid because of the termination. The amount may include a reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (g) or paragraph (g) of this clause, exclusive of costs shown in subparagraph (g)(3) of this clause, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be modified, and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and Contracting Officer fail to agree on the whole amount to be paid the Contractor because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined as follows, but without duplication of any amounts agreed upon under paragraph (f) of this clause:

(1) For contract work performed before the effective date of termination, the total (without duplication of any items) of--

(i) The cost of this work;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract if not included in subdivision (g)(1)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(1)(i) of this clause, determined by the Contracting Officer under 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the settlement to reflect the indicated rate of loss.

(2) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Storage, transportation, and other costs incurred, reasonably necessary for the preservation, protection, or disposition of the termination inventory.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value, as determined by the Contracting Officer, of property that is destroyed, lost, stolen, or damaged so as to become undeliverable to the Government or to a buyer.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal or request for equitable adjustment within the time provided in paragraph (e) or (l), respectively, and failed to request a time extension, there is no right of appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against costs incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate

established by the Secretary of the Treasury under 50 U.S.C. App. 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office, at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

(End of clause)

52.249-3 *TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (DISMANTLING, DEMOLITION, OR REMOVAL OF IMPROVEMENTS) (SEP 1996)*

(a) The Government may terminate performance of work under this contract, in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date. Upon receipt of the notice, if title to property is vested in the Contractor under this contract, it shall revert in the Government regardless of any other clause of this contract, except for property that the Contractor disposed of by bona fide sale or removed from the site.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

(2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.

(3) Terminate all subcontracts to the extent they relate to the work terminated.

(4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.

(5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.

(6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract has been completed, would be required to be furnished to the Government.

(7) Complete performance of the work not terminated.

(8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.

(9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.

(c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.

(d) After expiration of the plant clearance period as defined in Subpart 45.6 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored, within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request

of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid because of the termination. The amount may include a reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (f) or paragraph (g) of this clause, exclusive of settlement costs, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be amended and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and the Contracting Officer fail to agree on the whole amount to be paid because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined by the Contracting Officer as follows, but without duplication of any amounts agreed on under paragraph (f) of this clause:

(1) For contract work performed before the effective date of termination, the total (without duplication of any items) of--

(i) The cost of this work;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract, if not included in subdivision (g)(1)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(1)(i) of this clause, determined by the Contracting Officer under section 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the amount of the settlement to reflect the indicated rate of loss.

(2) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Preservation and protection of property under subparagraph (b)(8) of this clause.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value as determined by the Contracting Officer, of property that is destroyed, lost, stolen, or damaged so as to become undeliverable to the Government or to a buyer.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal within the time provided in paragraph (e) or (l) and failed to request a time extension, there is no right of appeal. If the Contracting Officer has made a determination of the amount due under paragraph (e), (g), or (l) of this clause, the Government shall pay the Contractor (1) the amount determined by the Contracting Officer, if there is no right of appeal or if no timely appeal has been taken, or (2) the amount finally determined on an appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against cost incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate established by the Secretary of the Treasury under 50 U.S.C. App 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction

in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office, at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

(End of clause)

52.249-10 *DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)*

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if--

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include

(i) acts of God or of the public enemy,

(ii) acts of the Government in either its sovereign or contractual capacity,

(iii) acts of another Contractor in the performance of a contract with the Government,

(iv) fires,

(v) floods,

(vi) epidemics,

(vii) quarantine restrictions,

(viii) strikes,

(ix) freight embargoes,

(x) unusually severe weather, or delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.252-2 CLAUSES INCORPORATED BY REFERENCE (FEB 1998)

This contract incorporates one or more clauses by reference, with the same force and effect as if they were given in full text. Upon request, the Contracting Officer will make their full text available. Also, the full text of a clause may be accessed electronically at this/these address(es):

<http://www.arnet.gov/far>

<http://farsite.hill.af.mil>

<http://www.dtic.mil/dfars>

(End of clause)

52.252-4 *ALTERATIONS IN CONTRACT (APR 1984)*

Portions of this contract are altered as follows:

N/A

(End of clause)

52.252-6 *AUTHORIZED DEVIATIONS IN CLAUSES (APR 1984)*

(a) The use in this solicitation or contract of any Federal Acquisition Regulation (48 CFR Chapter 1) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the date of the clause.

(h) The use in this solicitation or contract of any DoD FAR Supplement (48 CFR Chapter 2) clause with an authorized deviation is indicated by the addition of "(DEVIATION)" after the name of the regulation.

52.253-1 *COMPUTER GENERATED FORMS (JAN 1991)*

(a) Any data required to be submitted on a Standard or Optional Form prescribed by the Federal Acquisition Regulation (FAR) may be submitted on a computer generated version of the form, provided there is no change to the name, content, or sequence of the data elements on the form, and provided the form carries the Standard or Optional Form number and edition date.

(b) Unless prohibited by agency regulations, any data required to be submitted on an agency unique form prescribed by an agency supplement to the FAR may be submitted on a computer generated version of the form provided there is no change to the name, content, or sequence of the data elements on the form and provided the form carries the agency form number and edition date.

(i) If the Contractor submits a computer generated version of a form that is different than the required form, then the rights and obligations of the parties will be determined based on the content of the required form.

(End of clause)

252.201-7000 CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

252.203-7001 PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (MAR 1999)

(a) Definitions. As used in this clause—

(1) "Arising out of a contract with the DoD" means any act in connection with—

(i) Attempting to obtain;

(ii) Obtaining, or

(iii) Performing a contract or first-tier subcontract of any agency, department, or component of the Department of Defense (DoD).

(2) "Conviction of fraud or any other felony" means any conviction for fraud or a felony in violation of state or Federal criminal statutes, whether entered on a verdict or plea, including a plea of *nolo contendere*, for which sentence has been imposed.

(3) "Date of conviction" means the date judgment was entered against the individual.

(b) Any individual who is convicted after September 29, 1988, of fraud or any other felony arising out of a contract with the DoD is prohibited from serving--

(1) In a management or supervisory capacity on any DoD contract or first-tier subcontract;

(2) On the board of directors of any DoD contractor or first-tier subcontractor;

(3) As a consultant, agent, or representative for any DoD contractor or first-tier subcontractor; or

(4) In any other capacity with the authority to influence, advise, or control the decisions of any DoD contractor or subcontractor with regard to any DoD contract or first-tier subcontract.

(c) Unless waived, the prohibition in paragraph (b) of this clause applies for not less than 5 years from the date of conviction.

(d) 10 U.S.C. 2408 provides that a defense contractor or first-tier subcontractor shall be subject to a criminal penalty of not more than \$500,000 if convicted of knowingly—

(1) Employing a person under a prohibition specified in paragraph (b) of this clause; or

(2) Allowing such a person to serve on the board of directors of the contractor or first-tier subcontractor.

(e) In addition to the criminal penalties contained in 10 U.S.C. 2408, the Government may consider other available remedies, such as—

(1) Suspension or debarment;

(2) Cancellation of the contract at no cost to the Government; or

(3) Termination of the contract for default.

(f) The Contractor may submit written requests for waiver of the prohibition in paragraph (b) of this clause to the Contracting Officer. Requests shall clearly identify—

(1) The person involved;

(2) The nature of the conviction and resultant sentence or punishment imposed;

(3) The reasons for the requested waiver; and

(4) An explanation of why a waiver is in the interest of national security.

(g) The Contractor agrees to include the substance of this clause, appropriately modified to reflect the identity and relationship of the parties, in all first-tier subcontracts exceeding the simplified acquisition threshold in Part 2 of the Federal Acquisition Regulation, except those for commercial items or components.

(h) Pursuant to 10 U.S.C. 2408(c), defense contractors and subcontractors may obtain information as to whether a particular person has been convicted of fraud or any other felony arising out of a contract with the DoD by contacting The Office of Justice Programs, The Denial of Federal Benefits Office, U.S. Department of Justice, telephone (202) 616-3507.

(End of clause)

**252.204-7003 CONTROL OF GOVERNMENT PERSONNEL WORK
PRODUCT (APR 1992)**

The Contractor's procedures for protecting against unauthorized disclosure of information shall not require Department of Defense employees or members of the Armed Forces to relinquish control of their work products, whether classified or not, to the contractor.

(End of clause)

**252.204-7004 REQUIRED CENTRAL CONTRACTOR REGISTRATION
(NOV 2001)**

(a) Definitions.

As used in this clause--

(1) Central Contractor Registration (CCR) database means the primary DoD repository for contractor information required for the conduct of business with DoD.

(2) Data Universal Numbering System (DUNS) number means the 9-digit number assigned by Dun and Bradstreet Information Services to identify unique business entities.

(3) Data Universal Numbering System +4 (DUNS+4) number means the DUNS number assigned by Dun and Bradstreet plus a 4-digit suffix that may be assigned by a parent (controlling) business concern. This 4-digit suffix may be assigned at the discretion of the parent business concern for such purposes as identifying subunits or affiliates of the parent business concern.

(4) Registered in the CCR database means that all mandatory information, including the DUNS number or the DUNS+4 number, if applicable, and the corresponding Commercial and Government Entity (CAGE) code, is in the CCR database; the DUNS number and the CAGE code have been validated; and all edits have been successfully completed.

(b)(1) By submission of an offer, the offeror acknowledges the requirement that a prospective awardee must be registered in the CCR database prior to award, during performance, and through final payment of any contract resulting from this solicitation, except for awards to foreign vendors for work to be performed outside the United States.

(2) The offeror shall provide its DUNS or, if applicable, its DUNS+4 number with its offer, which will be used by the Contracting Officer to verify that the offeror is registered in the CCR database.

(3) Lack of registration in the CCR database will make an offeror ineligible for award.

(4) DoD has established a goal of registering an applicant in the CCR database within 48 hours after receipt of a complete and accurate application via the Internet. However, registration of an applicant submitting an application through a method other than the Internet may take up to 30 days. Therefore, offerors that are not registered should consider applying for registration immediately upon receipt of this solicitation.

(c) The Contractor is responsible for the accuracy and completeness of the data within the CCR, and for any liability resulting from the Government's reliance on inaccurate or incomplete data. To remain registered in the CCR database after the initial registration, the Contractor is required to confirm on an annual basis that its information in the CCR database is accurate and complete.

(d) Offerors and contractors may obtain information on registration and annual confirmation requirements by calling 1-888-227-2423, or via the Internet at <http://www.ccr.gov>.

(End of clause)

252.209-7000 ACQUISITION FROM SUBCONTRACTORS SUBJECT TO ONSITE INSPECTION UNDER THE INTERMEDIATE-RANGE NUCLEAR FORCES (INF) TREATY (NOV 1995)

(a) The Contractor shall not deny consideration for a subcontract award under this contract to a potential subcontractor subject to on-site inspection under the INF Treaty, or a similar treaty, solely or in part because of the actual or potential presence of Soviet inspectors at the subcontractor's facility, unless the decision is approved by the Contracting Officer.

(b) The Contractor shall incorporate this clause, including this paragraph (b), in all solicitations and contracts exceeding the simplified acquisition threshold in part 13 of the Federal Acquisition Regulation, except those for commercial items.

(End of clause)

252.209-7004 SUBCONTRACTING WITH FIRMS THAT ARE OWNED OR CONTROLLED BY THE GOVERNMENT OF A TERRORIST COUNTRY (MAR 1998)

(a) Unless the Government determines that there is a compelling reason to do so, the Contractor shall not enter into any subcontract in excess of \$25,000 with a firm, or subsidiary of a firm, that is identified, on the List of Parties Excluded from Federal Procurement and Nonprocurement

Programs, as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a terrorist country.

(b) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is identified, on the List of Parties Excluded from Federal Procurement and Nonprocurement Programs, as being ineligible for the award of Defense contracts or subcontracts because it is owned or controlled by the government of a terrorist country. The notice must include the name of the proposed subcontractor notwithstanding its inclusion on the List of Parties Excluded From Federal Procurement and Nonprocurement Programs.

(End of clause)

252.219-7009 *SECTION 8(A) DIRECT AWARD (MAR 2002)*

(a) This contract is issued as a direct award between the contracting office and the 8(a) Contractor pursuant to the Partnership Agreement dated February 1, 2002, between the Small Business Administration (SBA) and the Department of Defense. Accordingly, the SBA, even if not identified in Section A of this contract, is the prime contractor and retains responsibility for 8(a) certification, for 8(a) eligibility determinations and related issues, and for providing counseling and assistance to the 8(a) Contractor under the 8(a) Program. The cognizant SBA district office is:

(To be completed by the Contracting Officer at the time of award)

(b) The contracting office is responsible for administering the contract and for taking any action on behalf of the Government under the terms and conditions of the contract; provided that the contracting office shall give advance notice to the SBA before it issues a final notice terminating performance, either in whole or in part, under the contract. The contracting office also shall coordinate with the SBA prior to processing any novation agreement. The contracting office may assign contract administration functions to a contract administration office.

(c) The Contractor agrees that--

(1) It will notify the Contracting Officer, simultaneous with its notification to the SBA (as required by SBA's 8(a) regulations at 13 CFR 124.308), when the owner or owners upon whom 8(a) eligibility is based plan to relinquish ownership or control of the concern. Consistent with Section 407 of Pub. L. 100-656, transfer of ownership or control shall result in termination of the contract for convenience, unless the SBA waives the requirement for termination prior to the actual relinquishing of ownership and control; and

(2) It will not subcontract the performance of any of the requirements of this contract without the prior written approval of the SBA and the Contracting Officer.

(End of Clause)

252.223-7001 HAZARD WARNING LABELS (DEC 1991)

(a) "Hazardous material," as used in this clause, is defined in the Hazardous Material Identification and Material Safety Data clause of this contract.

(b) The Contractor shall label the item package (unit container) of any hazardous material to be delivered under this contract in accordance with the Hazard Communication Standard (29 CFR 1910.1200 et seq). The Standard requires that the hazard warning label conform to the requirements of the standard unless the material is otherwise subject to the labeling requirements of one of the following statutes:

(1) Federal Insecticide, Fungicide and Rodenticide Act;

(2) Federal Food, Drug and Cosmetics Act;

(3) Consumer Product Safety Act;

(4) Federal Hazardous Substances Act; or

(5) Federal Alcohol Administration Act.

(c) The Offeror shall list which hazardous material listed in the Hazardous Material Identification and Material Safety Data clause of this contract will be labeled in accordance with one of the Acts in paragraphs (b)(1) through

(5) of this clause instead of the Hazard Communication Standard. Any hazardous material not listed will be interpreted to mean that a label is required in accordance with the Hazard Communication Standard.

MATERIAL (If None, Insert "None.")

ACT

(d) The apparently successful Offeror agrees to submit, before award, a copy of the hazard warning label for all hazardous materials not listed in paragraph (c) of this clause. The Offeror shall submit the label with the Material Safety Data Sheet being furnished under the Hazardous Material Identification and Material Safety Data clause of this contract.

(e) The Contractor shall also comply with MIL-STD-129, Marking for Shipment and Storage (including revisions adopted during the term of this contract).

(End of clause)

252.223-7004 *DRUG-FREE WORK FORCE (SEP 1988)*

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources,

and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2.1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.225-7012 Preference for Certain Domestic Commodities (FEB 2003)

(a) Definitions. As used in this clause--

(1) Component means any item supplied to the Government as part of an end product or of another component.

(2) End product means supplies delivered under a line item of this contract.

(b) The Contractor shall deliver under this contract only such of the following items, either as end products or components, that have been grown, reprocessed, reused, or produced in the United States, its possessions, or Puerto Rico:

(1) Food.

(2) Clothing.

(3) Tents, tarpaulins, or covers.

(4) Cotton and other natural fiber products.

(5) Woven silk or woven silk blends.

(6) Spun silk yarn for cartridge cloth.

(7) Synthetic fabric, and coated synthetic fabric, including all textile fibers and yarns that are for use in such fabrics.

(8) Canvas products.

(9) Wool (whether in the form of fiber or yarn or contained in fabrics, materials, or manufactured articles).

(10) Any item of individual equipment (Federal Supply Class 8465) manufactured from or containing fibers, yarns, fabrics, or materials listed in this paragraph (b).

(c) This clause does not apply--

(1) To items listed in section 25.104(a) of the Federal Acquisition Regulation (FAR), or other items for which the Government has determined that a satisfactory quality and sufficient quantity cannot be acquired as and when needed at U.S. market prices;

(2) To end products incidentally incorporating cotton, other natural fibers, or wool, for which the estimated value of the cotton, other natural fibers, or wool--

(i) Is not more than 10 percent of the total price of the end product; and (ii) Does not exceed the simplified acquisition threshold in FAR part 2;

(3) To foods that have been manufactured or processed in the United States, its possessions, or Puerto Rico, regardless of where the foods (and any component if applicable) were grown or produced, except that this clause does apply to fish, shellfish, or seafood manufactured or processed in the United States and fish, shellfish, or seafood contained in foods manufactured or processed in the United States;

(4) To chemical warfare protective clothing produced in the countries listed in subsection 225.872-1 of the Defense FAR Supplement; or

(5) To fibers and yarns that are for use in synthetic fabric or coated synthetic fabric (but does apply to the synthetic or coated synthetic fabric itself), if--

(i) The fabric is to be used as a component of an end product that is not a textile product. Examples of textile products, made in whole or in part of fabric, include--

(A) Draperies, floor coverings, furnishings, and bedding (Federal Supply Group 72, Household and Commercial Furnishings and Appliances);

(B) Items made in whole or in part of fabric in Federal Supply Group 83, Textile/leather/furs/apparel/findings/ tents/flags, or Federal Supply Group 84, Clothing, Individual Equipment and Insignia;

(C) Upholstered seats (whether for household, office, or other use); and

(D) Parachutes (Federal Supply Class 1670); or

(ii) The fibers and yarns are para-aramid fibers and yarns manufactured in the Netherlands.

(End of clause)

252.225-7031 *SECONDARY ARAB BOYCOTT OF ISRAEL (JUN 1992)*

(a) Definitions. As used in this clause--

(1) "Foreign person" means any person other than a United States person as defined in Section 16(2) of the Export Administration Act of 1979 (50 U.S.C. App. Sec 2415).

(2) "United States person" is defined in Section 16(2) of the Export Administration Act of 1979 and means any United States resident or national (other than an individual resident outside the United States and employed by other than a United States person), any domestic concern (including any permanent domestic establishment of any foreign concern), and any foreign subsidiary or affiliate (including any permanent foreign establishment) of any domestic concern which is controlled in fact by such domestic concerns, as determined under regulations of the President.

(b) Certification. By submitting this offer, the Offeror, if a foreign person, company or entity, certifies that it--

(1) Does not comply with the Secondary Arab Boycott of Israel; and

(2) Is not taking or knowingly agreeing to take any action, with respect to the Secondary Boycott of Israel by Arab countries, which 50 U.S.C. App. Sec 2407(a) prohibits a United States person from taking.

(End of clause)

252.227-7033 *RIGHTS IN SHOP DRAWINGS (APR 1966)*

(a) Shop drawings for construction means drawings, submitted to the Government by the Construction Contractor, subcontractor or any lower-tier subcontractor pursuant to a construction contract, showing in detail (i) the proposed fabrication and assembly of structural elements and (ii) the installation (i.e., form, fit, and attachment details) of materials or equipment. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(b) This clause, including this paragraph (b), shall be included in all subcontracts hereunder at any tier.

252.231-7000 *SUPPLEMENTAL COST PRINCIPLES (DEC 1991)*

When the allowability of costs under this contract is determined in accordance with part 31 of the Federal Acquisition Regulation (FAR), allowability shall also be determined in accordance with part 231 of the Defense FAR Supplement, in effect on the date of this contract.

(End of clause)

252.236-7000 *MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)*

(a) The Contractor shall furnish a price breakdown, itemized as required and within the time specified by the Contracting Officer, with any proposal for a contract modification.

(b) The price breakdown --

(1) Must include sufficient detail to permit an analysis of profit, and of all costs for --

(i) Material;

- (ii) Labor;
 - (iii) Equipment;
 - (iv) Subcontracts; and
 - (v) Overhead; and
- (2) Must cover all work involved in the modification, whether the work was deleted, added, or changed.
- (c) The Contractor shall provide similar price breakdowns to support any amounts claimed for subcontracts.
- (d) The Contractor's proposal shall include a justification for any time extension proposed.

252.243-7001 *PRICING OF CONTRACT MODIFICATIONS (DEC 1991)*

When costs are a factor in any price adjustment under this contract, the contract cost principles and procedures in FAR part 31 and DFARS part 231, in effect on the date of this contract, apply.

252.247-7023 *TRANSPORTATION OF SUPPLIES BY SEA (MAY 2002)*

(a) Definitions. As used in this clause --

- (1) "Components" means articles, materials, and supplies incorporated directly into end products at any level of manufacture, fabrication, or assembly by the Contractor or any subcontractor.
- (2) "Department of Defense" (DoD) means the Army, Navy, Air Force, Marine Corps, and defense agencies.
- (3) "Foreign flag vessel" means any vessel that is not a U.S.-flag vessel.
- (4) "Ocean transportation" means any transportation aboard a ship, vessel, boat, barge, or ferry through international waters.
- (5) "Subcontractor" means a supplier, materialman, distributor, or vendor at any level below the prime contractor whose contractual obligation to perform results from, or is conditioned upon, award of the prime contract and who is performing any part of the work or other requirement of

the prime contract.

(6) "Supplies" means all property, except land and interests in land, that is clearly identifiable for eventual use by or owned by the DoD at the time of transportation by sea.

(i) An item is clearly identifiable for eventual use by the DoD if, for example, the contract documentation contains a reference to a DoD contract number or a military destination.

(ii) "Supplies" includes (but is not limited to) public works; buildings and facilities; ships; floating equipment and vessels of every character, type, and description, with parts, subassemblies, accessories, and equipment; machine tools; material; equipment; stores of all kinds; end items; construction materials; and components of the foregoing.

(7) "U.S.-flag vessel" means a vessel of the United States or belonging to the United States, including any vessel registered or having national status under the laws of the United States.

(b)(1) The Contractor shall use U.S.-flag vessels when transporting any supplies by sea under this contract.

(2) A subcontractor transporting supplies by sea under this contract shall use U.S.-flag vessels if--

(i) This contract is a construction contract; or

(ii) The supplies being transported are--

(A) Noncommercial items; or

(B) Commercial items that--

(1) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it contracts for f.o.b. destination shipment);

(2) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(3) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(c) The Contractor and its subcontractors may request that the Contracting Officer authorize shipment in foreign-flag vessels, or designate available U.S.-flag vessels, if the Contractor or a subcontractor believes that --

(1) U.S.-flag vessels are not available for timely shipment;

- (2) The freight charges are inordinately excessive or unreasonable; or
- (3) Freight charges are higher than charges to private persons for transportation of like goods.

(d) The Contractor must submit any request for use of other than U.S.-flag vessels in writing to the Contracting Officer at least 45 days prior to the sailing date necessary to meet its delivery schedules. The Contracting Officer will process requests submitted after such date(s) as expeditiously as possible, but the Contracting Officer's failure to grant approvals to meet the shipper's sailing date will not of itself constitute a compensable delay under this or any other clause of this contract. Requests shall contain at a minimum --

- (1) Type, weight, and cube of cargo;
- (2) Required shipping date;
- (3) Special handling and discharge requirements;
- (4) Loading and discharge points;
- (5) Name of shipper and consignee;
- (6) Prime contract number; and

(7) A documented description of efforts made to secure U.S.-flag vessels, including points of contact (with names and telephone numbers) with at least two U.S.-flag carriers contacted. Copies of telephone notes, telegraphic and facsimile message or letters will be sufficient for this purpose.

(e) The Contractor shall, within 30 days after each shipment covered by this clause, provide the Contracting Officer and the Maritime Administration, Office of Cargo Preference, U.S. Department of Transportation, 400 Seventh Street SW., Washington, DC 20590, one copy of the rated on board vessel operating carrier's ocean bill of lading, which shall contain the following information:

- (1) Prime contract number;
- (2) Name of vessel;
- (3) Vessel flag of registry;
- (4) Date of loading;
- (5) Port of loading;
- (6) Port of final discharge;

(7) Description of commodity;

(8) Gross weight in pounds and cubic feet if available;

(9) Total ocean freight in U.S. dollars; and

(10) Name of the steamship company.

(f) The Contractor shall provide with its final invoice under this contract a representation that to the best of its knowledge and belief--

(1) No ocean transportation was used in the performance of this contract;

(2) Ocean transportation was used and only U.S.-flag vessels were used for all ocean shipments under the contract;

(3) Ocean transportation was used, and the Contractor had the written consent of the Contracting Officer for all non-U.S.-flag ocean transportation; or

(4) Ocean transportation was used and some or all of the shipments were made on non-U.S.-flag vessels without the written consent of the Contracting Officer. The Contractor shall describe these shipments in the following format:

ITEM DESCRIPTION	CONTRACT LINE ITEMS	QUANTITY
TOTAL		

(g) If the final invoice does not include the required representation, the Government will reject and return it to the Contractor as an improper invoice for the purposes of the Prompt Payment clause of this contract. In the event there has been unauthorized use of non-U.S.-flag vessels in the performance of this contract, the Contracting Officer is entitled to equitably adjust the contract, based on the unauthorized use.

(h) In the award of subcontracts for the types of supplies described in paragraph (b)(2) of this clause, the Contractor shall flow down the requirements of this clause as follows:

(1) The Contractor shall insert the substance of this clause, including this paragraph (h), in subcontracts that exceed the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.

(2) The Contractor shall insert the substance of paragraphs (a) through (e) of this clause, and this paragraph (h), in subcontracts that are at or below the simplified acquisition threshold in part 2 of the Federal Acquisition Regulation.

(End of clause)

252.247-7024 Notification of Transportation of Supplies by Sea (MAR 2000)

(a) The Contractor has indicated by the response to the solicitation provision, Representation of Extent of Transportation by Sea, that it did not anticipate transporting by sea any supplies. If, however, after the award of this contract, the Contractor learns that supplies, as defined in the Transportation of Supplies by Sea clause of this contract, will be transported by sea, the Contractor --

(1) Shall notify the Contracting Officer of that fact; and

(2) Hereby agrees to comply with all the terms and conditions of the Transportation of Supplies by Sea clause of this contract.

(b) The Contractor shall include this clause; including this paragraph (b), revised as necessary to reflect the relationship of the contracting parties--

(1) In all subcontracts under this contract, if this contract is a construction contract; or

(2) If this contract is not a construction contract, in all subcontracts under this contract that are for--

(i) Noncommercial items; or

(ii) Commercial items that--

(A) The Contractor is reselling or distributing to the Government without adding value (generally, the Contractor does not add value to items that it subcontracts for f.o.b. destination shipment);

(B) Are shipped in direct support of U.S. military contingency operations, exercises, or forces deployed in humanitarian or peacekeeping operations; or

(C) Are commissary or exchange cargoes transported outside of the Defense Transportation System in accordance with 10 U.S.C. 2643.

(End of clause)

**AUSTIN, MISSISSIPPI
SEEPAGE RELIEF WELLS
TUNICA COUNTY, MISSISSIPPI
MISSISSIPPI RIVER AND TRIBUTARIES - CONSTRUCTION**

SECTION 00800

SPECIAL CONTRACT REQUIREMENTS

TABLE OF CONTENTS

<u>Para No.</u>	<u>Paragraph Title</u>	<u>Page No.</u>
1.1	Commencement, Prosecution, and Completion of Work	00800-1
1.2	Exclusion Periods in Computing Completion Schedules-Not Used	00800-1
1.3	Liquidated Damages-Construction	00800-1
1.4	Exception to Liquidated Damages	00800-1
1.5	Contract Drawings and Specifications	00800-1
1.6	Physical Data	00800-3
1.7	Rights-of-way	00800-3
1.8	Layout of Work	00800-4
1.9	Quantity Surveys-Not Used	00800-5
1.10	Quantity Surveys-Alternate I	00800-5
1.11	Progress Chart	00800-6
1.12	Safety-Related Special Requirements	00800-6
1.13	Basis for Settlement of Proposals	00800-9
1.14	Certificates of Compliance	00800-9
1.15	Contractor's Certificate	00800-10
1.16	Shop Drawings	00800-10
1.17	As-Built Drawings	00800-10
1.18	Damage to Work	00800-11
1.19	Notification of Area Engineer Before Beginning Work	00800-11
1.20	Equipment Ownership and Operating Expense Schedule	00800-11
1.21	Retesting of Construction Materials	00800-12
1.22	Vehicle Weight Limitations	00800-12
1.23	Obstructions	00800-12
1.24	National Pollutant Discharge Elimination System	00800-13
1.25	Performance of Work by the Contractor	00800-13
1.26	Continuing Contracts	00800-13
1.27	Acceptance Section-Not Used	00800-15

<u>Para No.</u>	<u>Paragraph Title</u>	<u>Page No.</u>
1.28	Time Extensions for Unusually Severe Weather	00800-15
1.29	Payment for Mobilization and Demobilization	00800-16
1.30	Stone Sources	00800-16
1.31	Field Office Building	00800-17
1.32	Submittals	00800-18
1.33	Haul Roads	00800-18
1.34	Temporary Project Fencing	00800-19
1.35	Maintenance of Traffic-Not Used	00800-19
1.36	Cooperation With Others-Not Used	00800-19
1.37	Hours of Work-Not Used	00800-19
1.38	Sunday, Holiday and Night Work	00800-19
1.39	Security Requirements- Not Used	00800-19
1.40	Insurance Requirements for Work on Government Property-Not Used	00800-19
1.41	Storage of Equipment and Materials	00800-19
1.42	Warranty of Construction	00800-19
1.43	Utility Services	00800-21
1.44	Commercial Warranty	00800-21
1.45	Payment for Material Stored Offsite-Not Used	00800-21
1.46	Work in Quarantined Area-Not Used	00800-21
1.47	Work on or Adjacent to Railroad Property-Not Used	00800-21
1.48	Insurance Requirements for Work on or Adjacent to Railroad Property-Not Used	00800-21
1.49	Control of Water Levels-Not Used	00800-21
1.50	Flood Emergency	00800-21
1.51	Patents Proprietary Right-Not Used	00800-22
1.52	Protection of Materials and Work-Not Used	00800-22
1.53	Existing Flood Protection	00800-22
1.54	Final Acceptance-Not Used	00800-22
1.55	Obstruction of Navigable Waterways-Not Used	00800-22
1.56	Dredge Size-Not Used	00800-22
1.57	Signal Lights-Not Used	00800-22
1.58	Inspection- Not Used	00800-22
1.59	Designated Billing Office	00800-22

**AUSTIN, MISSISSIPPI
SEEPAGE RELIEF WELLS
TUNICA COUNTY, MISSISSIPPI
MISSISSIPPI RIVER AND TRIBUTARIES - CONSTRUCTION**

SECTION 00800 - SPECIAL CONTRACT REQUIREMENTS

1.1 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984).

The Contractor shall be required to (a) commence work under this contract within 10 calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than 225 calendar days after the date of receipt by him of notice to proceed. The time stated for completion shall include final cleanup of the premises. (FAR 52.211-10)

1.2 EXCLUSION PERIODS IN COMPUTING COMPLETION SCHEDULES- NOT USED.

1.3 LIQUIDATED DAMAGES-CONSTRUCTION (SEP 2000).

a. If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of, \$555.00 for each calendar day of delay until the work is completed or accepted.

b. If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

1.4 EXCEPTION TO LIQUIDATED DAMAGES. The Contractor's obligations specified in the requirements of SECTION 02936 are exempt from liquidated damages.

1.5 CONTRACT DRAWINGS AND SPECIFICATIONS (AUG 2000).

a. The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

b. The Contractor shall--

- (1) Check all drawings immediately upon receipt;
- (2) Compare all drawings and verify the figures before laying out the work;
- (3) Promptly notify the Contracting Officer of any discrepancies;
- (4) Be responsible for any errors that might have been avoided by complying with this paragraph b; and
- (5) Reproduce and print contract drawings and specifications as needed

c. In general—

- (1) Large-scale drawings shall govern small-scale drawings; and
- (2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

d. Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

e. The work shall conform to the specifications and the contract drawings identified on the following index of drawings:

**AUSTIN, MISSISSIPPI
SEEPAGE RELIEF WELLS
TUNICA COUNTY, MISSISSIPPI
MISSISSIPPI RIVER AND TRIBUTARIES - CONSTRUCTION**

FILE NUMBER 001a0310

INDEX TO DRAWINGS

<u>TITLE</u>	<u>DRAWING NUMBER</u>
MAPS AND INDEX	1
PLAN AND PROFILES	2
WELL TABLES, PUMP PAD, AND SUMP DETAILS	3

TYPICAL SECTIONS	4
CULVERT AND MISCELLANEOUS DETAILS	5
DETAILS FOR WELLS 1-25	6
DETAILS FOR WELLS 26-56	7
OUTLET STRUCTURE DETAILS	8
BORING LOGS	9
BORING LOGS	10
BORING LOGS	11
BORING LEGEND	12
STAGE HYDROGRAPHS	13
TEMPORARY EROSION CONTROL DEVICES	14

(DFARS 252.236-7001)

1.6 PHYSICAL DATA (APR 1984).

Data and information furnished or referred to below are for the Contractor's information. The Government shall not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.

a. Physical Conditions. The indications of physical conditions on the drawings and in the specifications are the result of site investigations by aerial photographs and topographic surveys.

b. Weather Conditions. Information with respect to temperatures and precipitation may be obtained from the National Weather Service. Also see paragraph 1.28, "Time Extensions for Unusually Severe Weather".

c. Additional Data. Additional data consisting of cross sections, river stage records, and records of borings, may be available for inspection at the U.S. Army Engineer District, Memphis, Tennessee. (FAR 52.236-4)

1.7 RIGHTS-OF-WAY.

a. The rights-of-way and easements for the work to be constructed under this contract within the limits indicated on the drawings will be provided by the Government without cost to the Contractor. However, the Contractor shall make his own arrangements with the appropriate owners or organizations for transporting his equipment across, over or under railroad tracks, highways, bridges, private property, and utility lines and shall provide at his own expense any additional right-of-way or easements required to effect such crossings, including insurance requirements of owners. Limits of right-of-way which will be provided by the Government are as indicated on the drawings.

b. The Contractor shall, upon reasonable notice, without expense to the Government and at any time during the progress of the work when not being actively used for contract operations,

promptly vacate and clean up any part of the Government grounds that have been allotted to or have been in use by him when directed to do so by the Contracting Officer.

c. The Contractor shall not obstruct any existing roads on the lands controlled by the United States except with the permission of the Contracting Officer, and shall maintain such roads in as good condition as exists at the time of commencement of the work.

d. Any additional right-of-way required for access or for the Contractor's method of operation must be obtained by and at the expense of the Contractor. The Contractor shall submit written evidence to the Contracting Officer that he has obtained the rights-of-way from the property owners. The written evidence shall consist of an authenticated copy of the conveyance under which the Contractor acquired the rights-of-way, prepared and executed in accordance with the laws of the State of Mississippi. If temporary rights are obtained by the Contractor, the period of time shall coincide with paragraph 1.1, "Commencement, Prosecution, and Completion of Work", of the SPECIAL CONTRACT REQUIREMENTS, plus a reasonable time for any extension granted for completion of the work. The Contractor shall be solely responsible for any and all damages, claims for damages, and liability of any nature whatsoever arising from or growing out of the use of rights-of-way other than those rights-of-way furnished by the Government.

e. The Contractor shall repair, at his own expense, any and all damage to the existing roads when such damage is a result of his operations on this contract. The Contractor shall also replace, at his own expense, any and all surfacing displaced or damaged by his operations on this contract. The repairs and/or replacement shall be done to the satisfaction of the Contracting Officer.

1.8 LAYOUT OF WORK.

a. The Contractor will establish the following baselines and bench marks at the site of the work:

(1) Baselines as shown on the drawings.

(2) Bench marks as shown on the drawings.

b. From the baselines and bench marks established by the Contractor, the Contractor shall complete the layout of the work and shall be responsible for all measurements that may be required for the execution of the work to the location and limit marks prescribed in the specifications or on the contract drawings, subject to such modifications as the Contracting Officer may require to meet changed conditions or as a result of necessary modifications to the contract work.

c. The Contractor shall furnish, at his own expense, such stakes, templates, platforms, equipment, tools and materials, and all labor as may be required in laying out any part of the work from the baselines and bench marks established by the Government. It shall be the responsibility of the Contractor to maintain and preserve all stakes and marks established by the Contracting Officer until authorized to remove them, and if such marks are destroyed, by the

Contractor or through his negligence, prior to their authorized removal, they may be replaced by the Contracting Officer, at his discretion, and the expense of replacement will be deducted from any amounts due or to become due the Contractor. The Contracting Officer may require that work be suspended at any time when location and limit marks established by the Contractor are not reasonably adequate to permit checking of the work.

1.9 QUANTITY SURVEYS - NOT USED.

1.10 QUANTITY SURVEYS-ALTERNATE I (APR 1984).

a. Quantity surveys shall be conducted, and the data derived from these surveys shall be used in computing the quantities of work performed and the actual construction completed and in place.

b. The Contractor shall conduct the original and final surveys for any periods for which progress payments are requested. All these surveys shall be conducted under the direction of a representative of the Contracting Officer, unless the Contracting Officer waives this requirement in a specific instance. The Government shall make such computations as are necessary to determine the quantities of work performed or finally in place. The Contractor shall make the computations based on the surveys for any periods for which progress payments are requested.

c. Promptly upon completing a survey, the Contractor shall furnish the originals of all field notes and all other records relating to the survey or to the layout of the work to the Contracting Officer, who shall use them as necessary to determine the amount of progress payments. The Contractor shall retain copies of all such material furnished to the Contracting Officer. (FAR 52.236-16)

d. The Government shall conduct a meeting with the Contractor prior to the commencement of any work requiring quantity surveys to discuss the requirements and conditions relating to quantity surveys.

e. For periods that progress payments are requested, the Contractor shall provide the raw quantity survey data, plotted cross-sections and profiles indicating the theoretical grade and slope lines as specified by the contract drawings and the actual grade and slope lines as constructed, and quantity computations by the double end area method indicating end areas and tabulated volumes per station to verify the work in place.

f. Quantity surveys as used in this clause means a topographical survey accomplished by ground methods with the display output recorded and stored in an electronic field book for further calculations in a computer to develop a digital terrain model (DTM) at 2' contour intervals. The Contractor shall furnish to the Contracting Officer the electronic data in Microstation compatible files (DGN, ALG, DTM, and ASCII XYZ). The Contracting Officer shall disapprove any survey information submitted by the Contractor that lacks sufficient data.

g. Quantity Survey Method. The cross-section method shall be used to obtain topography. Individual cross sections will depend upon the terrain but shall not exceed 50 feet intervals. Observations shall be recorded at all breaks in slopes with a maximum distance 25 feet between observations. Annotated cross sections shall be created and included in DGN format at 1"=10'.

h. Quantity Survey Limits. After clearing of vegetation and trees, the topographic survey shall extend to 50 feet beyond the limits of work or to the Right-of-Way limits as shown on the drawings.

1.11 PROGRESS CHART. The schedule of work will be in accordance with the progress chart. The progress chart required by provisions of paragraph (a) of the CONTRACT CLAUSE entitled "Schedules for Construction Contracts" shall be prepared on ENG Form 2454, copies of which will be furnished to the Contractor by the Government. THREE COPIES OF THE SCHEDULE WILL BE REQUIRED.

1.12 SAFETY-RELATED SPECIAL REQUIREMENTS. ALL WORK UNDER THIS CONTRACT SHALL COMPLY WITH THE LATEST VERSION OF U.S. ARMY CORPS OF ENGINEERS SAFETY AND HEALTH REQUIREMENTS MANUAL, EM 385-1-1, AND OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA) STANDARDS IN EFFECT ON THE DATE OF THE SOLICITATION. NO SEPARATE PAYMENT WILL BE MADE FOR COMPLIANCE WITH EM 385-1-1, NOR FOR COMPLIANCE WITH ANY OF THE OTHER SAFETY-RELATED SPECIAL REQUIREMENTS.

a. Accident Investigations and Reporting. Refer to EM 385-1-1, Section 1. Accidents shall be investigated and reports completed by the immediate supervisor of the employee(s) involved and reported to the Contracting Officer or his/her representative immediately after the accident occurs. A report of all mishaps occurring on the project shall be submitted to the Contracting Officer on ENG Form 3394 within two working days following the incident. All data reported must be complete, timely and accurate. A follow-up report shall be submitted when the estimated lost time days differ from actual lost time days. When a job related injury occurs which requires medical treatment, a supervisor of the injured employee shall accompany the injured employee to the treatment facility and explain the employee's regular duties and the availability of "Light Duty" so the injured employee can return to work as soon as possible.

b. Accident Prevention Program. Refer to the CONTRACT CLAUSE entitled, "Accident Prevention (Alternate I)". Within 15 calendar days after receipt of Notice of Award of the contract, four copies of the Accident Prevention Program shall be submitted to the Contracting Officer for review and approval. The program shall be prepared in the following format:

(1) An executed LMV Form 358R, Administrative Plan (available upon request).

(2) An executed LMV Form 359R, Activity Hazard Analysis (available upon request).

(3) A copy of company policy statement regarding accident prevention.

(4) When marine plant and equipment are in use under a contract, the method of fuel oil transfer shall be submitted on LMV Form 414R, Fuel Oil Transfer, (available upon request). (Refer to 33 CFR 156.)

The Contractor shall not commence physical work at the site until the program has been approved by the Contracting Officer, or his authorized representative. At the Contracting Officer's discretion, the Contractor may submit his Activity Hazard Analysis for only the first phase of construction provided that it is accompanied by an outline of the remaining phases of construction. All remaining phases shall be submitted and accepted prior to the beginning of work in each phase. Also refer to Section 1 of EM 385-1-1.

c. Daily Inspections. The Contractor shall perform daily safety inspections and record them on the forms approved by the Contracting Officer. Reports of daily inspections shall be maintained at the jobsite. The reports shall be records of the daily inspections and resulting actions. Each report will include, as a minimum, the following:

(1) Phase(s) of construction underway during the inspection.

(2) Locations or areas inspections were made.

(3) Results of inspection, including nature of deficiencies observed and corrective actions taken, or to be taken, date, and signature of the person responsible for its contents.

d. Machinery and Mechanized Equipment. Machinery and mechanized equipment used under this contract shall comply with the following:

(1) When mechanized equipment is operated on floating plant, the Contractor shall provide positive and acceptable means of preventing this equipment from moving or falling into the water. The type of equipment addressed by this clause includes front-end loaders, bulldozers, trucks (both on- and off-road), backhoes, track hoes, and similar equipment. If the Contractor plans to use such equipment on floating plant, an activity hazard analysis must be developed for this feature of work. The plan must include a detailed explanation of the type or types of physical barriers, curbs, structures, etc., which will be incorporated to protect the operator and prevent the equipment from entering the water. Nonstructural warning devices may be considered for situations where the use of structural barriers is determined to be impracticable. The activity hazard analysis must thoroughly address the procedure and be submitted to the Corps for review and acceptance prior to start of this feature of work.

(2) The stability of crawler, truck, and wheel-mounted cranes shall be assured.

(a) The manufacturer's load-rating chart may be used to determine the maximum allowable working load for each particular crane's boom angle provided a test load, with a boom angle of 20 degrees, confirms the manufacturer's load-rating table.

(b) Stability tests are required if:

(i) There is no manufacturer's load-rating chart securely fixed to the operator's cab;

(ii) There has been a change in the boom or other structural members; or

(iii) There has been a change in the counterweight.

The test shall consist of lifting a load with the boom in the least stable undercarriage position and at an angle of 20 degrees above the horizontal. The test shall be conducted under close supervision on a firm, level surface. The load that tilts the machine shall be identified as the test load. The test load moment (in ft-lbs) shall then be calculated by multiplying the horizontal distance (in ft) from the center of rotation of the machine to the test load, times the test load (in lbs). Three-fourths of this test-load moment shall then be used to compute the maximum allowable operating loads for the boom at 20, 40, 60, and 80 degrees above horizontal. From these maximum allowable operating loads, a curve shall be plotted and posted in the cab of the machine in sight of the operator. These values shall not be exceeded except in the performance test described below. The test load shall never exceed 110 percent of the manufacturer's maximum rated capacity.

(c) In lieu of the test and computations above, the crane may be load tested for stability at each of the four boom positions listed above.

(3) Performance tests shall be performed in accordance with Section 16 of EM 385-1-1. Performance tests shall be conducted after each stability test, when the crane is placed in service on a project, and at least every 12 months.

(4) Inspections shall be made which will ensure a safe and economical operation of both cranes and draglines. Specific inspections and their frequencies are listed on the appropriate checklists noted below. Results of inspections and tests for cranes shall be recorded on the Safety Inspection Check List, LMV Form 326R (available upon request), and inspection results for draglines shall be recorded on LMV Form 373R (available upon request). Copies of the inspections and tests shall be available at the jobsite for review. All stability and performance tests on cranes and all complete dragline inspections shall be witnessed by the Contracting Officer or his authorized representative.

(5) A complete dragline inspection shall be made:

- (a) At least annually;
- (b) Prior to the dragline being placed in operation; and
- (c) After the dragline has been out of service for more than six months.

e. Safety Sign. The Contractor shall furnish, erect, and maintain a safety sign at the site, as located by the Contracting Officer. The sign shall conform to the requirements of this paragraph and the drawing entitled "Safety Sign", included at the end of these Special Contract Requirements. The lettering shall be black and the background white. When placed on floating plant, the sign may be half size. Upon request, the Government will furnish a decal of the Engineer Castle. The sign shall be erected as soon as practicable, but not later than 15 calendar days after the date established for commencement of work. The data required shall be current.

1.13 BASIS FOR SETTLEMENT OF PROPOSALS (JAN 1997). Actual costs will be used to determine equipment costs for a settlement proposal submitted on the total cost basis under FAR 49.206-2(b). In evaluating a terminations settlement proposal using the total cost basis, the following principles will be applied to determine allowable equipment costs:

(1) Actual costs for each piece of equipment, or groups of similar serial or series equipment, need not be available in the Contractor's accounting records to determine total actual equipment costs.

(2) If equipment costs have been allocated to a contract using predetermined rates, those charges will be adjusted to actual costs.

(3) Recorded job costs adjusted for unallowable expenses will be used to determine equipment operating expenses.

(4) Ownership costs (depreciation) will be determined using the Contractor's depreciation schedule (subject to the provisions of FAR 31.205-11).

(5) License, taxes, storage and insurance costs are normally recovered as an indirect expense and unless the Contractor charges these costs directly to contracts, they will be recovered through the indirect expense rate. (EFARS 52.249-5000)

1.14 CERTIFICATES OF COMPLIANCE. Any certificates required for demonstrating proof of compliance of material with specification requirements shall be executed in four (4) copies. Each certificate shall be signed by an official authorized to certify on behalf of the manufacturing company and shall contain the name and address of the Contractor, the project name and location, and the quantity and date or dates of shipment or delivery to which the certificates apply. Copies of

laboratory test reports submitted with certificates shall contain the name and address of the testing laboratory and the date or dates of the test to which the report applies. Certification shall not be construed as relieving the Contractor from furnishing satisfactory material, if, after tests are performed on selected samples, the material is found not to meet the specific requirements.

1.15 CONTRACTOR'S CERTIFICATE. Each submittal of shop drawings and materials data shall be accompanied by a certificate, signed by the head of the Quality Control Organization of the prime Contractor, that the prime Contractor has reviewed in detail all shop drawings and materials contained in the submittal and that they are correct and in strict conformance with the contract drawings and specifications except as may be otherwise explicitly stated. The Government will first check for the Contractor's certificate and then review and render approval action or indicate disapproval in those cases where contract requirements are not fulfilled.

1.16 SHOP DRAWINGS. The Contractor shall submit to the Contracting Officer for approval 6 copies of all shop drawings as called for under the various headings of these specifications. These drawings shall be complete and detailed. If approved by the Contracting Officer, each copy of the drawings will be identified as having received such approval by being so stamped and dated. The Contractor shall make any correction required by the Contracting Officer. If the Contractor considers any correction indicated on the drawings to constitute a change to the contract drawings or specifications, notice as required under the CONTRACT CLAUSE entitled "Changes", will be given to the Contracting Officer. Five sets of all shop drawings will be retained by the Contracting Officer and one set will be returned to the Contractor. The approval of the drawings by the Contracting Officer shall not be construed as a complete check, but will indicate only that the general method of construction and detailing is satisfactory. Approval of such drawings will not relieve the Contractor of the responsibility for any errors which may exist, as the Contractor shall be responsible for the dimensions and design of adequate connections, details, and satisfactory construction of all work.

1.17 AS-BUILT DRAWINGS. The Contractor shall maintain three (3) full-size sets of the Contract drawings depicting a current record of the work as actually constructed. One set is for the Contractor's use and two (2) sets for the Government's use. These working as-built drawing red-line mark-ups may be manually or electronically generated using the construction plans. These working as-built drawings shall be reviewed at least monthly with the Contracting Officer, prior to the Contractor submitting a request for progress payment. Both shall certify that the as-built drawings are accurate and up-to-date before progress payment is made. Upon completion of the work and not later than 60 days from acceptance, the Contractor shall deliver two (2) a complete final set of the as-built red-line marked-up plans depicting the construction as actually accomplished. The final as-built drawings shall be identified as such by marking or stamping them with the words "AS-BUILT DRAWINGS" in letters at least 3/16" high. Those drawings where no change is involved shall be marked or stamped "AS-BUILT, NO CHANGE". Compliance and delivery of the final as-built drawings will be enforced through the approval of final payment. Also, the quality of the final as-built drawings will be reflected in the Contractor's performance evaluation. The amount of \$5,000.00 in addition to any other retainage shall be withheld pending acceptance of the final as-

built drawings by the Contracting Officer.

1.18 DAMAGE TO WORK. The responsibility for damage to any part of the permanent work shall be as set forth in the CONTRACT CLAUSE entitled "Permits and Responsibilities". However, if, in the judgement of the Contracting Officer, any part of the permanent work performed by the Contractor is damaged by flood, tornado, or earthquake, which damage is not due to the failure of the Contractor to take reasonable precautions or to exercise sound engineering and construction practices in the conduct of the work, the Contractor shall make the repairs as ordered by the Contracting Officer and full compensation for such repairs will be made at the applicable contract unit or lump sum prices as fixed and established in the contract. If, in the opinion of the Contracting Officer, there are no contract unit or lump sum prices applicable to any part of such work, an equitable adjustment pursuant to the CONTRACT CLAUSE entitled "Changes" will be made as full compensation for the repairs of that part of the permanent work for which there are no applicable contract unit or lump sum prices. Except as herein provided, damage to all work (including temporary construction), utilities, materials, equipment and plant shall be repaired to the satisfaction of the Contracting Officer at the Contractor's expense regardless of the cause of such damage.

1.19 NOTIFICATION OF AREA ENGINEER BEFORE BEGINNING WORK. At least 7 days before beginning work, the Contractor shall notify Mr. Donald R. Tutor, Area Engineer, Wynne Area Office, 1932 N. Falls Boulevard, Wynne, Arkansas 72396-0729, Telephone No. 901-544-3856 or 870-238-7983. COLLECT CALLS WILL NOT BE ACCEPTED.

1.20 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE (MAR 1995).

a. This clause does not apply to terminations. See SPECIAL CONTRACT REQUIREMENT entitled, "Basis for Settlement of Proposals" and FAR Part 49.

b. Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a Contractor or subcontractor at any tier shall be based on actual cost data for each piece of equipment or groups of similar serial and series for which the Government can determine both ownership and operating costs from the Contractor's accounting records. When both ownership and operating costs cannot be determined for any piece of equipment or groups of similar serial or series equipment from the Contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP 1110-1-8, Construction Equipment Ownership and Operating Expense Schedule, Region III Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the Contracting Officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.

c. Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(2)(ii) and FAR 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees.

d. When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the Contracting Officer shall request the Contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet. (EFARS 52.231-5000)

NOTE: THE CONTRACTOR MAY PURCHASE THE EQUIPMENT MANUAL FROM THE GOVERNMENT PRINTING OFFICE. THE GOVERNMENT PRINTING OFFICE TELEPHONE NO. IS 202-512-1800 and THE INTERNET ADDRESS IS <http://bookstore.gpo.gov/sb/sb-261.html>. COST ENGINEERING BRANCH OF THE CORPS OF ENGINEERS HAS FREE EQUIPMENT MANUALS FOR ALL REGIONS ON COMPACT DISK (CD). CONTACT THE WYNNE AREA OFFICE IN ORDER TO OBTAIN A FREE COPY OF THE CD.

1.21 RETESTING OF CONSTRUCTION MATERIALS. Unless otherwise specified, where the Technical Specifications state that tests will be performed at the expense of the Government, the cost of only the initial test will be borne by the Government. Any retesting due to failure of the materials to meet the requirements in the initial test or any retesting requested by the Contractor shall be performed at the Contractor's expense. The retests shall be at laboratories approved by the Contracting Officer. The costs of retests made at Government laboratories will be deducted from the total amount due the Contractor.

1.22 VEHICLE WEIGHT LIMITATIONS. Vehicle weight limitations for operation on roads, streets, and bridges may affect the prosecution of work under this contract. The Contractor will be responsible for obtaining all necessary licenses and permits in accordance with the CONTRACT CLAUSE entitled "Permits and Responsibilities".

1.23 OBSTRUCTIONS.

a. Utilities. All utilities located at the site are to remain in place and operative during the construction. The exact location, depth, and height of utilities shown on drawings shall be verified in the field by the Contractor. At least 10 days before beginning work in the vicinity of a utility, the Contractor shall call the appropriate "Call Before You Dig" number listed below. The Contractor shall exercise special care when working in the vicinity of utilities to prevent damage thereto or injury to the Contractor's employees or others. Any damage to the utilities or interruptions of service occasioned by the Contractor's operations shall be repaired and the service restored promptly at his expense.

In the event the Contractor elects to have utilities relocated for his own convenience, he shall make his own arrangement with utility owners for the rerouting and replacement to their permanent location after completion of the work adjacent thereto. All costs associated with utility relocation for the Contractor's convenience shall be at his expense.

CALL BEFORE YOU DIG NUMBERS

Mississippi 1-800-227-6477

b. Existing Fences and Cattle Guards. Existing fences and cattle guards within the work limits will be removed, if necessary, by others as the construction progresses. The Contractor shall notify Mr. Kelly Greenwood, Chief Engineer, Yazoo-Mississippi Levee Delta Board District, Clarksdale, MS 38614-0610, P. O. Drawer (Box) 610, Telephone Number (662) 624-4397 / 8, at least 10 days prior to the date the removal of fences and cattle guards at each separate location will be required. The Contractor shall cooperate fully with the local officials with respect to the removal of fences and cattle guards. Any unwarrantable damage to the fences and cattle guards occasioned by the Contractor's operations shall be repaired at his expense.

1.24 NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES). In compliance with the General Permit of the NPDES, the Contracting Officer will file a Notice of Intent (NOI) with the State of Mississippi. The Contractor shall adhere strictly to the erosion control provisions of SECTION 01130 - ENVIRONMENTAL PROTECTION to minimize sediment discharge into nearby water courses to the maximum extent practicable. Furthermore, the Contractor and all subcontractors shall sign the certification contained in the SWPPP. The Contractor shall maintain the SWPPP on the construction site at all times. The SWPPP shall take precedence over the technical specifications.

1.25 PERFORMANCE OF WORK BY THE CONTRACTOR (APR 1984). The Contractor shall perform on the site, and with its own organization, work equivalent to at least fifteen (15) percent of the total amount of work to be performed under the contract. This percentage may be reduced by a supplemental agreement to this contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government. (FAR 52.236-1)

1.26 CONTINUING CONTRACTS (MAR 1995).

a. This is a continuing contract, as authorized by Section 10 of the River and Harbor Act of September 22, 1922 (33 U.S. Code 621). The payment of some portion of the contract price is dependent upon reservations of funds from future appropriations, and from future contribution to the project having one or more non-federal project sponsors. The responsibilities of the Government are limited by this clause notwithstanding any contrary provision of the "Payments Under Fixed-Price Construction Contracts" clause or any other clause of this contract.

b. The sum of \$ 1,000.00 has been reserved for this contract and is available for payments to the Contractor during the current fiscal year. It is expected that Congress will make appropriations for future fiscal years from which additional funds together with funds provided by one or more non-federal project sponsors will be reserved for this contract.

c. Failure to make payments in excess of the amount currently reserved, or that may be reserved from time to time, shall not entitle the Contractor to a price adjustment under the terms of this contract except as specifically provided in paragraphs "f" and "i" below. No such failure shall constitute a breach of this contract, except that this provision shall not bar a breach-of-contract action if an amount finally determined to be due as a termination allowance remains unpaid for one year due solely to a failure to reserve sufficient additional funds therefor.

d. The Government may at any time reserve additional funds for payments under the contract if there are funds available for such purpose. The Contracting Officer will promptly notify the Contractor of any additional funds reserved for the contract by issuing an administrative modification to the contract.

e. If earnings will be such that funds reserved for the contract will be exhausted before the end of any fiscal year, the Contractor shall give written notice to the Contracting Officer of the estimated date of exhaustion and the amount of additional funds which will be needed to meet payments due or to become due under the contract during that fiscal year. This notice shall be given not less than 45 nor more than 60 days prior to the estimated date of exhaustion.

f. No payments will be made after exhaustion of funds except to the extent that additional funds are reserved for the contract. The Contractor shall be entitled to simple interest on any payment that the Contracting Officer determines was actually earned under the terms of the contract and would have been made except for exhaustion of funds. Interest shall be computed from the time such payment would otherwise have been made until actually or constructively made, and shall be at the rate established by the Secretary of the Treasury pursuant to Public Law 92-41, 85 STAT 97, as in effect on the first day of the delay in such payment.

g. Any suspension, delay, or interruption of work arising from exhaustion or anticipated exhaustion of funds shall not constitute a breach of this contract and shall not entitle the Contractor to any price adjustment under the "Suspension of Work" clause or in any other manner under this contract.

h. An equitable adjustment in performance time shall be made for any increase in the time required for performance of any part of the work arising from exhaustion of funds or the reasonable anticipation of exhaustion of funds.

i. If, upon the expiration of sixty (60) days after the beginning of the fiscal year following an exhaustion of funds, the Government has failed to reserve sufficient additional funds to cover payments otherwise due, the Contractor, by written notice delivered to the Contracting Officer

at any time before such additional funds are reserved, may elect to treat his right to proceed with the work as having been terminated. Such a termination shall be considered a termination for the convenience of the Government.

j. If at any time it becomes apparent that the funds reserved for any fiscal year are in excess of the funds required to meet all payments due or to become due the Contractor because of work performed and to be performed under the contract during the fiscal year, the Government reserves the right, after notice to the Contractor, to reduce said reservation by the amount of such excess. (EFARS 52.232-5001)

1.27 ACCEPTANCE SECTIONS-NOT USED.

1.28 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER (31 OCT 1989).

a. This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance with the CONTRACT CLAUSE entitled "Default (Fixed-Price Construction)". In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied:

(1) The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.

(2) The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the Contractor.

b. The following schedule of monthly anticipated adverse weather delays is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the project location and will constitute the base line for monthly weather time evaluations. The Contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent activities.

MONTHLY ANTICIPATED ADVERSE WEATHER DELAY WORK DAYS BASED ON (6) DAY WORK WEEK

<u>JAN</u>	<u>FEB</u>	<u>MAR</u>	<u>APR</u>	<u>MAY</u>	<u>JUN</u>	<u>JUL</u>	<u>AUG</u>	<u>SEP</u>	<u>OCT</u>	<u>NOV</u>	<u>DEC</u>
(13)	(8)	(9)	(8)	(7)	(7)	(5)	(4)	(4)	(5)	(7)	(11)

c. Upon acknowledgment of the Notice to Proceed (NTP) and continuing throughout the contract, the Contractor will record on the daily CQC report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the Contractor's scheduled work day. The number of actual adverse weather delay days shall include days impacted by actual adverse weather

(even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph b, above, the Contracting Officer will convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the CONTRACT CLAUSE entitled "Default (Fixed-Price Construction)". (ER 415-1-15, Appendix A)

1.29 PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DEC 1991).

a. The Government will pay all costs for the mobilization and demobilization of all of the Contractor's plant and equipment at the contract lump sum price for this item.

(1) Sixty (60) percent of the lump sum price upon completion of the Contractor's mobilization at the work site.

(2) The remaining forty (40) percent upon completion of demobilization.

b. The Contracting Officer may require the Contractor to furnish cost data to justify this portion of the bid if the Contracting Officer believes that the percentages in paragraphs a(1) and (2) of this clause do not bear a reasonable relation to the cost of the work in this contract.

(1) Failure to justify such price to the satisfaction of the Contracting Officer will result in payment, as determined by the Contracting Officer, of--

(i) Actual mobilization costs at completion of mobilization;

(ii) Actual demobilization costs at completion of demobilization; and

(iii) The remainder of this item in the final payment under this contract.

(2) The Contracting Officer's determination of the actual costs in paragraph b (1) of this clause is not subject to appeal. (DFARS 252.236-7004)

1.30 STONE SOURCES.

a. For a list of quarries that have produced stone that meet the requirements of these specifications, view the website listed below. If a stone source is designated as "New Source," then that source has been tested and the results of those tests have indicated that the stone will meet the material quality requirements. However, the "New Sources" may not have been used; therefore, the stone gradation and quarry production capability may not have been verified. <http://155.76.117.11/conops/MVDStoneLST020601.htm>

b. Stone may be furnished either from any of the sources posted at the above website,

or from any other sources designated by the Contractor and accepted by the Contracting Officer, subject to the conditions hereinafter stated.

c. After the award of the contract, the Contractor shall designate in writing only one source or one combination of sources from which he/she proposes to furnish stone. If the Contractor proposes to furnish stone from a source or sources not posted at the above website, he/she may designate only a single source for stone. Samples for acceptance testing shall be provided as required in the Technical Specifications. If the Contracting Officer does not accept a source for stone, so designated by the Contractor, the Contractor may not propose other sources but shall furnish the stone from a posted source at no additional cost to the Government.

d. In the event that the Contractor proposes to furnish stone from a posted source, and that posted source fails to meet the material quality requirements as set forth in the technical specifications, the Contractor shall identify the reason for the deficiency and shall either rectify the situation or procure stone at another posted quarry. At no time shall stone be accepted that does not fulfill the requirements as described in the technical specifications.

e. Acceptance of a source of stone shall not be construed as acceptance of all material from that source. The right is reserved to reject materials from certain localized areas, zones, strata, or channels, when such materials are unsuitable for stone as determined by the Contracting Officer. Materials produced from a posted source shall meet all the requirements of the Technical Specifications.

1.31 FIELD OFFICE BUILDING.

a. The Contractor shall furnish and maintain a temporary building for the exclusive use of the Government inspectors during the life of the contract. The building shall conform to the following requirements:

Floor Space	Not less than 300 sq. ft.
Height of Ceiling	Not less than 7 feet
Windows	Not less than 4
Doors	At least 1
Type of Floor	Wood or Concrete
Active Telephone Lines	At least 2

The building shall be of light but weatherproof construction. Windows shall be arranged to open and to be fastened from the inside. All door and window openings shall be provided with suitable screens. The door shall be equipped with a durable hasp and padlock. Interior surfaces of exterior walls and ceilings shall be covered with insulating board. An inside storage room of adequate size shall be provided. The Contractor shall furnish an adequate supply of approved drinking water, a sink, running water for a toilet facility having a flushable toilet, all electricity required, sufficient electrical outlets for office calculators and equipment, and sufficient fixtures for adequate lighting..

The building shall also be equipped with air conditioning during hot weather and during cold weather shall be equipped with an adequate heating system.. The office shall be equipped with at least 8 chairs, two desks, a drawing table, 2 two-drawer filing cabinets, and a table suitable for use as a conference table. The Contractor shall furnish local and long distance service for the two phone lines. The Contractor shall thoroughly clean the office at least weekly. The field office, its location and all facilities shall be subject to the approval of the Contracting Officer.

b. No separate payment will be made for furnishing and maintaining the field office. Such building will remain the property of the Contractor and shall be removed upon completion of the work as provided in the CONTRACT CLAUSE entitled "Operations and Storage Areas."

1.32 SUBMITTALS. Within 15 calendar days after receipt of notice to proceed, the Contractor shall complete and submit to the Contracting Officer, in duplicate, submittal register ENG Form 4288-R listing all submittals and dates. In addition to those items listed on ENG Form 4288-R, the Contractor shall furnish submittals for any deviation from the plans or specifications. The scheduled need dates must be recorded on the document for each item for control purposes. In preparing the document, adequate time (minimum of 30 days) will be allowed for review and approval and possible resubmittal. Scheduling shall be coordinated with the approved progress schedule. The Contractor's Quality Control representative shall review the listing at least every 30 days and take appropriate action to maintain an effective system. Two (2) copies of updated or corrected listing shall be submitted to the Contracting Officer at least every 60 days. Payment will not be made for any material or equipment, which does not comply with contract requirements. An original and four (4) copies of all submittals shall be furnished the Contracting Officer. A completed submittal form, ENG Form 4025-R, shall accompany all submittals. Copies of ENG Form 4025-R and ENG Form 4288-R will be furnished the Contractor upon request. Copies of ENG Form 4025-R and ENG Form 4288-R are included at the end of these Special Contract Requirements. (ER 415-1-10, Appendices A and B)

1.33 HAUL ROADS. Whenever practical, one-way haul roads shall be used on this contract. Haul roads built and maintained for this work shall comply with the following:

a. One-way haul roads for off-the-road equipment; e.g., belly dumps, scrapers, and off-the-road trucks shall have a minimum usable width of 25 feet. One-way haul roads for over-the-road haulage equipment only (e.g., dump trucks, etc.) may be reduced to a usable width of 15 feet. When the Contracting Officer determines that it is impractical to obtain the required width for one-way haul roads (e.g., a road on top of a levee), a usable width of not less than 10 feet may be approved by the Contracting Officer, provided a positive means of traffic control is implemented. Such positive means shall be signs, signals, and/or signalman, and an effective means of speed control.

b. Two-way haul roads for off-the-road haulage equipment shall have a usable width of 60 feet. Two-way haul roads for over-the-road haulage equipment only may be reduced to a usable width of 30 feet.

c. Haul roads shall be graded and otherwise maintained to keep the surface free from

potholes, ruts, and similar conditions that could result in unsafe operation.

d. Grades and curves shall allow a minimum sight distance of 200 feet for one-way roads and 300 feet for two-way roads. Sight distance is defined as the centerline distance an equipment operator (4.5 feet above the road surface) can see an object 4.5 feet above the road surface. When conditions make it impractical to obtain the required sight distance (e.g., ramps over levees), a positive means of traffic control shall be implemented.

e. Dust abatement shall permit observation of objects on the roadway at a minimum distance of 300 feet.

f. Haul roads shall have the edges of the usable portion marked with posts at intervals of 50 feet on curves and 200 feet maximum elsewhere. Such markers shall extend 6 feet above the road surface and for nighttime haulage be provided with reflectors in both directions.

1.34 TEMPORARY PROJECT FENCING. Temporary project fencing as required by Paragraph 04.A.04 of EM 385-1-1 is required for well sites 9 thru 14 on this project.

1.35 MAINTENANCE OF TRAFFIC - NOT USED.

1.36 COOPERATION WITH OTHERS - NOT USED.

1.37 HOURS OF WORK - NOT USED.

1.38 SUNDAY, HOLIDAY AND NIGHT WORK. Sunday and Holiday work will be at the option of the Contractor, but night work will not be permitted unless otherwise authorized by the Contracting Officer.

1.39 SECURITY REQUIREMENTS - NOT USED.

1.40 INSURANCE REQUIREMENTS FOR WORK ON GOVERNMENT PROPERTY – NOT USED.

1.41 STORAGE OF EQUIPMENT AND MATERIALS. Storage of the Contractor's equipment and materials shall be at those areas within the rights-of-way designated by the Contracting Officer.

1.42 WARRANTY OF CONSTRUCTION (MAR 1994).

a. In addition to any other warranties in this contract, the Contractor warrants, except as provided in paragraph i. of this clause, that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, or design furnished, or workmanship performed by the Contractor or any subcontractor or supplier at any tier.

b. This warranty shall continue for a period of 1 year from the date of final acceptance of the work. If the Government takes possession of any part of the work before final acceptance, this warranty shall continue for a period of 1 year from the date the Government takes possession.

c. The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Government-owned or controlled real or personal property, when that damage is the result of--

(1) The Contractor's failure to conform to contract requirements; or

(2) Any defect of equipment, material, workmanship, or design furnished.

d. The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for 1 year from the date of repair or replacement.

e. The Contracting Officer shall notify the Contractor, in writing, within a reasonable time after the discovery of any failure, defect, or damage.

f. If the Contractor fails to remedy any failure, defect, or damage within a reasonable time after receipt of notice, the Government shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.

g. With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall--

(1) Obtain all warranties that would be given in normal commercial practice;

(2) Require all warranties to be executed, in writing, for the benefit of the Government, if directed by the Contracting Officer; and

(3) Enforce all warranties for the benefit of the Government, if directed by the Contracting Officer.

h. In the event the Contractor's warranty under paragraph (b) of this clause has expired, the Government may bring suit at its expense to enforce a subcontractor's, manufacturer's, or supplier's warranty.

i. Unless a defect is caused by the negligence of the Contractor or subcontractor or supplier at any tier, the Contractor shall not be liable for the repair of any defects of material or design furnished by the Government nor for the repair of any damage that results from any defect in

Government-furnished material or design.

j. This warranty shall not limit the Government's rights under the Inspection and Acceptance clause of this contract with respect to latent defects, gross mistakes, or fraud. (FAR 52.246-21)

1.43 UTILITY SERVICES.

a. The Contractor shall provide at the site for all work under this contract, the necessary utility services needed for completion of work under this contract.

b. Electricity. All electric current required by the Contractor shall be furnished at his own expense. All temporary connections for electricity shall be subject to the approval of the Contracting Officer. All temporary lines shall be furnished, installed, connected and maintained by the Contractor in a workman-like manner satisfactory to the Contracting Officer, and shall be removed by the Contractor in like manner at his expense prior to completion of the construction.

1.44 COMMERCIAL WARRANTY. The Contractor agrees that the building and construction materials and building hardware furnished under this contract shall be covered by the most favorable commercial warranty the Contractor gives to any customer for such products and that the rights and remedies provided herein are in addition to and do not limit any rights afforded to the Government by any other clause of this contract. The warranty will take effect immediately after compliance by the Contractor of these specifications, and acceptance of the completed work by the Government.

1.45 PAYMENT FOR MATERIALS STORED OFFSITE – NOT USED.

1.46 WORK IN QUARANTINED AREA– NOT USED.

1.47 WORK ON OR ADJACENT TO RAILROAD PROPERTY – NOT USED.

1.48 INSURANCE REQUIREMENTS FOR WORK ON OR ADJACENT TO RAILROAD PROPERTY – NOT USED.

1.49 CONTROL OF WATER LEVELS - NOT USED.

1.50 FLOOD EMERGENCY.

a. In the event that a threat of flood is considered to exist or to be impending during work under this contract, the Contractor, if ordered, shall perform emergency operations as directed and an equitable adjustment in the contract price will be made in accordance with the CONTRACT CLAUSE entitled "Changes" on account of the additional work required.

b. Should the Contractor, after specific notification by the Contracting Officer that a

flood emergency is considered to exist, or to be impending, fail to complete, without delay, the emergency operations as specified in paragraph a above, or should the flood emergency be of such nature that, in the opinion of the Contracting Officer, the Contractor is unable to complete the required emergency operations in the time it is needed, the Contracting Officer shall have the right to prescribe the location and the order of work by the Contractor for the duration of the flood emergency and to employ the necessary equipment and perform all or any part of such work or to cause all or any part of such work to be performed by others. No payment will be made to the Contractor for any work by the Contracting Officer or by others under the terms of this subparagraph or for added expense to the Contractor occasioned by construction difficulties arising from operations of the Contracting Officer or others under the terms of this subparagraph.

c. The right is reserved by the Contracting Officer to suspend the Contractor's operations for such period or periods of time during threat of impending flood or flood emergency as may be necessary. Intervals during which work is suspended by order of the Contracting Officer under the provisions of this subparagraph will not be counted as part of the contract period.

1.51 PATENTS PROPRIETARY RIGHT – NOT USED.

1.52 PROTECTION OF MATERIALS AND WORK – NOT USED.

1.53 EXISTING FLOOD PROTECTION. The Contractor shall conduct the construction of all work under this contract in such manner that existing flood protection within the limits of the existing embankments is maintained at all times. The embankments shall not be disturbed except as necessary to perform the work. When the work under this contract is completed, flood protection within such areas shall be at least equal to that existing before start of construction

1.54 FINAL ACCEPTANCE - NOT USED.

1.55 OBSTRUCTION OF NAVIGABLE WATERWAYS – NOT USED.


1.56 DREDGE SIZE – NOT USED.

1.57 SIGNAL LIGHTS – NOT USED.


1.58 INSPECTION – NOT USED.

1.59 DESIGNATED BILLING OFFICE. The designated billing office for this contract shall be Wynne Area Office, 1932 N. Falls Boulevard, P.O. Box 729, Wynne, Arkansas 72396-0729.


-- End of Section --



ELEVATION



ELEVATION



SECTION A-A

NOTES:

1. CONTRACTOR SHALL CONSTRUCT AND MAINTAIN A DURABLE SIGN AS SHOWN.
2. WOOD IN CONTACT WITH GROUND SHALL BE TREATED LUMBER.
3. ALL EXPOSED SURFACES SHALL BE WHITE HOUSE PAINT.
4. LETTERING SHALL BE BLACK.
5. ENGINEER CASTLE DECAL FURNISHED BY GOVERNMENT.
6. 22 GA. SHEET METAL MAY BE USED IN LIEU OF PLYWOOD.



**US Army Corps
of Engineers**

Memphis District

ENGINEER CASTLE DETAIL

SCALE: NONE

MARCH 1995

U.S. ARMY ENGINEER DISTRICT, MEMPHIS
CORPS OF ENGINEERS
MEMPHIS, TENNESSEE

SAFETY SIGN

**AUSTIN, MISSISSIPPI SEEPAGE RELIEF WELLS
TUNICA COUNTY, MISSISSIPPI
STORMWATER POLLUTION PREVENTION PLAN
FOR STORMWATER GENERAL PERMIT
U. S. ARMY CORPS OF ENGINEERS, MEMPHIS DISTRICT**

1. LOCATION AND NATURE OF ACTIVITY

This project consists of installing relief wells and adjacent collector ditches near Austin, Mississippi in Tunica County, Mississippi.

A set of construction drawings showing the project location and the details of installation of both the wells and the collector ditches will be located on the site at all times. The project will begin at levee mile 41/45+00 and extend to levee mile 43/05+79.

2. AREA AFFECTED

The total area of the site, within the right-of-way limits, which will be impacted by construction, is approximately 100 acres.

3. CONTROL OF POLLUTANTS DURING CONSTRUCTION

3.1 NON-STRUCTURAL MEASURES

3.1.1 General

Prior to the beginning of any construction, The Contracting Officer will identify all land resources to be preserved within the Contractor's work area. The Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, top soil, and land forms outside the construction limits without special permission. The Contractor shall provide effective protection for land, water, and vegetation resources at all times. The Contractor shall construct or install temporary and/or permanent erosion and sedimentation control features as indicated herein to minimize pollutants entering Beaverdam Lake, and other water bodies or wetlands.

3.1.2 Protection of Landscape

Trees, shrubs, vines, grasses, land forms and other landscape features indicated and defined on the contract drawings or as directed by the Contracting Officer to be preserved shall be clearly identified by marking, fencing, wrapping with boards, or other approved techniques.

3.1.3 Reduction of Exposure to Unprotected Erodible Soils

All earthwork shall be planned and conducted to minimize duration of exposure of unprotected soils. Vegetative ground cover shall not be destroyed, removed or disturbed more than 20 calendar days prior to grading or earth moving. Clearing shall progress in reasonable sized increments as needed to use the areas developed. To the extent feasible, material embankments, side slopes, back slopes, berms and any other exposed surfaces shall be stabilized by temporary seeding, mulching, fabric mats or other approved stabilization methods, as soon as possible after material placement, or within 14 days on areas that will remain unfinished more than 21 calendar days. Should construction be halted, for any reason, temporary or permanently, for more than 21 days, in any portion of the site, temporary or permanent turfing measures, or other approved temporary stabilization of exposed areas, such as mulching, shall be accomplished within 14 days after construction is halted.

3.2 STRUCTURAL MEASURES

3.2.1 General

The temporary erosion and sediment control measures such as silt fences, check dams, and sedimentation basins shall be constructed and maintained until permanent drainage and erosion control facilities are complete and operative. Placement of perimeter controls shall commence with initiation of construction and shall remain in effect during the remainder of construction until final stabilization of those portions of the site upward of the perimeter control. Temporary erosion controls shall be maintained until final stabilization of exposed areas, after which they shall be removed. All structural devices shall be constructed in accordance with Standard Drawing 51/208.

3.2.2 Silt Fences

If used, silt fences shall be constructed along the levee toe in any location where stormwater may enter the stream or wetland, along inlet ditches, and any other areas necessary to minimize the entry of excavated material into Beaverdam Lake.

3.2.3 Check Dams

Check dams shall be constructed across inlet ditches, drains and swales using baled straw or equivalent devices to minimize sediment entry into streams. Check dams shall be inspected for sediment accumulation after each significant rainfall and sediment removed when it reaches one-half the height of the barrier. Sediment removal shall include removal and disposition in a location where it will not erode into construction areas, watercourses or wetlands.

3.2.4 Sediment Basins

Sediment from construction areas 10 or more disturbed acres at one time shall be trapped in temporary or permanent sediment basins. After each storm, the basins shall be allowed to settle for 24 to 48 hours after which the basins shall be pumped dry. In order to maintain basin effectiveness, accumulated sediment shall be removed when the depth of sediment reaches one-third of the depth of structure in any part of the pool. Overflow shall be controlled by paved weir, by vertical overflow pipe draining from the spillway and at the outlet toe of the spillway. The collected topsoil sediment shall be reused for fill on the construction site, and/or conserved for use at another site(s). If used, the basins shall provide at least 3,600 cubic feet of storage for each acre drained. Where such basins are used, other equivalent sediment control measures are required.

3.2.5 Other Measures

Other temporary erosion and sediment control measures such as berms, dikes, swales, and drains, may be used with, or in lieu of, the abovementioned measures provided they are consistent with Best Management Practices (BMPs). They shall be maintained until permanent drainage and erosion control facilities are completed and operative. Earthen erosion control features shall be compacted and stabilized immediately with vegetation as specified in paragraphs 4.1.3 and 4.1.4.

3.2.6 Velocity Dissipation Devices

Should drains or swales be used, they shall be constructed with velocity dissipation devices (check dams) to reduce the need for more stringent erosion control practices in the swale or drain. These devices shall be removed after the erosive areas have been stabilized.

4. CONTROL OF POLLUTANTS AFTER CONSTRUCTION

4.1 ESTABLISHMENT OF TURF

4.1.1 General

Turf shall be established as a permanent erosion control measure along the levee embankment and any other areas which are disturbed during construction. All material embankments, all berm areas, and any other disturbed areas shall be turfed. Turf shall be established in accordance with the Contract Specifications.

4.1.2 Fertilizer

Fertilizer shall be distributed uniformly over the areas to be seeded at a rate which will supply no less than 40 pounds of available nitrogen, 40 pounds of available phosphorous, and 40 pounds of potash per acre.

4.1.3 Seeding

Seed sown for permanent turfing shall be as specified in the technical specifications. Temporary seeding shall consist of grasses appropriate for the season when they are sown. A satisfactory method of sowing shall be employed, using approved mechanical power-drawn seeders, mechanical hand-seeders, broadcast-seeders, or other approved methods. When conditions are such by reason of drought, high winds, excessive moisture, or other factors that satisfactory results are not likely to be obtained, work shall be halted as directed and resumed only when conditions are favorable or when approved alternative or corrective measures and procedures have been effected. If inspection either during seeding operations or after there is a show of green indicated that areas have been left unplanted, additional seed shall be sown.

4.1.4 Mulching

If used, mulch shall be materials that do not contain noxious grass or weed seed that might be detrimental to the turfing being established or to adjacent farmland. Mulch shall be spread uniformly in a continuous blanket, using 2 tons per acre of straw mulch or 1,200 pounds per acre of wood cellulose fiber mulch.

4.2 STATE AND LOCAL CONTROLS

There is no known State or local erosion and sediment control requirements applicable to this work other than those met by requirements of this permit.

5. RUNOFF COEFFICIENT, IMPERVIOUS AREAS, SOILS

The runoff coefficient immediately after construction is estimated to range between 0.10 and 0.30. Once the material embankment and other disturbed areas have been revegetated, the runoff coefficient should return to preconstruction conditions with no increase in impervious areas. Soils in the area consist of fat and lean clays with some sand and silty sands.

6. RECEIVING WATER

The receiving waters are Beaverdam Lake, a slough located in Tunica County, Mississippi and the Mississippi River.

7. INSPECTIONS

7.1 General

Quality assurance representatives shall inspect disturbed areas of the construction site and areas used for storage of materials that are exposed to precipitation that have not been finally stabilized, structural control measures and locations where vehicles enter or exit the site every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches or greater. Where sites have been stabilized, inspections shall be conducted at least once every month.

7.2 Disturbed Areas And Areas Used For Material Storage

Disturbed areas and areas used for material storage that are exposed to precipitation shall be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impact to receiving waters. Locations where vehicles enter or exit the site shall be inspected for evidence of offsite sediment tracking.

7.3 Modifications Of Pollution Plan

Based on the results of the inspection in paragraph 7.2, the site description identified in paragraphs 1 and 2 of this plan shall be revised as appropriate, but in no case more than 7 calendar days following the inspection. Such modifications shall provide for timely implementation of any changes to the plan within 7 calendar days following the inspection.

7.4 Reports

A report summarizing the scope of the inspection, name(s) and qualifications of personnel making the inspection, the date(s) of the inspection, major observations relating to the implementation of the Storm Water Pollution Prevention Plan (SWPPP), and actions taken shall be recorded and retained by the Contracting Officer as part of the SWPPP for at least (3) years from the date the site is finally stabilized.

8. DEFINITIONS

8.1 Best Management Practices (BMPs) Schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of waters of the State. BMPs also include treatment requirements, operation procedures and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage.

8.2 Commencement of Construction The initial disturbance of soils associated with clearing, grading, or excavating activities or other construction activities.

8.3 Drainage Swale A drainage way with a lining of grass, riprap, asphalt, concrete, or other material installed to convey runoff without causing erosion.

8.4 Check Dam Small temporary dams constructed across a swale or drainage ditch to reduce the velocity of runoff flows.

8.5 Final Stabilization All soil disturbing activities at the site have been completed, and a uniform perennial vegetative cover with a density of 85% of cover for the area has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed.

9. CERTIFICATION

“I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharge associated with industrial activity from the construction site identified as part of this certification.”

<u>Dennis J Kamper, P.E., Chief, Engineering Division</u>	<u>901-544-3226</u>
Name & Official Title	Phone No.

_____ Signature	_____ Date Signed
--------------------	----------------------

_____ Name & Official Title Of Contractor	_____ Phone No.
--	--------------------

_____ Signature	_____ Date Signed
--------------------	----------------------

_____ Name & Official Title Of Subcontractor	_____ Phone No
---	-------------------

_____ Signature	_____ Date Signed
--------------------	----------------------

[illegible]

[illegible]

[illegible]

TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES OR MANUFACTURE'S CERTIFICATES OF COMPLIANCE (Read instructions on the reverse side prior to initiating this form)				DATE		TRANSMITTAL NO.	
SECTION I - REQUEST FOR APPROVAL OF THE FOLLOWING ITEMS (This section will be initiated by the contractor)							
TO:		FROM		CONTRACT NO.		CHECK ONE: [] THIS IS A NEW TRANSMITTAL [] THIS IS A RESUBMITTAL OF TRANSMITTAL _____	
SPECIFICATION SECT. NO. (Cover only one section with each transmittal)		PROJECT TITLE AND LOCATION					
ITEM NO.	DESCRIPTION OF ITEM SUBMITTED (Type size, model number/etc.)	MFG OR CONTR. CAT., CURVE DRAWING OR BROCHURE NO. (See instruction no. 8)	NO. OF COPIES	CONTRACT REFERENCE DOCUMENT		FOR VARIATION (See Instruction No. 6)	FOR CE USE CODE
a.	b.	c.	d.	e.	f.	g.	h. i.
REMARKS		I certify that the above submitted items have been reviewed in detail and are correct and in strict conformance with the contract drawings and specifications except as otherwise stated. NAME AND SIGNATURE OF CONTRACTOR _____					
SECTION II - APPROVAL ACTION							
ENCLOSURE RETURNED (Listed by Item No.)		NAME, TITLE AND SIGNATURE OF APPROVING AUTHORITY			DATE		
ENG FORM 4025-R, MAR 95		(ER 415-1-10)		EDITION OF SEP 93 IS OBSOLETE		SHEET __ OF __ (Proponent: CEMP-CE)	

1. Section 1 will be initiated by the Contractor in the required number of copies.
2. Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial number for identifying each submittal. For new submittals or resubmittals, mark the appropriate box; on resubmittals, insert transmittal number of last submission as well as the new submittal number.
3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288 for each entry on this form.
4. Submittals requiring expeditious handling will be submitted on a separate form.
5. Separate transmittal form will be used for submittals under separate sections of the specifications.
6. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications--also, a written statement to that effect shall be included in the space provided for "Remarks".
7. Form is self-transmittal, letter of transmittal is not required.
8. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I.
9. U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below in Section I, column g, to each item submitted.

THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS
SUBMITTED

- | | | | | | |
|---|----|--|----|----|---|
| A | -- | Approved as submitted. | E | -- | Disapproved (See attached). |
| B | -- | Approved, except as noted on drawings. | F | -- | Receipt acknowledge. |
| C | -- | Approved, except as noted on drawings.
Refer to attached sheet resubmission required. | FX | -- | Receipt acknowledged, does not comply
as noted with contract requirements. |
| D | -- | Will be returned by separate correspondence. | G | -- | Other (Specify) |
10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

TECHNICAL SPECIFICATIONS

TABLE OF CONTENTS

Section No.

Description

DIVISION 1 - GENERAL REQUIREMENT

01025	Measurement and Payment
01130	Environmental Protection
01451	Contractor Quality Control
01452	Project Signs, Barricades, and Traffic Control Signs

DIVISION 2 - SITE WORK

02114	Clearing
02215	Geotextile (Filter Fabric)
02225	Earthwork
02542	Stone Protection
02545	Crushed Stone and Armorloc Blocks
02546	Aggregate Surfacing
02700	Culvert Installation
02704	Steel Pipe Installation
02708	Relief Wells
02936	Establishment of Turf

DIVISION 3 - CONCRETE

03307	Concrete for Minor Structures
-------	-------------------------------

DIVISIONS 4 THRU 14 - NOT USED

DIVISION 15 - MECHANICAL

15175	Discharge Pipe and Appurtenances
-------	----------------------------------

DIVISION 16 - NOT USED

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01025

MEASUREMENT AND PAYMENT

TABLE OF CONTENTS

PART 1	GENERAL
1.1	LUMP SUM PAYMENT ITEMS
1.1.1	General
1.1.2	Lump Sum Items
1.2	UNIT PRICE PAYMENT ITEMS
1.2.1	Unit Price Items
PART 2	PRODUCTS (Not Used)
PART 3	EXECUTION (Not Used)

SECTION 01025

MEASUREMENT AND PAYMENT

PART 1 GENERAL

1.1 LUMP SUM PAYMENT ITEMS

1.1.1 General

Payment items for the work of this contract for which contract lump sum payments will be made are listed in the BIDDING SCHEDULE and described below. All costs for items of work, which are not specifically mentioned to be included in a particular lump sum or unit price payment item, shall be included in the listed lump sum item most closely associated with the work involved. The lump sum price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, meeting safety requirements, tests and reports, and for performing all work required for which separate payment is not otherwise provided.

1.1.2 Lump Sum Items

(1) "Mobilization and Demobilization"

a. Payment

Payment will be made for all costs associated with operations necessary for mobilization and demobilization as specified in Paragraph 1.29 of the Special Contract Requirements.

b. Unit of measure, lump sum: LS.

(2) "Clearing"

a. Payment

Payment will be made for costs associated with operations necessary for clearing as specified in SECTION 02114.

b. Unit of measure, lump sum: LS.

(3) “Crushed Stone, Armorloc Blocks, and Geotextile”

a. Payment

Payment for crushed stone, armorloc blocks, and geotextile; will be made at the contract lump sum price for “Crushed Stone, Armorloc Blocks, and Geotextile”, which price and payment shall constitute full compensation for furnishing crushed stone to include 6” thick base at culverts, armorloc blocks, and geotextile all as specified in SECTIONS 02545 and 02215 as applicable.

b. Unit of measure, lump sum: LS.

(4) “Aggregate Surfacing”

a. Payment

Payment for aggregate surfacing will be made at the contract lump sum price for “Aggregate Surfacing”, which price and payment shall constitute full compensation for furnishing all material and equipment and performing all labor for placing aggregate surfacing; and all other operations incidental thereto; all as specified in SECTION 02546.

b. Unit of measure; lump sum: LS.

(5) “Establishment of Turf”

a. Payment

Payment for establishment of turf will be made at the contract lump sum price for “Establishment of Turf”, which price and payment shall constitute full compensation for preparation of ground surfaces, furnishing and distributing fertilizer and mulch; and performing all operations incidental thereto, all as specified in SECTION 02936. No payment for turfing will be made until acceptance by the Contracting Officer or his/her representative.

b. Unit of measure, lump sum: LS.

(6) “Environmental Protection”

a. Payment

Payment will be made for costs associated with operations necessary for environmental protection as

specified in SECTION 01130 and in the Storm Water Pollution Prevention Plan.

- b. Unit of measure, lump sum: LS.

1.2 UNIT PRICE PAYMENT ITEMS

1.2.1 Unit Price Items

(1) "Excavation"

a. Measurement

A survey of the site for excavation of the ditch in the vicinity of the relief wells will be made in accordance with the SPECIAL CONTRACT REQUIREMENTS entitled "Quantity Surveys-Alternate I," and all measurement of excavation will be based on this survey. The quantity of excavation at the pump site to be paid for will be computed between the ground surface, as determined by the above noted surveys, and the theoretical slope lines and grade lines for such excavation as indicated on the drawings and/or specified herein. No allowance will be made for over-depth excavation, or for the removal of any material outside the required side slope lines.

b. Payment

Payment for excavation, measures as prescribed hereinabove, will be made at the applicable contract unit price per cubic yard for "Excavation", which price and payment shall constitute full compensation for furnishing all materials and equipment and performing all labor for excavation for the pump site in the vicinity of the relief wells; excavation of North and South ditches; for the excavation and replacement of existing embankment; construction of levee ramps; disposal of excavated material including construction of structures for the control of excavated material and waste water; and all other operations incidental thereto as specified in SECTION 02225.

- c. Unit of Measure, cubic yard: CY.

(2) "Relief Wells 10" "

a. Measurement

Relief Wells will be measured for payment by the linear foot of completed well between the ground surface and the elevation at the bottom of the well screen.

b. Payment

Payment for Relief Wells will be made at the contract unit price, per linear foot, for “Relief Wells 10””, which price shall constitute full compensation for construction of relief wells all as specified in SECTION 02708. Wells ordered abandoned by the Contracting Officer before installation of well screen and riser, due to no fault of the Contractor, will be paid for at 50 percent of the contract unit price per linear foot, for “Relief Wells 10””. Wells ordered abandoned by the Contracting Officer after installation of well screen and casing, due to no fault of the Contractor, will be paid for at the full contract unit price for “Relief Wells 10””. No payment will be made for placement or replacement of temporary drilling casings or repair of damage resulting from Contractor operations. No separate payment will be made for relief well screen, risers, gravel pack, grout, development, sand and concrete backfill, discharge or outlet discharge assembly. No payment will be made for any wells or drilled holes that, in the opinion of the Contracting Officer, are abandoned due to Contractor fault or neglect.

c. Unit of measure, linear foot: LF.

(3) “Pumping Test”

a. Measurement

Pumping tests will be measured for payment for each hour, measured to the nearest 15 minutes, of pumping test successfully performed as specified in SECTION 02708, paragraph 3.1.14, and as otherwise directed by the Contracting Officer. Testing time will not include time required to place and remove testing and pumping equipment.

b. Payment

Payment for pumping test will be made at the applicable contract unit price per hour for “Pumping Test: 0005AA First 112 Hours” or “Pumping Test: 0005AB All over 112 Hours”, which price and payment shall constitute full compensation for performing satisfactory pumping tests as specified in SECTION 02708. No payment will be made for pumping tests not successfully completed.

c. Unit of measure, hour: HR.

(4) “Pilot Hole Boring”

a. Payment

Payment will be made at the contract unit price per linear foot for “Pilot Hole Boring”, which price and payment shall constitute full compensation for drilling of the pilot hole borings, taking of samples, sieve analysis tests, and the maintaining of a field boring log as specified in SECTION

02708.

b. Unit of measure, linear feet: LF.

(5) "Guard Posts"

a. Payment

Payment for relief well guard posts will be made at the contract unit price per each for "Guard Posts" which price and payment shall constitute full compensation for furnishing all plant, labor, material including concrete, and equipment for performing all operations necessary to constitute and install the guard posts as shown on the drawings and/or specified in SECTION 02708, paragraph 3.3.

b. Unit of Measure, each: EA

(6) "16" Steel Pipe"

a. Measurement

The 16" Steel Pipe will be measured for payment by the linear foot. Such measurement will be made in the field and be based on the length installed as determined by the Contracting Officer.

b. Payment

The 16" Steel Pipe will be made at the contract unit price per linear foot for "16" Steel Pipe", which price and payment shall constitute full compensation for furnishing and installing the 16" Steel Pipe; incidental excavation required for the installation of 16" Steel Pipe; backfilling around and over the 16" Steel Pipe; installation of locking device and padlock; and all other operations incidental there; all as specified in SECTION 02704.

c. Unit of measure, linear feet: LF.

(7) "Riprap "R-90"

a. Measurement

All materials will be measured for payment by the ton (2,000 pounds) by weighing each truckload to the nearest 0.1 ton, and the final quantity of the whole sum for material will be rounded to the nearest whole ton. The riprap will be measured for payment by being weighed on certified scales acceptable to the Contracting Officer before being placed into the work. Scales shall be of sufficient

length to permit simultaneous weighing of all axle loads and shall be inspected, tested and sealed as directed to assure accuracy within 0.5 percent throughout the range of the scales. Scales shall be checked and certified before any material hauling and rechecked and re-certified whenever a variance is suspected. As a minimum, all weight tickets shall have the contract number or project name, the gross weight, the vehicle identity and empty weight, and the net load weight. Scales that produce this information printed on the weight tickets are preferred. The Contractor has the option to use certified, and otherwise acceptable, scales that are Contractor furnished, quarry/supplier furnished, or commercial/public facilities.

b. Payment

Payment for riprap will be made at the applicable contract unit price per ton for "Riprap "R 90", which price and payment shall include all costs of furnishing, hauling, handling, placement, maintaining the riprap, and embedment for stone protection; all as specified in SECTION 02542.

c. Unit of measure: ton (2,000 lbs.), TN

(8) “Corrugated Metal Pipe, 24-inch”

a. Measurement

The culvert will be measured for payment by the linear foot. Such measurement will be made in the field and will be based on the length installed as determined and approved by the Contracting Officer.

b. Payment

Payment for the culvert will be made at the applicable contract unit price per linear foot for "Corrugated Metal Pipe, 24-inch", which price and payment shall constitute full compensation for furnishing and installing the culvert; incidental excavation required for the installation of the new culvert; backfilling around and over the culvert; and all other operations incidental thereto; all as specified in SECTION 02700 and as applicable to the culvert.

c. Unit of measurement, linear foot: LF.

(9) “Concrete Outlet Structure”

a. Payment

Payment for concrete outlet structure will be made at the contract unit price per each for “Concrete Outlet Structure” which price and payment shall constitute full compensation for furnishing

concrete, formwork, and steel bars and accessories for concrete reinforcement all as specified in SECTION 03307; and structures excavation and backfilling all as specified in SECTION 02225.

b. Unit of Measure, each: EA.

PART 2 PRODUCTS (Not Used)

PART 3 EXECUTION (Not Used)

-- End of Section --

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01130

ENVIRONMENTAL PROTECTION

TABLE OF CONTENTS

PART 1	GENERAL
1.1	DEFINITIONS
1.2	ENVIRONMENTAL PROTECTION REQUIREMENTS
1.2.1	Environmental Protection Plan
1.2.1.1	Protection of Features
1.2.1.2	Procedures
1.2.1.3	Permit or License
1.2.1.4	Drawings
1.2.1.5	Environmental Monitoring Plans
1.2.1.6	Traffic Control Plan
1.2.1.7	Surface and Ground Water
1.2.1.8	Work Area Plan
1.3	SUBCONTRACTORS
1.4	PERMITS OBTAINED BY CORPS OF ENGINEERS
1.5	REGULATORY REQUIREMENTS
PART 2	PRODUCTS (NOT APPLICABLE)
PART 3	EXECUTION
3.1	PROTECTION OF ENVIRONMENTAL RESOURCES
3.1.1	Protection of Land Resources
3.1.1.1	Work Area Limits
3.1.1.2	Protection of Landscape
3.1.1.3	Reduction of Exposure of Unprotected Erodible Soils
3.1.1.4	Temporary Protection of Disturbed Areas
3.1.1.5	Erosion and Sedimentation Control Devices
3.1.1.6	Location of Contractor Facilities
3.1.1.7	Borrow Areas on Government Property (Not Applicable)
3.1.1.8	Disposal Areas on Government Property
3.1.1.9	Temporary Excavation and Embankments
3.1.1.10	Disposal of Solid Wastes
3.1.1.11	Disposal of Chemical Wastes
3.1.1.12	Disposal of Discarded Materials

- 3.2 HISTORICAL, ARCHAEOLOGICAL AND CULTURAL RESOURCES
- 3.3 PROTECTION OF WATER RESOURCES
 - 3.3.1 Cofferdam and Diversion Operations
 - 3.3.2 Stream Crossings
 - 3.3.3 Monitoring of Water Areas Affected by Construction Activities
- 3.4 PROTECTION OF FISH AND WILDLIFE RESOURCES (Not Applicable)
- 3.5 PROTECTION OF AIR RESOURCES
 - 3.5.1 Particulate
 - 3.5.2 Hydrocarbons and Carbon Monoxide
 - 3.5.3 Odors
 - 3.5.4 Monitoring Air Quality
- 3.6 INSPECTION
- 3.7 POST CONSTRUCTION CLEANUP
- 3.8 RESTORATION OF LANDSCAPE DAMAGE
- 3.9 MAINTENANCE OF POLLUTION FACILITIES
- 3.10 TRAINING OF CONTRACTOR PERSONNEL IN POLLUTION CONTROL
- 3.11 REPORTING OF POLLUTION SPILLS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01130

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

1.1 DEFINITIONS

For the purpose of this specification, environmental pollution and damage is defined as the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to man; or degrade the utility of the environment for aesthetic, cultural and/or historical purposes. The control of environmental pollution and damage requires consideration of air, water, and land, and includes management of visual aesthetics, noise, solid waste, radiant energy and radioactive materials, as well as other pollutants.

1.2 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection. Plan for and provide environmental protective measures to control pollution that develops during normal construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Comply with Federal, State, and local regulations pertaining to the environment, including but not limited to water, air, and noise pollution.

1.2.1 Environmental Protection Plan

Within 15 days after receipt of Notice of Award of the contract, the Contractor shall submit in writing an Environmental Protection Plan and, prior to starting work, meet with representatives of the Contracting Officer to develop mutual understanding relative to compliance with this provision and administration of the environmental protection program. Approval of the Contractor's plan will not relieve the Contractor of his responsibility for adequate and continuing control of pollutants and other environmental protection measures. The Government reserves the right to make changes in his environmental protection plan and operations as necessary to maintain satisfactory environmental protection performance. The Environmental Protection Plan shall include but not be limited to the following:

1.2.1.1 Protection of Features

The Contractor shall determine methods for the protection of features to be preserved within authorized work areas. The Contractor shall prepare a listing of methods to protect resources needing protection, i.e., trees, shrubs, vines, grasses and ground cover, landscape features, air and water quality, fish and wildlife, soil, historical, archaeological and cultural resources.

1.2.1.2 Procedures

The Contractor shall implement procedures to provide the required environmental protection and to comply with the applicable laws and regulations. The Contractor shall set out the procedures to be followed to correct pollution of the environment due to accident, natural causes or failure to follow the procedures set out in accordance with the Environmental Protection Plan.

1.2.1.3 Permit or License

The Contractor shall obtain all needed permits or licenses.

1.2.1.4 Drawings

The Contractor shall include drawings showing locations of any proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, stockpiles of earth materials, and disposal areas for excess earth material and unsatisfactory earth materials.

1.2.1.5 Environmental Monitoring Plans

The Contractor shall include environmental monitoring plans for the job site which incorporate land, water, air and noise monitoring.

1.2.1.6 Traffic Control Plan

The Contractor shall include a traffic control plan for the job site.

1.2.1.7 Surface and Ground Water

The Contractor shall establish methods of protecting surface and ground water during construction activities. Anytime barge mounted hydraulic machinery requiring large storage capacities of hydraulic fluid, (i.e. Liebherr Trackhoe, Demag Trackhoe, etc.) is utilized, a plan to prevent discharge of fluids into the river in the event of a broken hydraulic line will be submitted to the Contracting Officer's Representative for approval.

1.2.1.8 Work Area Plan

The Contractor shall include a work area plan showing the proposed activity in each portion of the area and identifying the areas of limited use or nonuse. The plan shall include measures for marking the limits of use areas.

1.3 SUBCONTRACTORS

Assurance of compliance with this section by subcontractors will be the responsibility of the Contractor.

1.4 PERMITS OBTAINED BY CORPS OF ENGINEERS

This section supplements the Contractor's responsibility under the contract clause PERMITS AND RESPONSIBILITIES to the extent that the Government has already obtained some environmental permits. The Government has obtained permits for erosion control (SWPPP) and water quality certification for deposition into wetlands (Section 404). The Contractor shall comply with the terms and conditions of these permits. These conditions have been incorporated into these specifications. The Contractor shall obtain all other needed permits or licenses.

1.5 REGULATORY REQUIREMENTS

The Contractor shall comply with all state regulatory and statutory requirements.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 PROTECTION OF ENVIRONMENTAL RESOURCES

The environmental resources within the project boundaries and those affected outside the limits of permanent work under this contract shall be protected during the entire period of this contract. The Contractor shall confine his activities to areas defined by the contract drawings or specifications. Environmental protection shall be as stated in the following subparagraphs.

3.1.1 Protection of Land Resources

Prior to the beginning of any construction, the Contracting Officer will identify all land resources to be preserved within the Contractor's work area. The Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, top soil, and land forms without special permission from the Contracting Officer. No ropes, cables, or guys shall be fastened to or attached to any trees for anchorage unless specifically authorized. Where such

special emergency use is permitted, the Contractor shall provide effective protection for land and vegetation resources at all times as defined in the following subparagraphs.

3.1.1.1 Work Area Limits

Prior to any construction, the Contractor shall mark the areas where no work is to be performed under this contract. Isolated areas within the general work area which are to be saved and protected shall also be marked or fenced. Monuments and markers shall be protected before construction operations commence and during all construction operations. Where construction operations are to be conducted during darkness, the markers shall be visible during darkness. The Contractor shall convey to his personnel the purpose of marking and/or protection of all necessary objects.

3.1.1.2 Protection of Landscape

Trees, shrubs, vines, grasses, land forms and other landscape features to be preserved, indicated and defined on the drawings submitted by the Contractor as a part of the Environmental Protection Plan, shall be clearly identified by marking, fencing, or wrapping with boards, or any other approved techniques.

3.1.1.3 Reduction of Exposure of Unprotected Erodible Soils

Earthwork brought to final grade shall be finished as indicated and specified. Side slopes and back slopes shall be protected as soon as practicable upon completion of rough grading. All earthwork shall be planned and conducted to minimize the duration of exposure of unprotected soils. Except in instances where the constructed feature obscures borrow areas, quarries and waste material areas, these areas shall not initially be cleared in total. Clearing of such areas shall progress in reasonably sized increments as needed to use the areas developed as approved by the Contracting Officer.

3.1.1.4 Temporary Protection of Disturbed Areas

Such methods as necessary shall be utilized to effectively prevent erosion and control sedimentation, including but not limited to the following:

Retardation and Control of Runoff

Runoff from the construction site shall be controlled by construction of diversion ditches, benches, and berms to retard and divert runoff to protected drainage courses, and the Contractor shall also utilize any measures required by area-wide plans approved under Paragraph 208 of the Clean Water Act.

3.1.1.5 Erosion and Sedimentation Control Devices

The Contractor shall construct or install all temporary and permanent erosion sedimentation control features. Temporary erosion and sediment control measures such as berms, dikes, drains, sedimentation basin, grassing and mulching shall be maintained until permanent drainage and erosion control facilities are completed and operative.

3.1.1.6 Location of Contractor Facilities

The Contractor's field offices, staging areas, stockpiles, storage, and temporary buildings shall be placed in areas designated on the contract drawings and approved by the Contracting Officer. Temporary movement or relocation of Contractor facilities shall be made only on approval by the Contracting Officer.

3.1.1.7 Borrow Areas on Government Property (Not Applicable)

3.1.1.8 Disposal Areas on Government Property

Disposal areas on Government property shall be managed and controlled to limit material to areas designated on the contract drawings and prevent erosion of soil or sediment from entering nearby water courses or lakes. Disposal areas shall be developed in accordance with the grading plan indicated on the contract drawings.

3.1.1.9 Temporary Excavation and Embankments

Temporary excavation and embankments shall be controlled to protect adjacent areas from contamination.

3.1.1.10 Disposal of Solid Wastes

Solid wastes (excluding clearing debris) shall be placed in containers which are emptied on a regular schedule. All handling and disposal shall be conducted to prevent contamination. The Contractor shall transport all solid waste off Government property and dispose of it in compliance with Federal, State, and local requirements for solid waste disposal.

3.1.1.11 Disposal of Chemical Wastes

Chemical wastes shall be stored in corrosion resistant containers, removed from the work area and disposed of in accordance with Federal, State, and local regulations.

3.1.1.12 Disposal of Discarded Materials

Discarded materials other than those which can be included in the solid waste category shall be handled as directed by the Contracting Officer.

3.2 HISTORICAL, ARCHAEOLOGICAL AND CULTURAL RESOURCES

Existing historical, archaeological and cultural resources within the Contractor's work area will be so designated by the Contracting Officer and precautions shall be taken by the Contractor to preserve all such resources as they existed at the time they were pointed out to the Contractor. The Contractor shall install all protection for these resources so designated on the contract drawings and shall be responsible for their preservation during this contract. If during construction items of apparent archaeological or historical interest are discovered, they shall be left undisturbed and the Contractor shall report the find immediately to the Contracting Officer.

3.3 PROTECTION OF WATER RESOURCES

The Contractor shall keep construction activities under surveillance, management and control to avoid pollution of surface and ground waters. Special management techniques as set out below shall be implemented to control water pollution by the listed construction activities which are included in this contract.

3.3.1 Cofferdam and Diversion Operations

The Contractor shall plan his operations and perform all work necessary to minimize adverse impact or violation of the water quality standard. Construction operations for dewatering, removal of cofferdams, tailrace excavation, and tunnel closure shall be controlled at all times to limit impact of water turbidity on the habitat for wildlife and impacts on water quality for downstream use.

3.3.2 Stream Crossings

Stream crossings shall be controlled during construction. Crossings shall provide movement of materials or equipment which do not violate water pollution control standards of the Federal, State or local government.

3.3.3 Monitoring of Water Areas Affected by Construction Activities

Monitoring of water areas affected by construction activities shall be the responsibility of the Contractor. All water areas affected by construction activities shall be monitored by the Contractor.

3.4 PROTECTION OF FISH AND WILDLIFE RESOURCES (Not Applicable)

3.5 PROTECTION OF AIR RESOURCES

The Contractor shall keep construction activities under surveillance, management and control to minimize pollution of air resources. All activities, equipment, processes, and work operated or performed by the Contractor in accomplishing the specified construction shall be in strict accordance with the laws of the applicable state air pollution regulations and all Federal emission and performance laws and standards. Special management techniques as set out below shall be

implemented to control air pollution by the construction activities which are included in the contract.

3.5.1 Particulate

Dust particles, aerosols, gaseous by-products from all construction activities, processing and preparation of materials, such as from asphaltic batch plants, shall be controlled at all times, including weekends, holidays and hours when work is not in progress. The Contractor shall maintain all excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, areas of excess excavated material, and all other work areas within or outside the project boundaries free from particulate which would cause the air pollution standards mentioned in the paragraph "PROTECTION OF AIR RESOURCES" to be exceeded or which would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, light bituminous treatment, baghouse, scrubbers, electrostatic precipitators or other methods will be permitted to control particulate in the work area. Sprinkling, to be efficient, must be repeated at such intervals as to keep the disturbed area damp at all times. The Contractor must have sufficient equipment available to accomplish this task. Particulate control shall be performed as the work proceeds and whenever a particulate nuisance or hazard occurs.

3.5.2 Hydrocarbons and Carbon Monoxide

Hydrocarbons and carbon monoxide emissions from equipment shall be controlled to Federal and State allowable limits at all times.

3.5.3 Odors

Odors shall be controlled at all times for all construction activities, processing and preparation of materials.

3.5.4 Monitoring Air Quality

Monitoring of air quality shall be the responsibility of the Contractor. All air areas affected by the construction activities shall be monitored by the Contractor.

3.6 INSPECTION

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with the Contractor's environmental protection plan. The Contractor shall, after receipt of such notice, inform the Contracting Officer of proposed corrective action and take such action as may be approved. If the Contractor fails to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No time extensions will be granted or costs or damages allowed to the Contractor for any such suspension.

3.7 POST CONSTRUCTION CLEANUP

The Contractor shall clean up all area(s) used for construction.

3.8 RESTORATION OF LANDSCAPE DAMAGE

The Contractor shall restore all landscape features damaged or destroyed during construction operations outside the limits of the approved work areas. Such restoration shall be in accordance with the plans submitted for approval by the Contracting Officer.

3.9 MAINTENANCE OF POLLUTION FACILITIES

The Contractor shall maintain all constructed facilities and temporary pollution control devices for the duration of the contract or for that length of time construction activities create the particular pollutant.

3.10 TRAINING OF CONTRACTOR PERSONNEL IN POLLUTION CONTROL

The Contractor shall train his personnel in all phases of environmental protection. The training shall include methods of detecting and avoiding pollution, familiarization with pollution standards, both statutory and contractual, and installation and care of facilities (vegetative covers and instruments required for monitoring purposes) to insure adequate and continuous environmental pollution control.

3.11 REPORTING OF POLLUTION SPILLS

In the event that an oil spill or chemical release occurs during the performance of this contract, the Contractor is required to contact the National Response Center, telephone number 1-800-424-8802 as soon as possible, or if telephone communication is not possible, the nearest U.S. Coast Guard office may be contacted by radio to report the spill, (33 CFR 153.203). The Contractor shall comply with any instructions from the responding agency concerning containment and/or cleanup of the spill.

-- End of Section --

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01451

CONTRACTOR QUALITY CONTROL

TABLE OF CONTENTS

PART 1	GENERAL
1.1	REFERENCES
1.2	PAYMENT
PART 2	PRODUCTS (NOT APPLICABLE)
PART 3	EXECUTION
3.1	GENERAL
3.2	QUALITY CONTROL PLAN
3.2.1	General
3.2.2	Content of the CQC Plan
3.2.3	Acceptance of Plan
3.2.4	Notification of Changes
3.3	COORDINATION MEETING
3.4	QUALITY CONTROL ORGANIZATION
3.4.1	CQC System Manager
3.4.2	CQC Staff
3.4.3	Additional Requirement
3.5	SUBMITTALS
3.6	CONTROL
3.6.1	Preparatory Phase
3.6.2	Initial Phase
3.6.3	Follow-up Phase
3.6.4	Additional Preparatory and Initial Phases
3.7	TESTS
3.7.1	Testing Procedure
3.7.2	Testing at Validated Laboratories
3.7.2.1	Laboratory Validation
3.7.2.2	Capability Check
3.7.2.3	Capability Recheck
3.7.3	On-Site Laboratory
3.7.4	Furnishing or Transportation of Samples for Testing
3.8	COMPLETION INSPECTION

- 3.9 DOCUMENTATION
- 3.10 NOTIFICATION OF NONCOMPLIANCE

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01451

CONTRACTOR QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740	Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E 329	Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause entitled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both on-site and off-site, and shall be keyed to the proposed construction sequence.

3.2 QUALITY CONTROL PLAN

3.2.1 General

The Contractor shall furnish for review by the Government, not later than 15 calendar days after receipt of Notice of Award of the contract the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause entitled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, test, records, and forms to be used. The Government will consider an interim plan for the first 15 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

3.2.2 Content of the CQC Plan

The CQC plan shall include, as a minimum, the following to cover all construction operations, both on-site and off-site, including work by subcontractors, fabricators, suppliers, and purchasing agents:

a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC system manager who shall report to the project manager or someone higher in the Contractor's organization. Project manager in this context shall mean the individual with responsibility for the overall management of the project including quality and production.

b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.

c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters will also be furnished to the Government.

d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, off-site fabricators, suppliers, and purchasing agents.

e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, testing laboratory, and person responsible for each test. (Laboratory facilities will be approved by the Contracting Officer.)

f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.

g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures will establish verification that identified deficiencies have been corrected.

h. Reporting procedures, including proposed reporting formats.

i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks and has separate control requirements. It could be identified by different trades or disciplines, or it could be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable feature under a particular section. This list will be agreed upon during the coordination meeting.

3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.4 Notification of Changes

After acceptance of the QC plan, the Contractor shall notify the Contracting Officer in writing a minimum of seven calendar days prior to any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the Quality Control Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both on-site and off-site work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 CQC System Manager

The Contractor shall identify an individual within his organization at the worksite who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. This CQC System Manager shall be subject to acceptance by the Contracting Officer. The CQC System Manager shall be assigned as System Manager but may have other duties in addition to quality control.

3.4.2 CQC Staff

A staff shall be maintained under the direction of the CQC System Manager to perform all CQC activities. An alternate will be identified to serve in the absence of the CQC System Manager. The staff must be of sufficient size to ensure adequate CQC coverage of all work phases, work shifts, and work crews involved in the construction. These personnel may perform other duties, but must be fully qualified by experience and technical training to perform their assigned CQC responsibilities and must be allowed sufficient time to carry out these responsibilities. The CQC plan will clearly state the duties and responsibilities of each staff member. All CQC Staff members or replacements shall be subject to acceptance by the Contracting Officer.

3.4.3 Additional Requirement

In addition to the above requirements, the CQC System Manager and his/her alternate shall complete the course entitled "Construction Quality Management for Contractors". This course is generally offered every quarter starting with the month of February. For further details and for the actual class schedule see the following website http://155.76.117.11/conops/const_quality.htm. This course is periodically offered by the Memphis District as well as other Corps Districts.

3.5 SUBMITTALS

The CQC organization shall be responsible for certifying that all submittals are in compliance with the contract requirements.

3.6 CONTROL

The controls shall include at least three phases of control to be conducted by the CQC System Manager for all definable features of work, as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work and shall include:

- a. A review of each paragraph of applicable specifications.
- b. A review of the contract drawings.

- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. A check to assure that provisions have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for constructing the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that phase of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. The Government shall be notified at least 24 hours in advance of beginning any of the required action of the preparatory phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of preliminary work to ensure that it is in compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verification of full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with sample panels is appropriate.
- d. Resolve all differences.

e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.

f. The Government shall be notified at least 24 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.

g. The initial phase should be repeated for each new crew to work on-site, or any time acceptable specified quality standards are not being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure continuing compliance with contract requirements, including control testing, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon or conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

As determined by the Government, additional preparatory and initial phases may be conducted on the same definable features of work if the quality of on-going work is unacceptable, if there are changes in the applicable CQC staff, on-site production supervision or work crew, if work on a definable feature is resumed after a substantial period of inactivity, or if other problems develop.

3.7 TESTS

3.7.1 Testing Procedure

The Contractor shall perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site in accordance with paragraph 3.7.2 below. The Contractor shall perform the following activities and record and provide the following data:

- a. Verify that testing procedures comply with contract requirements.
- b. Verify that facilities and testing equipment are available and comply with testing standards.
- c. Check test instrument calibration data against certified standards.

d. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.

e. Results of all tests taken, both passing and failing tests, will be recorded on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test will be given. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. An information copy of tests performed by an off-site or commercial test facility will be provided directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.

3.7.2 Testing at Validated Laboratories

3.7.2.1 Laboratory Validation.

All testing of soil, gravel, aggregate, stone, concrete, and asphalt shall be performed by a testing laboratory validated by the Material Testing Center (MTC) of the Corps of Engineers. Refer to the MTC website <http://www.wes.army.mil/SL/MTC/ValStatesTbl.htm> for a complete and current list of validated commercial laboratories. If the Contractor proposes to use a commercial laboratory that is not validated or set up an on-site laboratory, he shall make arrangements for validation by contacting the Material Testing Center at Waterways Experiment Station, Vicksburg, Mississippi, telephone number: 601-634-2496 or 601-634-3610, www.wes.army.mil/SL/MTC/inspection.htm. The Government will not be responsible for any cost associated with the validation of laboratories that are not currently validated. The validation process could take 60 to 90 days or more. The Contractor shall be responsible for determining the amount of time required for the validation of the proposed laboratory and accounting for this event in his progress schedule. If the Contractor elects to use a non-validated laboratory, work requiring testing shall not commence until the laboratory has been validated by MTC.

3.7.2.2 Capability Check

The Contracting Officer reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329.

3.7.2.3 Capability Recheck

If the selected laboratory fails the capability check, the Contractor will be assessed a charge to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the contract amount due the Contractor. There will be no extension of time allowed due to necessity to perform capability rechecks.

3.7.3 On-site Laboratory

The Contracting Officer reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

3.7.4 Furnishing or Transportation of Samples for Testing

Costs incidental to the transportation of samples or materials will be borne by the contractor. Samples of materials for test verification and acceptance testing by the government shall be delivered by the contractor to a location specified by the Contracting Officer.

3.8 COMPLETION INSPECTION

At the completion of all work or any increment thereof established by a completion time stated in the Special Contract Requirements entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the CQC System Manager shall conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings and specifications. Such a list of deficiencies shall be included in the CQC documentation, as required by paragraph DOCUMENTATION below, and shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected and so notify the Government. These inspections and any deficiency corrections required by this paragraph will be accomplished within the time stated for completion of the entire work or any particular increment thereof if the project is divided into increments by separate completion dates.

3.9 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of sub-contractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase should be identified (Preparatory, Initial, Follow-up). List deficiencies noted along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.

- f. Submittals reviewed, with contract reference, by whom, and action taken.
- g. Off-site surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date(s) covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every seven days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the worksite, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

--End of Section--

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01452

PROJECT SIGNS, BARRICADES, AND TRAFFIC CONTROL SIGNS

TABLE OF CONTENTS

PART 1 GENERAL

1.1 SCOPE

1.2 PROJECT SIGNS

1.3 BARRICADES AND TRAFFIC CONTROL SIGNS

1.4 PAYMENT

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

SECTION 01452

PROJECT SIGNS, BARRICADES, AND TRAFFIC CONTROL SIGNS

PART 1 GENERAL

1.1 SCOPE.

The work covered by this section consists of furnishing, erecting, maintaining, and removing project signs, barricades, and traffic control signs.

1.2 PROJECT SIGNS.

The Contractor shall furnish, erect, and maintain two double-faced project sign, at designated locations specified by the Contracting Officer. The signs shall be constructed of 3/4-inch marine-grade plywood or 22 gage metal, mounted on a substantial framework of 2-inch material. Size, lettering, color and paint shall conform to the details shown on the drawing "Temporary Project Sign" included at the end of this section. Upon request, the Government will furnish without cost to the Contractor four decals of the Engineer Castle. The signs shall be erected as soon as practicable, but not later than 15 calendar days after the date established for commencement of work. The sign shall be removed upon completion of all other construction work under the contract and will become the property of the Contractor.

1.3 BARRICADES AND TRAFFIC CONTROL SIGNS.

Barricades and traffic control signs shall be those as recommended by the Contracting Officer and conform to the Manual on Uniform Traffic Control Devices for Streets and Highways, Current Edition. Refer to Specification Section 00800, Paragraph 1.35, Maintenance of Traffic, for further details.

1.4 PAYMENT.

No separate payment will be made for erection, maintenance or removal of the project sign, barricades, or traffic control signs. All costs in connection therewith will be considered an incidental obligation of the Contractor.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

--End of Section--

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01452

PROJECT SIGNS, BARRICADES, AND TRAFFIC CONTROL SIGNS

TABLE OF CONTENTS

PART 1 GENERAL

1.1 SCOPE

1.2 PROJECT SIGNS

1.3 BARRICADES AND TRAFFIC CONTROL SIGNS

1.4 PAYMENT

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

SECTION 01452

PROJECT SIGNS, BARRICADES, AND TRAFFIC CONTROL SIGNS

PART 1 GENERAL

1.1 SCOPE.

The work covered by this section consists of furnishing, erecting, maintaining, and removing project signs, barricades, and traffic control signs.

1.2 PROJECT SIGNS.

The Contractor shall furnish, erect, and maintain two double-faced project sign, at designated locations specified by the Contracting Officer. The signs shall be constructed of 3/4-inch marine-grade plywood or 22 gage metal, mounted on a substantial framework of 2-inch material. Size, lettering, color and paint shall conform to the details shown on the drawing "Temporary Project Sign" included at the end of this section. Upon request, the Government will furnish without cost to the Contractor four decals of the Engineer Castle. The signs shall be erected as soon as practicable, but not later than 15 calendar days after the date established for commencement of work. The sign shall be removed upon completion of all other construction work under the contract and will become the property of the Contractor.

1.3 BARRICADES AND TRAFFIC CONTROL SIGNS.

Barricades and traffic control signs shall be those as recommended by the Contracting Officer and conform to the Manual on Uniform Traffic Control Devices for Streets and Highways, Current Edition. Refer to Specification Section 00800, Paragraph 1.35, Maintenance of Traffic, for further details.


1.4 PAYMENT.

No separate payment will be made for erection, maintenance or removal of the project sign, barricades, or traffic control signs. All costs in connection therewith will be considered an incidental obligation of the Contractor.


PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)


--End of Section--



ELEVATION



ELEVATION



SECTION A-A

SPECIFICATIONS

- SIGN PANEL SHALL BE 4' x 6' x 3/4" MARINE PLYWOOD OR 22 GAGE SHEET METAL.
- POSTS AND BRACING SHALL BE TREATED, NO.1 GRADE YELLOW PINE.
- ALL EXPOSED SURFACES SHALL BE GIVEN ONE COAT OF LINSEED OIL AND WIPED PRIOR TO PRIMING.
- ALL EXPOSED SURFACES SHALL BE GIVEN ONE COAT OF WHITE AS PRIMER. SECOND COAT SHALL BE COMMUNICATIONS RED ON LEFT AND WHITE ELSEWHERE.
- THE LEFT SECTION SHALL BE RED WITH WHITE LEGEND. THE RIGHT SECTION SHALL BE WHITE WITH BLACK LEGEND.
- PAINT SHALL BE BENJAMIN MOORE NO. 120-60 POLY-SILICONE ENAMEL OR APPROVED
- ALL LETTERING SHALL BE 1/4" EXCEPT FOR THE WORDS "US Army Corps of Engineers" AND THE PROJECT TITLE. THE WORDS "US Army Corps of Engineers" SHALL BE 1/2" TALL. THE PROJECT TITLE LETTERING SHALL BE A MINIMUM OF 1/2" TALL AND A MAXIMUM OF 3/2" TALL. THE LETTERING SIZE SHALL BE CHOSEN SUCH THAT LARGEST POSSIBLE LETTERS ARE USED WITHOUT EXCEEDING A MAXIMUM LINE LENGTH OF 42". THE NUMBER OF LINES IN THE PROJECT TITLE SHALL MATCH THAT SHOWN ON THE COVER SHEET OF THE SPECIFICATIONS.

SCALE: NONE

JUNE 1998

U.S. ARMY ENGINEER DISTRICT, MEMPHIS
CORPS OF ENGINEERS
MEMPHIS, TENNESSEE

**TEMPORARY
PROJECT SIGN**

DIVISION 2 - SITE WORK

SECTION 02114

CLEARING

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
PART 2	PRODUCTS (Not Applicable)
PART 3	EXECUTION
3.1	CLEARING
3.1.1	General
3.1.2	Miscellaneous
3.2	DISPOSAL OF CLEARED MATERIALS
3.2.1	General
3.2.2	Burning
3.2.3	Removal from Site
3.3	SMALL EQUIPMENT

SECTION 02114

CLEARING

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, material and equipment, and performing all operations required for proper execution of the clearing work as specified herein. Such work includes clearing and disposal of debris therefrom, and performing all work incidental thereto.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with the contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

- (1) Clearing. Location, heights, limits.
- (2) Damage to Trees to be left standing. Shall be kept to a minimum.
- (3) Disposal of Cleared Materials. All felled trees and debris shall be removed and disposed of off-site.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 CLEARING

3.1.1 General

Clearing shall consist of the removal of all trees, standing or felled in previous cuttings, snags, abaned piling, vines, stumps from previous cuttings, rootwads, bushes, partially buried logs, debris from clearing operations, driftwood, and other debris in areas and to the extent specified

hereinbelow. Clearing shall be performed by hand or by the use of small equipment as approved by the Contracting Officer. See small equipment list, paragraph 3.3 below.

3.1.2 Miscellaneous

Clearing shall be only that necessary for construction purposes and operation of equipment. At the installation site of each individual relief well, trees and limbs of nearby trees that restrict boom operation shall be removed subject to the approval of the Contracting Officer. Optimum effort shall be exercised by the Contractor to preserve as many trees as practicable outside the required clearing areas at each well site. At the construction site where (2) two 16" steel pipes go over the levee, the embankment area from South ditch STATION 8+00 to STATION 23+00, and the drainage ditch areas, the sod shall be removed, stockpiled and reused or disposed of as directed by the Contracting Officer.

3.2 DISPOSAL OF CLEARED MATERIALS

3.2.1 General

All debris resulting from clearing operations on this contract shall be disposed of by burning or removal from the site

3.2.2 Burning.

The Contractor shall comply with the applicable pollution restrictions of the State of Mississippi. Subject to such restrictions and obtaining any permit which may be required by said State, the Contractor may burn material within the contract area, and at any time within the contract period. If the Contractor elects to burn, any remaining root wads or unburned wood shall be removed from the site. Burning operations shall be conducted so as to prevent damage to standing timber or other flammable growth. The Contractor will be responsible for any damage to life and/or property resulting from fires that are started by his employees or as a result of his operations. The Contractor shall furnish, at the site of burning operations, adequate fire fighting equipment to properly equip his personnel for fighting fires. Fires shall be guarded at all times and shall be under constant surveillance until they have been extinguished.

3.2.3 Removal from Site

The Contractor shall remove all debris resulting from clearing operations from the site of the work. Such disposal shall comply with all applicable Federal, State and local laws. The Contractor may, at his option retain for his own use or disposal by sale or otherwise any such materials of value. The Government assumes no responsibility for the protection or safekeeping of any materials retained by the Contractor. Such materials shall be removed from the site of the work before the date of completion of the work under this contract. The locations and manner of placement of clearing debris on the right-of-way by the Contractor for his convenience prior to removal of the debris from the site of the work shall be subject to the approval of the Contracting Officer.

3.3 SMALL EQUIPMENT

Small equipment shall be similar in size to the following:

- D 4 Caterpillar
- Log Skidder (John Deere)
- Small Excavator (Hydraulic) with Grapple
- Bob Truck (Farm Type)
- Chain Saws
- 215 Cat Excavator
- 1 ½ Ton Truck

.
--End of Section--

DIVISION 2 - SITE WORK

SECTION 02215

GEOTEXTILE (FILTER FABRIC)

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATION
PART 2	PRODUCTS
2.1	GEOTEXTILE
2.1.1	General
2.1.2	Seams
2.1.3	Acceptance Requirements
2.2	SHIPMENT AND STORAGE
PART 3	EXECUTION
3.1	BASE PREPARATION
3.2	SECURING PINS
3.3	INSTALLATION

SECTION 02215

GEOTEXTILE (FILTER FABRIC)

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, material, and equipment and performing all operations required for furnishing, hauling, and placing the geotextile complete, as specified herein, and maintaining the geotextile until applicable cover is completed and accepted.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Material

Conforms to specifications.

(2) Placement

Location, foundation, limits, anchoring, laps, finished surfaces.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATION

The following publication of the issues listed below, but referred to thereafter by basic designation only, forms a part of this specification to the extent indicated by the references thereto:

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) PUBLICATIONS.

D 1683

Failure in Sewn Seams of Woven Fabrics

D 4439	Terminology for Geosynthetics
D 4491	Water Permeability of Geotextiles by Permittivity
D 4533	Trapezoid Tearing Strength of Geotextiles
D 4632	Grab Breaking Load and Elongation of Geotextiles
D 4751	Apparent Opening Size of a Geotextile
D 4833	Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products
D 4886	Abrasion Resistance of Geotextiles (Sand Paper/Sliding Block Method)

PART 2 PRODUCTS

2.1 GEOTEXTILE

2.1.1 General

The geotextile shall be a non-woven pervious sheet of plastic yarn as defined by ASTM D 4439. The geotextile shall meet the physical requirements listed in Table No. 1, inserted at the end of this section. The geotextile shall provide an Equivalent Opening Size (EOS) no finer than the U.S. Standard Sieve No. 100 and no coarser than the U.S. Standard Sieve No. 50. The geotextile shall consist of a long-chain synthetic polymer composed of at least 85 percent by weight of ester, propylene, ethylene, amide or vinylidene-chloride, and shall contain stabilizers and/or inhibitors added to the base plastic if necessary to make the filaments resistant to deterioration due to ultra-violet and heat exposure. The edges of the geotextile shall be finished to prevent the outer yarn from pulling away from the geotextile.

2.1.2 Seams

The seams of the geotextile shall be sewn with thread of a material meeting the chemical requirements given above for geotextile yarn or shall be bonded by cementing or by heat. The sheets of geotextile shall be attached at the factory or another approved location, if necessary, to form sections using the manufacturer's standard width or a width of 12-feet, whichever is greater. Seams shall be tested in accordance with method ASTM D 1683, using 1-inch square jaws and 12 inches per minute constant rate of traverse. The strengths shall be not less than 90 percent of the required tensile strength (Table No. 1) of the unaged geotextile in any principal direction. "Table No. 1 - Physical Requirements" is at the end of this section.

2.1.3 Acceptance Requirements

All brands of geotextile and all seams to be used will be accepted on the following basis. The Contractor shall furnish the Contracting Officer, in duplicate, a mill certificate or affidavit signed by a legally authorized official from the company manufacturing the geotextile. The mill certificate or affidavit shall attest that the geotextile meets the chemical, physical and manufacturing requirements stated in this specification. If requested by the Contracting Officer, the Contractor shall provide to the Government geotextile samples for testing to determine compliance with any or all of the requirements in this specification. When samples are to be provided, they shall be submitted a minimum of 60 days prior to the beginning of installation of the same geotextile. All samples provided shall be from the same production lot as will be supplied for the contract, and shall be the full manufactured width of the geotextile by at least 10 ft. long, except that samples for seam strength may be a full width sample folded over and the edges stitched for a length of at least 5 feet. Samples submitted for testing shall be identified by manufacturer's lot designation.

2.2 SHIPMENT AND STORAGE

During all periods of shipment and storage, the geotextile shall be protected from direct sunlight, ultra-violet rays, temperatures greater than 140 degrees F, mud, dirt, dust and debris. To the extent possible, the geotextile shall be maintained wrapped in a heavy duty protective covering.

PART 3 EXECUTION

3.1 BASE PREPARATION

Areas on which geotextile is to be placed shall be dressed to remove humps and depressions within the slope lines and to provide relatively smooth and uniform surfaces to conform to the cross sections shown on the drawings and as described henceforth in this paragraph. Immediately prior to placing the geotextile, the prepared base will be inspected by the Contracting Officer and no geotextile shall be placed until those areas have been approved.

3.2 SECURING PINS

Securing pins shall be 3/16-inch in diameter, steel, pointed at one end and fabricated with a head to retain a steel washer having an outside diameter of no less than 1.5 inches. The length of the pins shall be no less than 18 inches. Securing pins with washers shall be inserted through both strips of overlapped cloth at not greater than 2 foot intervals along a line through the midpoint of the overlap.

Additional pins shall be installed as necessary to prevent any slippage of the filter cloth regardless of location. Geotextile placed against riprap may be held in place using riprap stones.

3.3 INSTALLATION

The geotextile shall be placed in the locations shown on the drawings. At the time of installation, geotextile will be rejected if it has defects, rips, holes, flaws, deterioration or damage incurred during manufacture, transportation or storage. The geotextile shall be laid smooth and free of tension, folds, wrinkles or creases. The strips shall be placed to provide a minimum width of 12

inches of overlap for each joint. The geotextile shall be secured as specified in 3.2 above and any additional securing regardless of location shall be made as necessary to prevent any slippage of the geotextile. The geotextile shall be protected at all times during construction from contamination by surface runoff and any geotextile so contaminated shall be removed and replaced with uncontaminated geotextile. The geotextile shall be installed perpendicular to the slopes as shown on the drawings. Any geotextile damaged during its installation or during placement of the specified material upon or against the geotextile shall be replaced by the Contractor at no cost to the Government. The work shall be scheduled so that the covering of the geotextile with a layer of the specified material is accomplished within 7 days after placement of the geotextile. Failure to comply will require replacement of geotextile. The geotextile shall be protected from damage due to the placement of material thereon by limiting the height of drop of the material. Before placement of material thereon, the Contractor shall demonstrate that the placement technique will prevent damage to the geotextile. Also, after installation of geotextile, no construction equipment of any type will be allowed on the geotextile surface.

-- End of Section --

Table No. 1 - Physical Requirements

<u>Physical Property</u>	<u>Test Procedure</u>	<u>Applicable Values++</u>
Geotextile Permeability (Kg)	ASTM D 4491 Test Methods For Water Permeability of Geotextiles by Permittivity	The permeability of the Geotextile shall be greater than 0.49 Feet Per Minute (0.25 Centimeters per Second)
Tear Strength	ASTM D 4533 Trapezoidal Tear Strength	30 pounds minimum in any principal direction
Tensile Strength +(unaged geotextile)	ASTM D 4632 Determine breaking load as specified in the ASTM	200 pound minimum in any principal direction
Breaking Elongation +(unaged geotextile)	ASTM D 4632 Determine Apparent Elongation Breaking	15 percent minimum in any principal direction
Equivalent Opening Size (EOS)	ASTM D 4751 Determine Apparent Opening Size-AOS (EOS)	No finer than the U.S. Standard Sieve No. 100 and no coarser than the U.S. Standard Sieve No. 50
Puncture Strength +(unaged geotextile)	ASTM D 4833 Determine puncture resistance as specified in the ASTM	80 pound minimum
Abrasion Resistance	ASTM D 4886 Determine breaking load after abrasion test as specified in ASTM	55 pound minimum Residual Breaking Load in any principal direction
(N/A) Percent Open Area (POA)	(N/A) Specification Paragraph titled, "Determination of Percent Open Area."	(N/A) The percent of open area shall not be less than () percent

+Unaged geotextile is defined as geotextile in the condition received from the manufacturer or distributor.

++All numerical values represent minimum average roll values (i.e., any roll in a lot should meet or exceed the minimum in the table).

DIVISION 2 - SITE WORK

SECTION 02225

EARTHWORK

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATIONS
PART 2	PRODUCTS (Not Applicable)
PART 3	EXECUTION
3.1	EXCAVATION
3.1.1	General
3.1.2	Structure Excavation
3.1.3	Existing Embankment
3.2	DISPOSAL OF EXCAVATED MATERIAL
3.3	BACKFILL AT 16" STEEL PIPES AND CONCRETE OUTLET STRUCTURES
3.3.1	General
3.3.2	Materials
3.3.3	Placement
3.3.4	Compaction
3.4	SEMI-COMPACTED BACKFILL
3.4.1	General
3.4.2	Placement of Semi-Compacted Backfill
3.4.2.1	General
3.4.2.2	Moisture Control
3.4.2.3	Compaction
3.4.2.4	Definition of a Pass
3.4.2.5	Additional Compaction
3.4.2.6	Dressing
3.5	RAMPS
3.6	SLIDES

SECTION 02225

EARTHWORK

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all plant, labor, materials, and equipment, and performing all operations necessary for excavation and disposal of material therefrom; backfill of culvert excavations; and all other operations incidental thereto.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with the contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Excavation

Layout, bottom width, grades, slopes, alignment, transitions, disposition of materials, slides.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATION

The following publications of the issue listed below, but referred to thereafter by basic designation only, form a part of this specification to the extent indicated by the references thereto:

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D 698	Laboratory compaction Characteristics Using Standard Effort (12,400 ft-lbf/ft ³ (600 kN-m/m ³))
D 1556	Density and Unit Weight of Soil In-Place by the Sand- Cone Method

D 2216	Water (Moisture) Content of Soil and Rock
D 2922	Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
D 3017	Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 EXCAVATION

3.1.1 General

The Contractor shall excavate and remove all material of whatever nature encountered as may be necessary to construct the inlet pump station area, two (2) concrete outlet structure areas for the 16" steel discharge pipes, excavate and replace the existing embankment area, and excavation of drainage ditch areas along line of relief wells, at the locations as indicated on the drawings and/or specified herein.

3.1.2 Structure Excavation

Excavation shall conform to the dimensions and elevations indicated for the inlet pump station area and two (2) concrete outlet structures and all work incidental thereto. Excavation shall extend a sufficient distance from the inlet and outlet (head wall) structures to allow for placing and removal of forms. Excavations below indicated depths will not be permitted except to remove unsatisfactory material. Unsatisfactory material encountered below the grades shown shall be removed as directed by the Contracting Officer and replaced with satisfactory material. Satisfactory material removed below the depths indicated without specific direction of the Contracting Officer shall be replaced at no additional cost to the Government to the indicated excavation grade with satisfactory materials, except that concrete footings shall be increased in thickness to the bottom of the overdepth excavations. Satisfactory material shall be placed and compacted as specified in paragraph 3.3.4 as applicable. Determination of elevations and measurements of approved overdepth excavation of unsatisfactory material below grades indicated shall be done under the direction of the Contracting Officer.

3.1.3 Existing Embankment

The Contractor shall excavate and move the existing embankment between Station 8+00 thru Station 23+00 to the lines and grade as indicated on the drawings. The embankment shall be reconstructed with a 25 feet minimum width apron between the newly constructed drainage ditch and embankment as indicated on the drawings. The 25 feet easement shall be used for access of construction equipment and future maintenance of the site. The embankment shall be reconstructed using semi-compaction backfill as specified in 3.4 below to the lines, grades and cross sections as indicated on the drawings. The end slopes shall feather into the existing natural ground line or as directed by the Contracting Officer.

3.2 DISPOSAL OF EXCAVATED MATERIAL

Excavated material shall be utilized to the extent necessary to backfill the 16" steel pipes excavation, to place embankment over the 16" steel pipes that goes over the levee, and to reconstruct the existing ramps and construct new ramps; all as indicated on the drawings. Excavated material which is not utilized in the 16" steel pipes backfill, to place the embankment over the steel pipes, or to reconstruct the existing ramps and construct new ramps, shall be placed in areas within the right-of-way as directed by the Contracting Officer or shall be removed from the site.

3.3 BACKFILL AT 16" STEEL PIPES AND CONCRETE OUTLET STRUCTURES

3.3.1 General

Backfill materials shall be placed to the lines, grades, and sections as indicated therefor on the drawings and/or as directed by the Contracting Officer. The Contracting Officer will determine the suitability of each section of the foundation for placing materials thereon.

3.3.2 Materials

Materials for backfill at the 16" steel pipes and two (2) concrete outlet structures shall be those materials resulting from the required excavation which, in the opinion of the Contracting Officer, are suitable for such embankment work. No unsuitable organic or inorganic matter, sticks, trash, building debris, brush, trees, tree roots, stumps, rubbish, sod, muck, frozen material or any other objectionable matter shall be placed therein. The Contractor shall, when directed, remove any materials that the Contracting Officer considers objectionable in the backfill. The Contractor, at his option, may utilize borrow areas from an off site source, provided that he has submitted written evidence to the Contracting Officer that he has obtained property rights and access to the material therein, and that their location and dimensions, and the character of the material therein, as indicated by tests of soil samples, submitted by the Contractor, are approved by the Contracting Officer. The material shall conform to requirements of CH and CL materials as specified under the Unified Soil Classification System as shown on the Boring Legend drawing.

3.3.3 Placement

Backfill within 2 feet of the 16" steel pipes and within 2 feet of the two (2) concrete outlet structures shall be placed in layers not exceeding 6 inches in thickness prior to compaction, except as noted for semi-compacted fill as specified in paragraph 3.4 below. Any approved equipment may spread the materials and each layer shall be compacted as specified in 3.3.4 below. All fills shall be kept thoroughly drained and no fill shall be placed on frozen ground. When, in the opinion of the Contracting Officer, the surface of any layer is too smooth to bond properly with the succeeding layer, it shall be adequately scarified before the succeeding layer is placed. A tolerance of two-tenths of one foot above the prescribed grade and cross section will be permitted in the final dressing.

3.3.4 Compaction

Each layer of backfill within 2 feet and to the height of 2 feet above the top of the 16" steel pipes and within 2 feet of the two (2) concrete outlet structures, shall be compacted to a density of at least 95 percent of the laboratory density obtained by the standard density test (ASTM D 698) by means of approved hand-operated mechanical tampers. The field density determination shall be by the Sand-Cone Method (ASTM D 1556) or the Nuclear Method (ASTM D 2922, Method B). The moisture content after compaction shall be within the limits of 2 percentage points above optimum and 3 percentage points below optimum moisture content as determined by the Contractor in accordance with ASTM D 698. The field moisture content after compaction shall be performed in accordance with ASTM D 2216 or ASTM D 3017. The materials may require moistening or aerating as necessary to provide the above specified moisture content. The Contractor will perform standard laboratory density tests as specified in ASTM D 698 for each type of material used in the fill to determine optimum water content and maximum densities and will perform field density and water content tests. The Contractor shall perform field density and water content tests on each layer of material placed to assure that proper compaction is being achieved. The locations where the Contractor is to take the field density and water content tests shall be as specified by the Contracting Officer.

3.4 SEMI-COMPACTED BACKFILL

3.4.1 General

Backfill at the 16" steel pipes which is more than 2 feet from or above the top of the steel pipes and more than 2 feet from the concrete outlet structures and the existing ramps and the new ramps as specified in paragraph 3.5 below, shall be constructed of semi-compacted fill to line, grade and cross sections shown on the drawings.

3.4.2 Placement of Semi-Compacted Backfill

3.4.2.1 General

Semi-compacted backfill shall not be placed in water. The materials for semi-compacted backfill shall be placed or spread in layers, the first layer not more than 6 inches in thickness and the succeeding layers no more than 12 inches in thickness prior to compaction. When the surface of any compacted layer is too smooth to bond properly with the succeeding layer, it shall be adequately scarified before the next layer is placed thereon.

3.4.2.2 Moisture Control.

It is intended that semi-compacted backfill shall be placed at its natural moisture content. No moisture control will be required by the Contractor unless, in the opinion of the Contracting Officer, the desired compaction is not being obtained with the prescribed compactive effort due to the material being too wet or too dry. In such cases, the Contractor will be directed to perform moisture control as prescribed below. If the material is too wet, it shall either be stockpiled and allowed to drain before it is placed in the embankment cross sections and/or the wet material shall be processed by disking and harrowing, if necessary, until the moisture content is reduced sufficiently. If the material is too dry, sufficient moisture shall be uniformly distributed in each layer before compaction. If the Contractor is directed to perform any moisture control as outlined in this paragraph, an equitable adjustment in the contract price and time will be made.

3.4.2.3 Compaction.

When the moisture content and conditions of the spread layers are satisfactory, each layer shall be compacted by any of the following methods at the option of the Contractor:

(1) Tamper-Type Roller. Four complete passes over each layer will be required. If tamping rollers are used in tandem, not more than two rows will be permitted, and in such case, one trip of the tandem rollers over any surface will be considered as two passes. When tamping rollers are used in tandem, the tamper foot spacing shall be offset so that the circumferential rows on the rear drums are in line with the midpoint of the circumferential rows of the forward drums. Each pass of the tamping roller shall overlap the preceding or adjacent pass by not less than 1.0 foot.

(2) Rubber-Tired Roller. Two complete passes over each layer will be required.

(3) Crawler-Type Tractor. Three complete passes over each layer will be required. The tractor will not be considered to be compacting while spreading materials.

3.4.2.4 Definition of Pass

A pass shall consist of one complete coverage of the surface of a layer by the treads of the roller,

tractor, or other compacting equipment. Portions of the backfill that the compacting equipment cannot reach for any reason shall be compacted by an approved method to the density at least equal to that of the surrounding embankments.

3.4.2.5 Additional Compaction

If, in the opinion of the Contracting Officer, the desired compaction of any portion of the backfill cannot be secured by the minimum number of passes specified, additional complete passes shall be made over the surface area of such designated portion until the desired compaction has been obtained. An equitable adjustment in the contract price and time will be made.

3.4.2.6 Dressing.

Unreasonable roughness of surface shall be dressed out to permit turfing operations.

3.5 RAMPS

The existing levee ramps and the new ramps that is to be constructed, using semi-compacted material as specified in paragraph 3.4 above, shall be reconstructed or constructed to the lines and grades and side slopes as indicated therefore on the drawings or as directed by the Contracting Officer. The ramps shall be constructed using semi-compacted material as specified in 3.4 above. Ramps shall be surfaced with 6 inches compacted aggregate surfacing for a width of 10 feet as indicated on the drawings. The ramps shall be surfaced as specified in SECTION 02546, AGGREGATE SURFACING.

3.6 SLIDES

In case sliding occurs in any part of the ditch excavation prior to the final acceptance of the work, the Contractor shall repair such portions of the slides as the Contracting Officer may direct. In case the slide is caused through the fault of the Contractor, it shall be repaired without cost to the Government. In case the slide is due to no fault of the Contractor, the yardage ordered removed will be included in the yardage to be paid for at the contract unit price per cubic yard for "Excavation". Material removed from the slides shall be disposed of in accordance with the provisions of 3.2 above.

--End of Section--

DIVISION 2 - SITE WORK

SECTION 02542

STONE PROTECTION

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATION
PART 2	PRODUCTS
2.1	BEDDING MATERIALS
2.1.1	General
2.1.2	Gradation
2.2	STONE
2.2.1	General
2.2.2	Sources and Evaluation Testing
2.2.3	Gradation
2.2.4	Test Method
2.2.5	Gradation Test
PART 3	EXECUTION
3.1	BASE PREPARATION
3.2	PLACEMENT OF BEDDING MATERIAL
3.3	RIPRAP
3.3.1	General
3.3.2	Placement

SECTION 02542

STONE PROTECTION

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, equipment and materials, and performing all operations in connection with the construction of the stone protection, including foundation preparation, placement of bedding material, placement of riprap, and excavation for placement of stone protection, all in accordance with these specifications and the contract drawings.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for all stone protection testing and operations to assure compliance with contract requirements, and shall maintain records of the quality control for all construction including but not limited to the following:

- (1) Foundation preparation (line and grade).
- (2) Inspection at the worksite to ensure use of specified materials.
- (3) Bedding material gradation and placement.
- (4) Riprap gradation and placement.

A copy of these records of inspections and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATION

The following publication of the issue listed below, but referred to thereafter by basic designation only, forms a part of this specification to the extent indicated by the reference thereto:

U.S. ARMY CORPS OF ENGINEERS, HANDBOOK FOR CONCRETE AND CEMENT (CRD)

CRD-C 106

Unit Weight and Voids in Aggregate

CRD-C 107

Specific Gravity and Absorption of Coarse Aggregate

PART 2 PRODUCTS

2.1 BEDDING MATERIALS

2.1.1 General

Bedding material shall consist of crushed stone. The material shall be composed of tough, durable particles, shall be reasonably free from thin, flat and elongated pieces, and shall contain no organic matter nor soft, friable particles in quantities considered objectionable by the Contracting Officer.

2.1.2 Gradation

<u>U.S. Standard Sieve No.</u>	<u>Permissible Limits Percent by Weight, Passing</u>
1 1/2-inch	100
1 -inch	85-100
1/2-inch	35-70
No. 4	5-40
No. 100	0-10

The material shall be well graded between the limits shown. The Contractor shall furnish a certified test report which certifies that the supplied bedding material meets the above gradation and also furnish a representative sample of this same material to the Government.

2.2 STONE

2.2.1 General

All stone shall be durable material as approved by the Contracting Officer. The sources from which the Contractor proposes to obtain the material shall be selected well in advance of the time when the material will be required. In case an undeveloped source is to be used, the Contractor shall show that an ample quantity of material is available. Stone for riprap shall be of a suitable quality to ensure permanence in the structure and in the climate in which it is to be used. It shall be free from cracks, seams and other defects that would tend unduly to increase its deterioration from natural causes. The inclusion of objectionable quantities of dirt, sand, clay and rock fines will not be permitted.

2.2.2 Sources and Evaluation Testing

Sources and Evaluation Testing

Riprap shall be obtained in accordance with the provisions in SECTION 00800 paragraph 1.30 STONE SOURCES. The Contractor shall submit suitable test reports and service records to show the acceptability of the riprap. If the Contractor proposes to furnish riprap from a source not currently listed, the Contractor will make such investigations as necessary to determine whether acceptable riprap can be produced from the proposed source. Satisfactory service records on work outside the Corps of Engineers will be acceptable. In order for riprap to be acceptable on the basis of service records, riprap of a similar size must have been placed in a similar thickness and exposed to weathering under similar conditions as is anticipated for this contract, and have satisfactorily withstood such weathering for a minimum of twenty years. If no such records are available, the Contractor will make tests to assure the acceptability of the riprap. The tests to which the riprap may be subjected will include petrographic analysis, specific gravity, abrasion; absorption, wetting and drying, freezing and thawing and such other tests as may be considered necessary by the Contracting Officer. The following guidance is provided for use by the Contractor in analyzing a new source of riprap. Riprap that weighs less than 155 lbs/c.f. or has more than 2% absorption will not be accepted unless other tests and service records show that the riprap is satisfactory. The method of tests for unit weight will be CRD-C 106. The method of tests for absorption will be CRD-C 107. Samples shall be taken by the Contractor under the supervision of the Contracting Officer at least 60 days in advance of the time the placing of the riprap is expected to begin. The Contractor has the responsibility to assure the tests are performed in accordance with applicable Corps of Engineers methods of testing given in the Handbook for Concrete and Cement, and will be performed at an independent, approved testing laboratory. The cost of testing will be borne by the Contractor.

2.2.3 Gradation

Gradation shall conform to Tables I below and to Plate I at the end of this section and format thereof shall be as shown. Neither the width nor the thickness of any piece shall be less than one-third of its length. An allowance of 5 percent by weight for inclusion of quarry spalls will be permitted. Stone shall be reasonably well graded between the largest and smallest pieces. The table below describes the upper and lower limit curves for the riprap gradation. The graph of the riprap when plotted on ENG Form 4055 with the limit curves plotted thereon is inserted at the end of this section as Plate I. The graph of the riprap when plotted on ENG Form 4055 must lie between these upper and lower limit curves.

TABLE I
(For Riprap "R-90")

<u>Percent Lighter by Weight (SSD)</u>	<u>Limits of Stone Weight, lb.</u>
100	90-40
50	40-20
15	20-5

2.2.4 Test Method

Gradation test method shall conform to the requirements of “LMVD Standard Test method for Gradation of Riprap” which is inserted at the end of this section as PLATE I; an Example Gradation and Worksheet, an Example Gradation plotted on ENG Form 4055, and example Gradation Test Data Sheet; all inserted at the end of this section as Plates III, IV and V. Plate VI has been provided for the convenience of the Contractor and can be used as necessary.

2.2.5 Gradation Test

The Contractor shall perform a gradation test or tests on the riprap at the quarry. At least one gradation test shall be performed. The sample shall be taken by the Contractor under the supervision of the Contracting Officer, shall consist of not less than 15 tons of riprap and shall be collected in a random manner which will provide a sample which accurately reflects the actual gradation arriving at the jobsite. If collected by the truckload, each truckload shall be representative of the gradation requirements. The Contractor shall provide all necessary screens, scales and other equipment, and the operating personnel therefor, and shall grade the samples, all at no additional cost to the Government. The results of the gradation test (s) shall be plotted on ENG form 4055 with the graphs of the upper and lower limit curves and shall be submitted to the Contracting Officer for approval. For each sample, the Contractor shall record, plot, and submit the gradation data, using the forms noted at the end of this section, to the Contracting Officer.

PART 3 EXECUTION

3.1 BASE PREPARATION

Areas on which the bedding material and riprap are to be placed shall be dressed to conform to cross sections shown on the contract drawings and as specified herein. Humps and depressions within the slope lines shall be dressed to provide relatively smooth and uniform surfaces. Immediately prior to placing the bedding material, the prepared base will be inspected by the Contracting Officer and no material shall be placed thereon until that area has been approved. Bedding material and riprap shall be placed as channel excavation progresses upstream as soon as practicable

3.2 PLACEMENT OF BEDDING MATERIAL

Bedding Material for riprap bedding shall be spread uniformly on the prepared base to the lines and grades as indicated on the contract drawings and in such manner as to avoid damage to the prepared base. Any damage to the surface of the prepared base during placing of the material shall be repaired before proceeding with the work. Compaction of material placed on the prepared base will not be required, but each layer shall be finished to present a reasonably even surface, free from mounds or windrows. The allowable deviation from the prescribed thickness shall be plus 2 inches.

3.3 RIPRAP

3.3.1 General.

Riprap shall be placed on the prepared base and/or bedding material within the limits shown on the contract drawings. Riprap shall be as specified in 2.2 above.

3.3.2 Placement

Riprap shall be placed in a manner which will produce a reasonably well-graded mass of rock with the minimum practicable percentage of voids, and shall be constructed, within the specified tolerance, to the lines and grades indicated on the contract drawings. A tolerance of plus 6 inches and minus 3 inches from the required finished surface of the riprap will be allowed provided these extremes do not occur adjacent to each other, and that neither extreme exists over more than 10 percent of the total area. Riprap shall be placed to its full course thickness in one operation and in such manner as to avoid displacing the bedding material. The larger stones shall be well distributed and the entire mass of stones in their final position shall be graded to conform to the gradation specified in 2.2.3 above. The finished riprap shall be free from objectionable pockets of small stones and clusters of larger stones. Placing riprap in layers will not be permitted. Placing riprap by dumping it at the top of the slope and pushing it down the slope will not be permitted. The desired distribution of the various sizes of stones throughout the mass shall be obtained by selective loading of the material at the quarry or other source; by controlled dumping of successive loads during final placing; or by other methods of placement which will produce the specified results. Rearranging of individual stones by mechanical equipment or by hand will be required to the extent necessary to obtain a reasonably well-graded distribution of stone sizes as specified above. The Contractor shall maintain the riprap until accepted and any material displaced prior to acceptance and due to the Contractor's negligence shall be replaced at his expense and to the lines and grades indicated on the contract drawings.

-- End of Section --

LMVD STANDARD TEST METHOD FOR GRADATION

December 14, 1998

- A. Select a representative sample (Note #1), weigh and dump on hard stand.
- B. Select four specific size stones to use as reference stones (a1, b1, c1, and d1) while performing the "individual weight larger than" test (see example & Note #2). Selected stone sizes should represent an evenly distributed cross section of the various size stones contained within the sample. Reference stone "a1" is typically the largest stone in the sample. Procedure is similar to the standard aggregate gradation test for "individual weight retained".
- C. Determine the largest size stone in the sample. (100% size)
- D. Separate the sample into piles starting with the stones that are larger than reference stone "b1" and proceeding to the smallest stones. The first pile should contain all stones larger than reference stone "b1" and smaller than "a1", the largest stone. Pile two should contain all stones larger than "c1" and smaller than "b1". Pile 3 should contain all stones larger than "d1" and smaller than "c1". The remaining pile should contain all stones smaller than "d1". Use reference stones for visual comparison in separating the obviously "larger than" stones. Stones that appear close to a specific size reference stone must be individually weighed. If a stone is heavier than the specific size reference stone, it should be placed in the pile containing the stones larger than the reference stone. Weigh each pile as a whole or cumulatively adding each stone in the individual piles.
- E. Paragraph D above will result in "individual weight retained" figures. Calculate individual percent retained (heavier than) and cumulative percent retained and cumulative percent passing (lighter than). Record test results on the "Gradation Test Data Sheet" (plate V) as shown on example plate III. Plot percent finer by weight, along with the specification curves on ENG Form 4055.
- F. See plate V and plate VI for a blank "Gradation Test Data Sheet" and a blank ENG Form 4055. Plates VII, VIII, and IX have been provided for the convenience of the contractor and can be used as necessary. These three plates have the upper and lower specification limits for "R-90", "R-200", and "R-650" pre-plotted on ENG Form 4055.

NOTES

1. Sample Selection. The most important part of the test and the least precise is the selection of a representative sample. No "standard" can be devised; larger quarry run stone is best sampled at the shot or muck pile by given direction to the loader; small graded riprap is best sampled by random selection from the transporting vehicles. If possible, all parties should take part in the sample selection and agree before the sample is run that the sample is representative.
2. Selection of Size for Separation. It is quite possible and accurate to run a gradation using any convenient sizes for the separation, without reference to the specifications. However, it is usually more convenient to select weights from the gradation limits, such as the 90 lbs., 40 lbs., 20 lbs., and 5 lbs. as shown in the following "R-90" example. After the test is plotted on ENG 4055 and a curve drawn, the gradation limits from the specifications shall be plotted.

(EXAMPLE)

Table From Specifications

TABLE I
(For Riprap "R 90")

<u>Percent Lighter by Weight (SSD)</u>	<u>Limits of Stone Weight, lb.</u>
100	90-40
50	40-20
15	20-5

(EXAMPLE)

GRADATION TEST DATA SHEET

Quarry AAA Quarry Inc. Stone Tested R-90

Date of Test 24 May 79 Testing Rate _____

TEST REPRESENTS

Contract No.	District	Tons
DACW66-79-C-0005	Memphis	16
TOTAL		16

GRADATION


Stone Size (lbs.)	Individual Weight Retained	Individual % Retained	Cumulative %Coarser	%Finer	Specification % Finer by wt
90 "a1"	0	0	0	100	100
40 "b1"	9600	30	30	70	100-50
20 "c1"	11200	35	65	35	50-15
5 "d1"	8000	25	90	10	<15
< 5 "d1"	3200	10	100	-	
Total Weight	32000lbs				

Remarks: LARGEST STONE SIZE = 78 LBS


I Certify that the above stone sample is representative of the total tonnage covered by this test report.

Contractor Representative: Representative's Name and Signature

Government Representative: Representative's Name and Signature



WEIGHT OF STONES IN POUNDS*
 SPECIFIC GRAVITY OF ROCK _____
 *ASSUMING STONE SHAPE MIDWAY BETWEEN A SPHERE AND CUBE



MEMPHIS DISTRICT - CORPS OF ENGINEERS
 MEMPHIS, TENNESSEE

EXAMPLE "R-90" EXAMPLE

PROJECT: NEW FRANKLIN DITCH DATE: 24 MAY 79

RIPRAP GRADATION CURVES

G R A D A T I O N T E S T D A T A S H E E T

Quarry _____ Stone Tested _____

Date of Test _____ Testing Rate _____

T E S T R E P R E S E N T S

Contract No.	District	Tons
TOTAL		

G R A D A T I O N


Stone Size (lbs)	Individual Weight Retained	Individual % Retained	Cumulative %Coarser	%Finer	Specification % Finer by wt
Total Weight					

Remarks: _____

I Certify that the above stone sample is representative of the total tonnage covered by this test report.

Contractor Representative _____

Government Representative _____



WEIGHT OF STONES IN POUNDS*

SPECIFIC GRAVITY OF ROCK _____

*ASSUMING STONE SHAPE MIDWAY BETWEEN A SPHERE AND CUBE

SIZE OF STONE IN INCHES

MEMPHIS DISTRICT - CORPS OF ENGINEERS
MEMPHIS, TENNESSEE

PROJECT: _____ DATE: _____

RIPRAP GRADATION CURVES

PLATE VI

DIVISION 2 - SITE WORK

SECTION 02545

CRUSHED STONE AND ARMORLOC BLOCKS

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
PART 2	PRODUCTS
2.1	CRUSHED STONE MATERIAL
2.1.1	General
2.1.2	Gradation
2.2	ARMORLOC BLOCKS
PART 3	EXECUTION
3.1	BASE PREPARATION
3.2	PLACEMENT OF GEOTEXTILE (FILTER FABRIC) AND CRUSHED STONE MATERIAL
3.2.1	Geotextile
3.2.2	Crushed Stone Material

SECTION 02545

CRUSHED STONE AND ARMORLOC BLOCKS

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, equipment and materials, and performing all operations in connection with the placement of the Armorloc Blocks, placement of geotextile, placement of crushed stone material, and including foundation preparation, all in accordance with these specifications and the contract drawings.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in the section to assure compliance with contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Foundation
Preparation (line and grade).

(2) Inspection

At the worksite to ensure use of specified materials.

(3) Crushed Stone Material

Gradation and placement.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

PART 2 PRODUCTS

2.1 CRUSHED STONE MATERIAL

2.1.1 General

Crushed stone material shall consist of gravel or crushed stone. The material shall be composed of tough, durable particles, shall be reasonably free from thin, flat and elongated pieces, and shall contain no organic matter nor soft, friable particles in quantities considered objectionable by the Contracting Officer.

2.1.2 Gradation

<u>U.S. Standard Sieve No.</u>	<u>Permissible Limits Percent by Weight, Passing</u>
1 1/2-inch	100
1 -inch	85-100
1/2-inch	35-70
No. 4	5-40
No. 100	0-10

The material shall be well graded between the limits shown. The Contractor shall furnish a certified test report which certifies that the supplied crushed stone material meets the above gradation and also furnish a representative sample of this same material to the Government.

2.2 ARMORLOC BLOCKS

Armorloc (Using No. 4511 Blocks) or approved equal shall be placed to the dimensions as noted on the drawings and/or as directed by the Contracting Officer. Method of placement shall be as recommended by the manufacturer of the Armorloc blocks. Blocks at the edges of the placement areas shall be cut to give a finished appearance to the boundary edges. After placement is complete, crushed stone material shall be worked into the voids between the blocks creating an even surface. The manufacturer of the blocks is NICOLON Corporation 3500 Parkway Lane, Suite 500 Norcross, GA 30092 (404) 447-6272, Fax: (404) 662-5819.

PART 3 EXECUTION

3.1 BASE PREPARATION

Areas, on which the crushed stone material is to be placed, shall be dressed to conform to cross sections shown on the contract drawings. Humps and depressions within the slope lines shall be dressed to provide relatively smooth and uniform surfaces. Immediately prior to placing the filter material, the prepared base will be inspected by the Contracting Officer and no material shall be placed thereon until that area has been approved.

3.2 PLACEMENT OF GEOTEXTILE (FILTER FABRIC) AND CRUSHED STONE MATERIAL

3.2.1 Geotextile

Geotextile shall be placed on prepared sub-base as directed by Contracting Officer.

3.2.2 Crushed Stone Material

Crushed stone material for Armorloc bedding shall be spread uniformly on the geotextile to the lines and grades as indicated on the contract drawings and in such manner as to avoid damage to the geotextile (filter fabric) or prepared base. Any damage to the geotextile or the surface of the prepared base during placing of the material shall be repaired before proceeding with the work. The 4 inch layer of crushed stone as indicated on the drawings shall be finished to present a reasonably even surface, free from mounds or windrows. The allowable deviation from the prescribed thickness shall be plus 2 inches. The geotextile shall be placed on the prepared subbase, under the crushed stone to the dimensions as shown on the drawings and/or as directed by the Contracting Officer.

-- End of Section --

DIVISION 2 - SITE WORK

SECTION 02546

AGGREGATE SURFACING

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATION
PART 2	PRODUCTS
2.1	AGGREGATE
2.1.1	Coarse Aggregate
2.1.2	Fine Aggregate
2.1.3	Gradation
2.2	SAMPLING AND TESTING
2.2.1	General
2.2.2	Contractor Testing
2.2.3	Government Testing
PART 3	EXECUTION
3.1	SUBGRADE COMPACTION
3.2	SUBGRADE
3.3	PLACEMENT
3.4	MAINTENANCE

DIVISION 2 - SITE WORK

SECTION 02546

AGGREGATE SURFACING

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all plant, labor, and materials, and performing all operations necessary for constructing aggregate surfacing upon the crown of the existing ramps, and new ramp all as indicated on the drawings, as directed by the Contracting Officer, and/or as specified herein.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements, and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Subgrade

Location, preparation.

(2) Materials

Material delivered to the site conforms to specifications and is comparable to samples of material previously tested and approved for use. Tests include gradation, liquid limit and plasticity index of material passing the No. 40 sieve.

(3) Placement

Width, thickness, distribution, compaction, final grading, and maintenance.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATION

The following publication of the issues listed below, but referred to thereafter by basic designation only, form a part of this specification to the extent indicated by the references thereto:

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) PUBLICATIONS.

D 698	Laboratory compaction Characteristics Using Standard Effort (12,400 ft-lbf/ft ³ (600 kN-m/m ³))
D 1556	Density and Unit Weight of Soil in Place by the Sand-Cone Method
D 2216 and Ed Comt 1	Water (Moisture) Content of Soil, Rock
D 2922	Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
D 3017	Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)
D 4318	Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils

PART 2 PRODUCTS

2.1 AGGREGATE

Aggregate for surfacing shall be composed of sand-clay-gravel mixtures; gravel or stone screenings; crusher run coarse aggregate consisting of gravel or crushed stone with sand and binding material; or any combination of such materials which conforms to specified requirements. All material shall be free from organic matter and lumps or balls of clay. The material shall conform to the requirements as specified in 2.1.1 and 2.1.2 below, and shall conform to the gradation specified in 2.1.3 below. All aggregate surfacing furnished under this contract shall comply favorably with representative samples as to quality, gradation, and moisture content.

2.1.1 Coarse Aggregate

Coarse aggregate is defined as aggregate retained on the No. 10 (2.00 mm) sieve. Coarse aggregate shall consist of hard, durable particles or fragments of stone or gravel. Materials that are soft, pliable, or subject to rapid deterioration when exposed to weathering shall not be used.

2.1.2 Fine Aggregate

Fine aggregate is defined as aggregate passing the No. 10 (2.00 mm) sieve. Fine aggregate shall consist of natural or crushed sand, and also shall include fine mineral particles passing the No. 200 (0.075 mm) sieve. The fraction of the material passing the No. 200 (0.075 mm) sieve shall be no more than two-thirds that of the fraction passing the No. 40 (0.425 mm) sieve. That portion of the aggregate passing the No. 40 (0.425 mm) sieve shall have a liquid limit of not more than 35 and a plasticity index of not less than 6, nor more than 15, as determined by ASTM D 4318. However, if crushed stone is utilized then the plasticity index shall be between 0 and 15.

2.1.3 Gradation

Aggregate surfacing material shall conform to the following gradation:

<u>U.S. Standard Sieve</u>	<u>Permissible Limits Percent by Weight, Passing</u>
3"	100
1-1/2"	95-100
3/4"	65-100
3/8"	40- 80
No. 4	30- 60
No. 10	20- 50
No. 40	15- 35
No. 200	5- 15

2.2 SAMPLING AND TESTING

2.2.1 General

Representative samples for testing of the material shall be taken by the Contractor under the supervision of the Contracting Officer. All costs of sampling and testing, shall be borne by the Contractor and no separate payment will be made therefor.

2.2.2 Contractor Testing

Prior to delivery of any material to the job site, the material shall be tested for compliance with the specifications by an approved independent testing laboratory. In the event a noticeable change in the materials is observed during placement, such testing shall be performed at the direction of the Contracting Officer regardless of the quantity of material delivered. Certified results of the tests shall be submitted to the Contracting Officer for approval

2.2.3 Government Testing

At the same time that samples for Contractor testing as specified in 2.2.2 above are taken, the Contractor shall take samples for assurance testing to be performed by and at the expense of the Government. The Contractor shall deliver such samples to Wynne Area Office, 1932 N. Falls Boulevard, Wynne, Arkansas 72396-0729. Notice of assurance sample deliveries shall be given to the Contracting Officer's Representative prior to delivery.

PART 3 EXECUTION

3.1 SUBGRADE COMPACTION

The top 16-inches of subgrade shall be compacted as specified in SECTION 02225 paragraph 3.3.4.

3.2 SUBGRADE

The subgrade shall be symmetrical about the centerline of the existing gravel ramps and also the existing levee roadway at the sump ditch inlet at Station 43/05+79, and the new ramps that are to be constructed upon which aggregate surfacing is to be placed, all as indicated on the drawings. Subgrade for all surfacing shall be graded and smoothed prior to placing the surfacing. Subgrade for the surfacing shall be in a satisfactory condition for receiving aggregate surfacing for a distance of at least 200 feet in advance of the placing of aggregate surfacing material, as applicable. Aggregate shall not be placed on frozen ground.

3.3 PLACEMENT

Aggregate shall be placed and spread upon the subgrades of the ramps in the amount required to produce a pavement with width and compacted thickness as indicated on the drawings. The placement shall be commenced at the nearest point of delivery of the resurfacing material to the ramps to be surfaced and shall be carried continuously away from such point unless otherwise authorized by the Contracting Officer. Placing of aggregate will not be allowed when the ramp surface, in the opinion of the Contracting Officer, is too wet to place aggregate. Ramps that are completed shall be graded and dressed to provide a slope each way from the centerline and then compacted by at least four passes of a pneumatic tired roller having tire pressure of 35 to 40 pounds per square inch and a gross weight of not less than 20,000 pounds or by other approved compacting equipment which will obtain comparable compaction. A pass of the roller shall consist of the completed coverage of the surface by the roller. The compaction passes of the roller shall not be performed when the material is so wet that it is displaced under the roller or when the material is too dry for proper bonding. In the event aggregate is hauled over roller portions of the resurfacing, such portions shall subsequently be graded, dressed and rolled again as specified hereinabove at no additional cost to the Government. The resurfacing shall be maintained in an acceptable condition until acceptance.

3.4 MAINTENANCE

The Contractor shall maintain the aggregate surfacing in a good and satisfactory condition until acceptance. The Contractor shall correct any deficiencies in width and thickness and shall remove, dispose of as described in paragraph 3.1 above, and replace, without additional compensation, any deficient material placed in the work.

-- End of Section --

DIVISION 2 – SITE WORK

SECTION 02700

CULVERT INSTALLATION

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATIONS
PART 2	PRODUCTS
2.1	MATERIALS
2.1.1	Pipe
PART 3	EXECUTION
3.1	INSTALLATION
3.1.1	Culvert Pipe
3.2	BACKFILL
3.2.1	General
3.2.2	Compacted Backfill

SECTION 02700

CULVERT INSTALLATION

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all labor, equipment, and materials, and performing all operations necessary for the installation of new corrugated metal pipe culverts, all as indicated on the drawings, and/or specified herein.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Materials. Review, prior to submittal, of certificates for compliance with specification requirements.

(2) Installation. Length, type, location, alignment, grade, slope, foundation bedding, coupling bands, repair of damaged areas.

(3) Backfill. Thickness of layers, maintenance of culvert alignment, compaction, elevation.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATIONS

The following publications of the issues listed below, but referred to thereafter by basic designation only, form a part of this specification to the extent indicated by the reference thereto:

American Society for Testing and Materials (ASTM) Publications.
A 760/A760M95-b Corrugated Steel Pipe, Metallic-

Coated for Sewers and Drains

A 849	Post Applied Coatings, Pavings, and Linings for Corrugated Steel Sewer and Drainage Pipe
D 698	Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft ³ (600kN-m/m ³))
D 1556	Density and Unit Weight of Soil in Place by the Sand-Cone Method
D 2922	Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Pipe

The zinc coated (Galvanized) corrugated metal pipe culvert shall conform to the requirements of ASTM A 760, for Type I and ASTM A 849, for fully coated using Class A material. As an alternate, aluminum coated (Aluminized) corrugated metal pipe culverts may be used conforming to ASTM A 760, Type I with no bituminous coating required. The manufacturer's certified statement as to quality will be accepted in lieu of performing the prescribed tests. Certificates required for demonstrating proof of compliance shall be in compliance with SPECIAL CONTRACT REQUIREMENTS CLAUSE 1.14. The pipe shall be fabricated from 0.079 inches thick sheets. Coupling bands for joints may be 0.064 inches thick or heavier and shall be installed as recommended by the materials manufacturer except as specified herein. Coupling bands shall be coated as specified hereinabove for the pipe and shall have corrugations, not projections, that mesh with the pipe corrugations, and if helical corrugations are used, each length of helical pipe used shall have a minimum 12-inch length of annular corrugations at each end. All installation hardware shall be as recommended by the materials manufacturer. Inlet and outlet sections shall be unjointed sections at least 20 feet in length.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Culvert Pipe

The exact length of the culvert pipe will be determined in the field by the Contracting Officer and the Contractor will be notified of such length prior to installation. The pipe shall be placed at the

location indicated on the drawings. Installation of the pipe shall be accomplished in the dry. The pipe shall be bedded on a smooth surface with invert elevation as determined in the field. Joints shall be carefully made by the material manufacturer's standard method, subject to the provisions of 2.1.1 above. Pipe shall be handled with care so that damage to the coating will be minimized. Coupling band rods if applicable and damaged areas of pipe shall be coated with approved asphaltic cement prior to placement of backfill, and in case damaged areas are at joints, such areas shall be coated prior to making the joint. The Contractor shall perform such excavation as is necessary for the installation of culvert, all as indicated on the drawings. Excavated materials shall be utilized in the backfill or embankment or shall be disposed of as specified in SECTION 02225, paragraph 3.2.

3.2 BACKFILL

3.2.1 General

Backfill shall be placed around and over the culvert pipes to the line and grade indicated on the drawings and/or as directed by the Contracting Officer. Backfill material shall be obtained from the required excavations, and shall be free from roots, muck, brush and other objectionable matter. Material used within 2 feet of the pipes shall consist of cohesive material. The Contractor will be required, when directed, to remove any materials which the Contracting Officer considers to be objectionable in the backfill. Frozen material shall not be placed in the backfill nor shall material be placed upon frozen foundations. The suitability of each section of the foundation for placing materials thereon will be determined by the Contracting Officer.

3.2.2 Compacted Backfill

Backfill material within 2 feet of the pipe shall be placed concurrently on each side of the pipe in layers not more than 6 inches in thickness prior to compaction. In placing and compacting the material, care shall be taken to insure that the backfill is rammed tight against the pipe at all points. Compaction within 2 feet of culvert pipe shall be accomplished by the use of approved mechanical hand tampers. Each layer of backfill shall be compacted to a density of at least 95 percent of the laboratory density obtained by the standard density test (ASTM D 698), Method D. The field density determination shall be by the Sand-Cone Method (ASTM D 1556) or by the Nuclear Method (ASTM D 2922). The moisture content after compaction shall be within the limits of 2 percentage points above optimum and 3 percentage points below optimum moisture content as determined in accordance with ASTM D 698. The materials may require moistening or aerifying as necessary to provide the above specified moisture content. The Contractor shall perform standard compaction tests to determine optimum water content and maximum densities and will perform field density and water content tests as assurance checks; the Contractor shall perform field density and water content tests on each layer of material placed to assure that proper compaction is being achieved.

--End of Section--

DIVISION 2 - SITE WORK

SECTION 02704

STEEL PIPE INSTALLATION

TABLE OF CONTENTS

PART 1 GENERAL

1.1 SCOPE

1.2 QUALITY CONTROL

1.3 APPLICABLE PUBLICATION

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Steel Pipe

3.1.2 Steel Pipe Backfill

3.1.2.1 Impervious Backfill Material

3.1.2.1.1 Placement

3.1.2.1.2 Compaction

3.1.2.2 Semi-Compacted Backfill

3.1.2.2.1 General

3.1.2.2.2 Moisture Control

3.1.2.2.3 Compaction

3.1.2.2.4 Definition of Pass

3.1.2.2.5 Additional Compaction

3.1.2.2.6 Dressing

SECTION 02704

STEEL PIPE INSTALLATION

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all labor, equipment, and materials, and performing all operations necessary for the installation of new steel pipes, as indicated on the drawings, specified herein, and/or as directed.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements and maintain records of his quality control for all construction operations including; but not limited to, the following:

(1) Materials

Review, prior to submittal, of certificates for compliance with specification requirements.

(2) Installation

Length, type, location, alignment, grade, slope, foundation bedding, coupling bands, repair of damaged areas.

(3) Backfill

Thickness of layers, maintenance of culvert alignment, compaction, elevation.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATION

The following publications of the issue listed below, but referred to thereafter by basic designation only, forms a part of this specification to the extent indicated by the reference thereto:

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

C 33 (CRD-C 11)	Concrete Aggregates
D 698	Laboratory Compaction Characteristics of Soil using Standard Effort (12,400 ft-lbf/ft ³ (600 kN-m/m ³))
D 1556 with editorial change 2	Density and Unit Weight of Soil in Place by the Sand-Cone Method
D 2216	Water (Moisture) Content of Soil and Rock
D 2922	Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
D 3017	Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth)

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Steel Pipe

The steel pipes as shown on the drawings shall be as specified in SECTION 15175, paragraph 2.1.1. The steel pipes shall be placed at the locations indicated on the drawings. Installation of the steel pipes shall be accomplished in the dry. The steel pipes shall be bedded as indicated on the drawings and/or as specified SECTION 15175, paragraph 3.3. Joints shall be as shown on the drawings. The Contractor shall perform such excavation as shown on the drawings for the installation of the steel pipes. Excavated materials shall be utilized in the backfill or ramps or shall be disposed of as specified in SECTION 02225, paragraph 3.2. A locking device consisting of a 1" steel rod and padlock shall be installed on the inlet end of discharge pipes as shown on the drawings and as

specified herein. The steel rod shall be removed only during operation of the pumps.

3.1.2 STEEL PIPE BACKFILL

3.1.2.1 Impervious Backfill Material

Impervious backfill materials for steel pipe backfill shall be those materials resulting from the required excavation as specified in paragraph 3.1.1 above and SECTION 02225 which, in the opinion of the Contracting Officer, are suitable for such embankment work or shall be provided by the Contractor as specified in SECTION 02225, paragraph 3.3.2. No unsuitable organic or inorganic matter, sticks, trash, building debris, brush, trees, tree roots, stumps, rubbish, sod, muck, frozen material or any other objectionable matter shall be placed therein. The Contractor shall, when directed, remove any materials that the Contracting Officer considers objectionable in the backfill.

3.1.2.1.1 Placement.

Impervious backfill material for steel pipe backfill shall be placed in layers not exceeding 12 inches in thickness prior to compaction, except as noted for semi-compacted fill as specified in paragraph 3.1.2.2. Any approved equipment may spread the materials and each layer shall be compacted as specified in 3.1.2.2.3 below. Fill within two feet of the culverts shall be compacted by means of hand-operated mechanical tampers. All fills shall be kept thoroughly drained and no fill shall be placed on frozen ground. When, in the opinion of the Contracting Officer, the surface of any layer is too smooth to bond properly with the succeeding layer, it shall be adequately scarified before the succeeding layer is placed. A tolerance of two-tenths of one foot above the prescribed grade and cross section will be permitted in the final dressing.

3.1.2.1.2 Compaction

Impervious embankment placed within 2 feet of the steel pipe shall be placed in layers not exceeding 6 inches in thickness prior to compaction and each layer shall be compacted by mechanical hand tampers to 95 percent standard Proctor. Each layer of pervious bedding backfill and impervious backfill material to the height of 2 feet above the top of the steel pipe as applicable shall be compacted to a density of at least 95 percent of the laboratory density obtained by the standard density test (ASTM D 698). The field density determination shall be by the Sand-Cone Method (ASTM D 1556) or the Nuclear Method (ASTM D 2922, Method B). The moisture content after compaction shall be within the limits of 2 percentage points above optimum and 3 percentage points below optimum moisture content as determined by the Contractor in accordance with ASTM D 698. The field moisture content after compaction shall be performed in accordance with ASTM D 2216 or ASTM D 3017. The materials may require moistening or aerating as necessary to provide the above-specified moisture content. The Contractor will perform standard laboratory density tests as specified in ASTM D 698 for each type of material used in the fill to determine optimum water content and maximum densities and will perform field density and water content tests. The Contractor shall perform field density and water content tests on each layer of material placed to assure that proper compaction is being achieved. The locations where the Contractor is to take the

field density and water content tests shall be as specified by the Contracting Officer.

3.1.2.2 Semi-Compacted Backfill

3.1.2.2.1 General

Backfill for the steel pipe which is more than 2 feet above the top of the steel pipes shall be constructed of semi-compacted fill to line, grade and cross sections shown on the drawings. The source and suitability of backfill material shall be as specified in paragraph 3.1.2.1 above. Semi-compacted backfill shall not be placed in water. The materials for semi-compacted backfill shall be placed or spread in layers, the first layer not more than 6 inches in thickness and the succeeding layers no more than 12 inches in thickness prior to compaction. When the surface of any compacted layer is too smooth to bond properly with the succeeding layer, it shall be adequately scarified before the next layer is placed thereon.

3.1.2.2.2 Moisture Control

It is intended that the material will be placed in the backfill at its natural moisture content. No moisture control will be required by the Contractor unless, in the opinion of the Contracting Officer, the desired compaction is not being obtained with the prescribed compactive effort due to the material being too wet or too dry. In such cases, the Contractor will be directed to perform moisture control as prescribed below. If the material is too wet, it shall either be stockpiled and allowed to drain before it is placed in the embankment cross sections and/or the wet material shall be processed by disking and harrowing, if necessary, until the moisture content is reduced sufficiently. If the material is too dry, sufficient moisture shall be uniformly distributed in each layer before compaction. If the Contractor is directed to perform any moisture control as outlined in this paragraph, an equitable adjustment in the contract price and time will be made.

3.1.2.2.3 Compaction

When the moisture content and conditions of the spread layers are satisfactory, each layer shall be compacted by any of the following methods at the option of the Contractor:

(1) Tamper-Type Roller. Four complete passes over each layer will be required. If tamping rollers are used in tandem, not more than two rows will be permitted, and in such case, one trip of the tandem rollers over any surface will be considered as two passes. When tamping rollers are used in tandem, the tamper foot spacing shall be offset so that the circumferential rows on the rear drums are in line with the midpoint of the circumferential rows of the forward drums. Each pass of the tamping roller shall overlap the preceding or adjacent pass by not less than 1.0 foot.

(2) Rubber-Tired Roller. Two complete passes over each layer will be required.

(3) Crawler-Type Tractor. Three complete passes over each layer will be required. The tractor will not be considered to be compacting while spreading materials.

3.1.2.2.4 Definition of Pass

A pass shall consist of one complete coverage of the surface of a layer by the treads of the roller, tractor, or other compacting equipment. Portions of the backfill that the compacting equipment cannot reach for any reason shall be compacted by an approved method to the density at least equal to that of the surrounding embankments.

3.1.2.2.5 Additional Compaction

If, in the opinion of the Contracting Officer, the desired compaction of any portion of the backfill cannot be secured by the minimum number of passes specified, additional complete passes shall be made over the surface area of such designated portion until the desired compaction has been obtained. An equitable adjustment in the contract price and time will be made.

3.1.2.2.6 Dressing

Unreasonable roughness of surface shall be dressed out to permit turfing operations.

--End of Section--

DIVISION 2 - SITE WORK

SECTION 02708

RELIEF WELLS

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATIONS
PART 2	PRODUCTS (Not Applicable)
PART 3	EXECUTION
3.1	GENERAL - NEW RELIEF WELLS
3.1.1	Shop Drawings and Field Procedures
3.1.2	Location
3.1.3	Depth-of-Well
3.1.4	Obstructions Encountered
3.1.5	Well Screen
3.1.5.1	General
3.1.5.2	Stainless Steel
3.1.5.2.1	General
3.1.5.2.2	Coupling
3.1.5.3	Bottom Plug for Well Screen
3.1.6	Riser Pipe
3.1.7	Gravel Packing
3.1.8	Outlet for Relief Well
3.1.8.1	Well Guard
3.1.8.2	Cover Plate
3.1.8.3	Check Valves
3.1.8.3.1	Aluminum Check Valve
3.1.8.3.2	Installation
3.1.8.3.3	"Duckbill" Elastomeric Check Valve
3.1.8.3.4	Installation
3.1.9	Drilling

	3.1.9.1	General
	3.1.9.2	Reverse Rotary Method
	3.1.9.3	Temporary Casing
	3.1.9.4	Pilot Hole Borings
3.1.10		Installation of Riser Pipe and Screen
	3.1.10.1	Assembly
	3.1.10.2	Joints
	3.1.10.3	Installation
	3.1.10.4	Plumb and Alignment
3.1.11		Placing Gravel Pack
3.1.12		Development
	3.1.12.1	General
	3.1.12.2	Surge Blocks
	3.1.12.3	Development
	3.1.12.4	Chemicals
3.1.13		Backfilling
3.1.14		Pumping Tests
	3.1.14.1	General
	3.1.14.2	Equipment
		3.1.14.2.1 Pump
		3.1.14.2.2 Water Level
		3.1.14.2.3 Flow Meter
		3.1.14.2.4 Sand Infiltration Measurement
	3.1.14.3	Data
	3.1.14.4	Procedure
	3.1.14.5	Records
3.2		PLUGGING ABANDONED HOLES
3.3		RELIEF WELL GUARD POSTS
3.4		CONCRETE
3.5		EMERGENCY WELL CLOSURE DURING CONSTRUCTION
3.6		WELL CLOSURE DURING CONSTRUCTION

SECTION 02708

RELIEF WELLS

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all plant, labor, material and equipment, and performing all operations required for proper execution of the relief well work as specified herein and/or indicated on the drawings. Such work includes installation of new relief wells; relief well outlets; guard posts; pump testing new wells; pilot hole borings and all work incidental thereto.

1.2 QUALITY CONTROL

(1) General

The Contractor shall perform the inspection, sampling and testing, corrective actions, and reports required to substantiate his compliance with the technical provisions of this specification. Responsibility for quality control of relief well construction, rehabilitation, sampling and testing procedures shall be the Contractor's. The Contractor's quality control organization shall have personnel sufficient in number to monitor at all times the relief well activities.

(2) Inspection

The Contractor's quality control organization shall be responsible to observe and control for compliance to technical specifications all relief well operations including but not limited to the following: survey layout, materials, drilling method, joints, bottom plug, materials storage, well pipe assembly and installation, backfilling, cleaning, development, pumps, pump testing, installation of outlets, chemical treatment, environmental compliance and safety. Completed relief wells shall be protected against damage and contamination. The detailed inspection may be assigned to the construction foreman supervising the work.

(3) Sampling and Testing

The Contractor's quality control organization shall verify that the well pipe material and manufacturing conforms to the specifications before delivery to the project. The particle size distribution of the gravel pack shall be sampled and tested by the Contractor using the U. S. Standard Sieves described in paragraph 3.1.7. Two representative samples shall be taken from each dump truck load

of gravel pack delivered to the project site and shall be tested for particle size distribution. The labs

performing the particle size distribution tests shall be validated and meet all requirements as specified in 3.7.2 Testing Laboratories. The gravel pack material being tested shall be stored separately from the approved stockpile until results of the gradation test results are obtained and indicate that the gravel pack meets the specified requirements. Only approved gravel pack material will be allowed for placement in the relief wells. The laboratory test procedure shall conform to that presented in EM 1110-2-1906, Appendix V, a copy of which will be furnished the Contractor upon request. A pumping and sand infiltration test and alignment and plumbness test shall be performed in accordance with technical provisions herein specified.

(4) Action Required

When quality control monitoring or testing detects non-conformance with specifications, corrective action shall be directed. The details of the irregularities and the actions directed to correct them shall be reported immediately to the representative of the Contracting Officer and included in the daily Quality Control report. Corrective action shall include steps taken to assure against recurrence of the irregularity.

(5) Reports

Reports shall include, for each new relief well, WES Form 797 "Relief Well Installation Report," WES Form 796, "Relief Well Pumping Test Report" and the completed form for the sanding test results. The gradation curves for the gravel pack material shall be submitted on ENG Form 2087, "Gradation Curves" with all gravel pack filter material being approved before placing around each relief well. A copy of each report form is attached at the end of this section. The elevation of changes between materials on these reports shall be to the nearest 0.1 foot. Data concerning installation and development of the relief well shall be included in the report on relief well installation. The pump test report shall include the time pumped and rate of flow, the draw down response data of the pumped well, and the amount of sand produced by the well during pumping. The reports shall be completely filled out and shall be submitted to the Contracting Officer as part of the daily quality control report specified in the Special Contract Requirements.

(6) Licenses and Permits

The contractor shall be responsible for having and obtaining all licenses and permits required to meet all state and/or federal requirements needed to install relief wells in the particular state or states for the proposed relief wells as stated for this project.

(7) Manufacturer Product

The Contractor shall furnish product literature on performance and operation of the valve, materials of construction, dimensions and weights, elastomer characteristics, flow data, headloss data, and pressure ratings. The manufacturer shall have at least ten (10) years experience in the production of elastomer "Duckbill" style elastomeric valves, and shall provide references and a list of installations upon request. The manufacturer shall provide shop drawings that clearly identify the valve

dimensions. Manufacturer shall have performed hydraulic tests on valves through 48 inch for flow capacity, headloss, and jet velocity at an accredited flow laboratory and shall provide test data upon request. A copy of these records and tests as well as the records of corrective action taken, shall be furnished to the Government.

1.3 APPLICABLE PUBLICATIONS

The following publications of the issues listed below, but referred to elsewhere in this section by basic designation only, form a part of this specification to the extent indicated by the references thereto:

American Society for Testing and Materials (ASTM).

A 53	Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
A 276	Stainless and Heat Resisting Steel Bars and Shapes
A 312/A312M	Seamless and Welded Austenitic Stainless Steel Pipes
A 555/A555M	General Requirements for Stainless Steel Wire and Wire Rods
C-117	Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
C-136	Sieve Analysis of Fine and Coarse Aggregates
D-1586	Penetration Test and Split-Barrel Sampling of Soils

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM) WITH CORRESPONDING CRD STANDARD INDICATED WHERE AVAILABLE.

C 31 (CRD-C 11)	Making and Curing Concrete Test Specimens in the Field
C 33 (CRD-C 133)	Concrete Aggregates
C 39 (CRD-C 14)	Compressive Strength of Cylindrical Concrete Specimens

C 94 (CRD-C 31)	Ready-Mixed Concrete
C 150 (CRD-C 201)	Portland Cement
C 171 (CRD-C 310)	Sheet Materials for Curing Concrete
C 172 (CRD-C 4)	Sampling Freshly Mixed Concrete
C 231	Air Content of Freshly Mixed Concrete by the Pressure Method

The Aluminum Association (AA) Specifications.

Specifications for Aluminum Structures Available from: Aluminum Association, Inc., 818 Connecticut Avenue, NW Washington, D.C. 20006

Federal Specifications (Fed. Spec.).

TT-E-489H	Enamel, Alkyd, Gloss Low VOC content
-----------	--------------------------------------

Steel Structures Painting Council specifications (SSPC).

SSPC-Paint 25	Red Iron Oxide, Zinc Oxide, Raw Linseed Oil and Alkyd Primer
---------------	---

Department of the Army, Corps of Engineers, Engineer Manual.

EM 1110-2-1906	Laboratory Soils Testing, 1 May 1980
----------------	--------------------------------------

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL - NEW RELIEF WELLS

3.1.1 Shop Drawings and Field Procedures

The Contractor shall submit shop drawings which present details of his methods for drilling, coupling well screen and riser sections together, installing the well screen and riser, backfilling,

developing and pump testing the well. The shop drawings shall show the well screen material, size, perforation size, shape and pattern and bottom plug material and installation detail. Also, the riser pipe and well discharge details shall be shown on the shop drawings. Any Contractor proposed substitutes or alternates in material, construction details, or methods must be presented in the shop drawings. No phase of the work shall be initiated until all shop drawings concerning that activity, have been approved.

3.1.2 Location

The location and elevation of the wells as shown on the drawings shall be located in the field by the Contractor. The results of the survey shall be available for review by the Contracting Officer. The location of the wells may be field adjusted by the Contracting Officer. The top of the relief wells shall be installed no higher than the maximum elevation for each well as shown on the drawings except as directed by the Contracting Officer.

3.1.3 Depth-of-Well

The length of well screen and length of riser pipe shall conform to the elevations shown on the drawings and to the final design as presented after the pilot hole boring data has been furnished and evaluated.

3.1.4 Obstructions Encountered

If obstructions are encountered in the foundation which, in the opinion of the Contracting Officer, render it impracticable to complete the well to the directed depth, the Contracting Officer may adjust the depth to conform to that of the obstruction. Alternatively, the Contracting Officer may direct the Contractor to abandon the well, plug the hole by backfilling in accordance with paragraph 3.2 and construct another well at an adjacent site. The Contractor shall be required to provide and use drills and equipment that are capable of drilling through insitu wood deposits within the alluvium and capable of removing cobbles up to 5-1/2 inches in diameter. The presence of cobbles up to 5-1/2 inches in diameter or insitu wood that may be encountered during drilling shall not be considered as obstructions or sufficient reason for abandonment of a well. Where obstructions are encountered, drilling shall be continued until it is demonstrated to the Contracting Officer that further efforts to advance the drill hole are impracticable. Such demonstration shall include, but not be limited to, continuing drilling operations when no gain in depth is being made for a minimum of 15 minutes. Wells which are abandoned because of impracticability of completion to the desired depth will be paid for as specified in SECTION 01025, paragraph 1.2.1(2)(b), except that payment will not be made if abandoned because of faulty operation or neglect of the Contractor.

3.1.5 Well Screen

3.1.5.1 General

Well screen shall be stainless steel and shall be of the dimensions hereinafter specified. The inside diameter of the screen shall be not less than 10 inches. Screen openings shall be uniform in size and

pattern, and shall be spaced approximately equally around the circumference of the pipe. Before installation, all well screens shall be approved by the Contracting Officer.

3.1.5.2 Stainless Steel

3.1.5.2.1 General

Stainless steel well screen shall be a non-clogging wire-wrapped continuous slot strainer equivalent to that manufactured by Johnson Division, UOP, Inc., St. Paul, MN. All pipes, rods, bars, and wire shall be stainless steel conforming to ASTM A 276, A 312 or A 555 for Grade TP-304 as applicable. The width of the clear space between the wire wrappings for the 10 inch wells shall 0.10 inch and shall provide a total opening of not less than 188 square inches per foot of 10 inch diameter screen. The screen shall have a minimum clear inside diameter of 10 inches.

3.1.5.2.2 Coupling

Couplings for stainless steel well screen shall consist of the same material as the well screen and shall be welded joint couplings. Connections between the well screen and the riser pipe shall be threaded connections or welded joint couplings. If welded connections are used, end fittings for stainless steel well screens shall be suitably beveled and furnished with welding rings of the same alloy as the well screen and riser pipe. Welding rings that join well screen to riser pipe shall adequately provide for the transition from well screen to riser pipe. Joints in riser pipe shall be single or double bevel welded and shall have strengths equal to the pipe being joined. Deposited weld metal shall have a resistance to corrosion equal to or greater than that of the pipe used. Joints shall be designed and constructed to support the weight of the screen and/or pipe as it is lowered into the hole. Welding shall be performed by a certified welder using approved welding rods, and performed in a manner which will not cause the screen sections to deviate from a straight alignment.

3.1.5.3 Bottom Plug for Well Screen

The bottom plug for each well screen shall be made of the same material and at least the same minimum thickness as the riser pipe. Plugs shall be the same diameter as the outside of the screen and fastened to the bottom of the screen in an approved manner.

3.1.6 Riser Pipe

The relief well riser pipe material and method of manufacture shall conform to the requirements specified in paragraph 3.1.5.2 above and shall be schedule 10 wall thickness. The relief well riser

pipe shall have a minimum inside diameter of 10 inches. Discharge details shall be as shown on the drawings. Couplings to the well screen and between riser pipe sections shall be as specified for well screen pipes.

3.1.7 Gravel Packing

Material for the gravel pack around the riser pipes and screens shall be washed gravel composed of hard, tough, durable particles free from adherent coating. Limestone, dolomite, or carbonate materials will not be acceptable materials. The gravel pack material shall contain neither detrimental quantities of vegetable matter nor soft, friable, thin, or elongated particles. The gravel pack shall meet the following gradation requirements:

<u>U. S. Standard Sieve No.</u>	<u>Percent by Weight Passing</u>
1/2 inch	100
3/8 inch	78-100
No. 4	50-70
No. 8	20-37
No.10	15-31
No. 16	3-16
No. 20	0-7

Materials shall be uniformly graded between the limits specified above. All points on individual grading curves obtained from representative samples of gravel pack material shall lie between the boundary limits as defined by smooth curves drawn through the tabulated grading limits plotted on a mechanical analysis diagram. The individual grading curves within these limits shall not exhibit abrupt changes in slope denoting skip grading, scalping of certain sizes or other irregularities that would be detrimental to the proper functioning of the gravel pack. For each relief well the gravel pack material and its gradation shall be approved before it is placed. The filter gravel pack material shall be pre-approved by the COR from the source quarry and meet the requirements of these specifications before individual truck loads of material shall be delivered to the project site.

3.1.8 Outlet for Relief Well

3.1.8.1 Well Guard

Each outlet shall consist of a metal well guard as shown on the drawings. The well guard shall consist of a section of 20-inch outside diameter stainless steel well screen constructed using the wire-wrapped continuous slot design method. The well screen shall be equivalent to that manufactured by Johnson Division, UOP, Inc., St. Paul, MN. It shall be fabricated by

circumferentially wrapping a triangularly shaped wire around a circular array of internal bars on one-inch centers. The wire configuration must produce inlet slots with sharp outer edges, widening inwardly so as to minimize clogging. For maximum collapse strength each juncture between the horizontal wire and the vertical bars will be fusion welded under water by the electrical resistance method. The minimum wire/weld strength shall be 650 lb. The screen and attached fittings shall be completely fabricated of stainless steel conforming to ASTM A 555, Grade TP 304. The width of

the clear space between the wire wrappings shall be 0.250 inch. The wire wrappings shall be composed of "190" wire. The surface of the well guard shall be free of pits, slag and discoloration. All welds shall be ground and brushed.

3.1.8.2 Cover Plate

The cover plate and fittings shall be fabricated of stainless steel conforming to ASTM A 276, Grade TP 304. The plate shall be 1/4-inch in thickness and shall have a diameter of 21 inches. The cover plate shall be attached to the well guard using 3/8-inch socket head cap screws. A slotted lug shall be welded on the well screen to serve as a hinge and to prevent removal of the cover plate.

3.1.8.3 Check Valves

3.1.8.3.1 Aluminum Check Valve

The aluminum check valves shall be fabricated in accordance with details shown on the drawings and as specified herein. The aluminum parts, at the Contractor's option, may be any one or a combination of aluminum alloys 3005-H14, 6061-T4, or T6. Rods shall be carefully bent to avoid flattening at the bends. The seat for the check valve is to be constructed of two 1/4-inch aluminum plates and a 1/4-inch thick neoprene gasket, all bolted together as indicated on the drawings. Drilling or punching the aluminum plates and neoprene gasket shall form the bolt holes. The neoprene gasket shall have a thickness of 1/4 inch and shall be fabricated from neoprene gasket material. The aluminum guide rods and aluminum lifting ring shall be connected by welding. Welding of aluminum shall conform to the applicable provisions of the AA Specifications for Aluminum Structures.

3.1.8.3.2 Installation

The top of the riser pipe for each well shall be fitted with an aluminum check valve. The check valve and/or a temporary cover as approved by the Contracting Officer shall be installed on top of the riser pipe immediately after installation of the riser pipe and filter gravel. The temporary cover as approved shall be used during the installation and development process only. The aluminum check valve or temporary cover shall remain in place at all times throughout the well installation and development process to prevent possible contamination or damage to the well. The only time the check valve or temporary cover shall be removed will be during pumping, development and cleaning operations. The riser pipe shall be cut at the specified elevation for each relief well or 4-inches above the top of the concrete slab. The cut shall be square, smooth and even along the top of the riser

pipe. An angular face ring shall be fabricated or purchased from a supplier conforming to ASTM A 276, Grade TP 304L or 316L stainless steel as shown on the drawings and the flange shall be a minimum of 3/16-inch in thickness. The angular face ring shall be at least the same diameter or slightly larger than the aluminum top plate of the check valve as shown on the drawings. The angular face ring shall be welded to the top of the riser pipe with the top of the ring 1/4-inch above the smooth cut on the riser pipe. The weld shall be a continuous weld of the angular face ring along

the top edge of the riser pipe. The finished product shall result in a smooth surface with no ruff edges and provide continuous support between the Neoprene gasket and top of the angular face ring.

The aluminum guide rods shall also slide freely up and down inside the riser pipe and shall be dimensioned as shown on the drawings to ensure proper seating of the check valve for the life of the relief well. The installation of the check valve shall be inspected and approved by the Contracting Officer prior to installation of each relief well outlet.

3.1.8.3.3 "Duckbill" Elastomeric Check Valve

Check valves are to be all rubber of the flow operated check type with a slip-on construction. The check valve is designed to slip over the specified pipe outside diameter and be attached by means of vendor furnished stainless steel clamps. The port area shall contour down to a duckbill, which shall allow passage of flow in one direction while preventing reverse flow. The valve shall be one-piece rubber construction with nylon reinforcement. In sizes 20 inches and large, the bill portion shall be thinner and more flexible than the valve body, and formed into a curve of 180 degrees. The company name, plate location, valve size and serial number shall be bonded to the check valve. Elastomeric duckbill check valve shall be manufactured in the United States of America. A single manufacturer shall provide all elastomer duckbill check valves. All valves shall be of the Series TF-2 as manufactured by the Red Valve Co., Inc. of Carnegie, PA 15106 or approved equal.

3.1.8.3.4 Installation

"Duckbill" Elastomeric check valves shall be installed in accordance with manufacturer's written Installation and Operation Manual and approved submittals. A manufacturer's authorized representative shall be available for installation and start-up, and to train personnel in the operation, maintenance and troubleshooting of the valve. The manufacturer shall make customer service available directly from the factory during installation of the valves. When line pressure inside the valve exceeds the backpressure outside the valve by a certain amount, the line pressure forces the valve open, allowing flow to pass. When backpressure exceeds the line pressure by at the same amount, the bills of the valve are forced closed.

3.1.9 Drilling

3.1.9.1 General

Wells shall be drilled by the reverse rotary method, in such a manner to insure proper placement of the well screen, riser pipe and gravel pack. Methods which involve radical displacement of the

formation, or which may reduce the yield of the well, will not be permitted. The use of a bentonitic type drilling fluid is prohibited. Drilling fluid additives similar and equal to "Revert" and "Fastbreak" products of Johnson Division, UOP, Inc., St. Paul, MN 55104, may be used. Drilling and installation of well screen and gravel pack shall be completed for each well without interruption.

Excavated material shall be disposed of as directed by the Contracting Officer. Before drilling operation begins on each well, the Contractor shall demonstrate that all material, equipment, and experienced personnel are mobilized and that all equipment necessary for the job is adequate for an

efficient operation and is operating in a satisfactory manner. Loss of a hole or well because of lack of material, inadequate or faulty equipment, or careless operating procedures will be considered cause for an abandoned well due to fault or negligence of the Contractor.

3.1.9.2 Reverse Rotary Method

The diameter of the hole shall be such as shall permit the placement of the minimum thickness of gravel pack as specified in paragraph 3.1.11. The drilling fluid (not a bentonite or other expansive clay system) shall be a suspension of fine-grained soil or shall be a commercial product of a recognized manufacturer. The drilling fluid shall have the characteristic of being readily removable from the gravel pack and the walls of the formation by development methods as specified in paragraph 3.1.12. If the walls of the hole above the top of the gravel pack require support during development operations, a temporary casing similar to that specified in paragraph 3.1.9.3 shall be placed so as to extend from the ground surface to at least three feet below the top of the gravel pack material.

3.1.9.3 Temporary Casing

A temporary well casing of either iron or steel, new or used, may be used to support the sides of the entire hole during drilling and placement of screen, riser pipe, and gravel pack and to support the sides of the unbackfilled portion of the hole during development of the well. Any temporary casing shall have an inside diameter large enough to provide the minimum gravel pack thickness, as specified in paragraph 3.1.11, entirely around the well screen or riser pipe and shall have sufficient thickness to retain its shape and maintain a true section throughout its depth, and may be in sections of any convenient length. The temporary casing shall be securely anchored to the drill rig or ground surface at all times until removed. The temporary casing shall be such as to permit its removal without interfering with the gravel pack or riser pipe. Methods of installation that will create a cavity outside the temporary casing will not be permitted.

3.1.9.4 Pilot Hole Borings

Prior to drilling the relief wells, the Contractor shall drill a pilot hole at each well location indicated on the drawings and at any additional locations determined necessary by the Contracting Officer. Pilot holes may be drilled by any method approved by the Contracting Officer which will allow the recovery of samples as described below. Samples shall be obtained with a standard split spoon sampler, (inside diameter of 1-3/8 inch), and shall be driven by any method approved by the Contracting Officer to obtain samples 18 inches in length. Blow counts will not be required unless as

specified below. The pilot holes shall be located within 5 feet of the well locations. Drilling fluid additives shall be as discussed in 3.1.9.1 above. The bottom elevation of the pilot holes shall be (15) feet below the elevation of the bottom of the well screen as indicated on the drawings, as applicable to each well location. Pilot holes shall be continuously drilled to an elevation 10 feet less than the approximate riser pipe lengths shown in the (Relief Well Location Table on Drawing Number 3) from the ground surface. Sampling shall begin at this elevation unless sand is encountered during the continuous drilling of the hole. If sand is encountered, then sampling shall begin at the clay/sand

interface. Samples shall be taken at 2-1/2 foot intervals or change of strata, whichever occurs first for the next 40 feet of each pilot hole. After 40 feet of sampling, the sampling interval shall change to every 5 feet for the remainder of the hole. Samples may be removed less than 18 inches in length if the total blow counts for the sample reaches 180. If samples are removed before reaching 18 inches in length due to the maximum blow count per sample, then the blow counts shall be documented by the driller. Beginning with the first non-cohesive sample, all samples shall be washed in accordance with ASTM C 117 and shall undergo a sieve analysis test in conformance with ASTM C 136. Samples taken shall assist in determining the elevation at which the well screen and riser pipe shall be set and to assist in confirming the possible location of blank areas. A field-boring log shall be maintained for each pilot hole drilled. This data shall be recorded on Form LMM 650 Jan '64 "Field Boring Log", a copy of which is attached at the end of this section. The Contractor shall submit the logs of the pilot borings, the samples and results of sieve analysis tests obtained from the pilot borings with the depths from which samples were obtained, the elevations at which soil strata changes occur, and any other information available from the pilot boring to the Contracting Officer. The Contracting Officer shall then make a determination as to the lengths and locations of well screen, blank pipes between screen sections and riser pipe to be installed in each well. The Contractor shall provide the sieve analyses data through a Microsoft Excel spread sheet provided by the Memphis District for each boring. A copy of each sieve analysis results shall be emailed to both the Memphis District Geotechnical Engineering Branch and the Wynne Area Office. After receipt of the required information from the pilot hole described above, the Contracting Officer will make a determination and convey it to the Contractor within 10 working days. Lengths and locations of screen and riser pipe shall be approximately as shown on the drawings but will be subject to change based on the results of the sieve analysis from the pilot hole boring data.

3.1.10 Installation of Riser Pipe and Screen

3.1.10.1 Assembly

All riser pipe and screen shall be new and in good condition before installation and all couplings and other accessory parts shall be securely fastened in place. The successive lengths of pipe shall be arranged to provide accurate placement of the screen sections in the soil strata. The use of lengths of screen and riser shorter than 15-ft. long will not be permitted unless previously approved by the Contracting Officer. The bottom of the screen and riser assembly shall be equipped with an appropriate centering guide which will satisfactorily center the assembly in the hole and hold it securely in position while the gravel pack material is being placed. The centering guide should be placed on the bottom of the screen and have a minimum diameter no less than one and one half

inches of the diameter of the drilled hole and ensure minimum clearance needed for placement of the gravel pack. The centering guide or guides should be designed and attached so that natural material removed from the sides of the drilled hole during installation shall be at a minimum. Centering guides (also at a minimum diameter of 1 and 1/2 inches less than the diameter of the drilled hole) may be placed at other locations along the screen and riser pipe assembly provided they do not interfere with placement of gravel pack material as specified in paragraph 3.1.11. If a centering guide apparatus or ring is used for placement of the gravel pack that will slip around the well screen and riser pipe, then the guide apparatus shall also have a minimum diameter of 1 and 1/2 inches less than

the diameter of the drilled hole (or on all four sides) ensuring correct alignment along the entire length of the relief well.

3.1.10.2 Joints

Sections of relief well pipe shall be jointed together as specified in paragraph 3.1.5.2.2. Joints shall be designed to provide strength capable of supporting the weight of the relief well stem as it is lowered into the hole.

3.1.10.3 Installation

The Contractor shall be required to install, develop and test at least one well to insure compliance with the specifications before installation of the 6th well is allowed. Results of all tests must be submitted to the Contracting Officer prior to beginning the installation process of the 6th well. The assembled riser pipe and screen shall be placed in the hole in such manner as to avoid jarring impacts and to insure that the assembly is centered and not damaged or disconnected. After the screen and riser pipe have been placed, a gravel pack shall be constructed around the screen section as specified in paragraph 3.1.11 and the well developed as specified in paragraph 3.1.12. The top of the riser pipe shall be held at the designated elevation as shown on the drawings during placement of the gravel pack. Immediately after the installation of the well screen and riser pipe assembly, the depth of the well shall be measured by means of an approved sounding device.

3.1.10.4 Plumb and Alignment

Each well shall be installed and maintained straight and plumb during placement of gravel pack and development. Immediately before placing the gravel pack and with the top of the well fastened securely in a vertical and horizontal position, an alignment test shall be conducted in the presence of the Contracting Officer. Excessive misalignment or deviation from plumb shall be corrected before placing the gravel pack. The alignment test shall consist of two 10-ft sections of standard 8-inch diameter pipe coupled together with a 9.5-inch OD coupling lowered inside the well for the full depth of the well and withdrawn without binding against the sides of the well screen or riser pipe. The Contractor shall furnish the above apparatus and shall perform the alignment tests. The Contractor shall notify the Contracting Officer a minimum of 8 working hours prior to performing the alignment tests. After completion of the alignment test, the Contracting Officer may elect to perform a plumb test before placement of the gravel pack. This test, if performed, will be at the

expense of the Government using Contractor-furnished equipment and shall consist of a plumb-line run from the top of the well to the bottom of the well. A variation of 12-in. per 100-ft, will be permitted in the combined length of screen and riser pipe of the well. In the event the Contracting Officer elects to perform the plumb survey prior to gravel pack placement and the well fails to conform to the standard described above, the Contractor, at no additional expense to the Government, shall correct the plumb of the well. The Contractor shall provide assistance to the Contracting Officer in performing the plumb test, if requested.

3.1.11 Placing Gravel Pack

After the screen and riser pipes have been placed, and alignment surveys and plumb surveys (if performed) are conducted, the gravel packs shall be placed through two 4-in. I.D. tremies with no obstructions. The tremie hopper shall be so constructed and balanced that gravel pack material will feed freely and equally to two (2) tremie pipes located at 180 degrees on each side of the screen. Connections between the tremie pipe and the hopper shall be designed for quick connection or disconnection for adding or removing tremie pipe with least possible delay. Tremie pipe shall consist of equal 10-ft lengths of standard 4-in. pipe with 1/16-in. wide equally spaced slotted openings. Tremie pipe shall contain no dents, flat spots, damaged threads, or holes, and shall be reamed and/or deburred to full I.D. of the pipe. The tremie guide shall consist of a metal ring or rings of sufficient inside diameter to slip freely over riser pipe and screen with 4-in. collars welded to the guide at 180 degrees to securely hold the tremie pipe in place. If this metal ring/rings or apparatus is also used as a centering device for correct alignment of the relief wells, then the ring/rings or apparatus shall have a minimum outside diameter of one and one half inches less than the diameter of the drilled hole for each well. This apparatus does not have to be continuous in diameter around the relief well pipe but shall have the minimum clearance on all four sides ensuring that the relief well pipe will be centered in the hole and the gravel pack will be evenly distributed around the pipe. The Contractor shall be equipped to efficiently add gravel pack material to the hopper in any position from the ground surface to the maximum height of the hopper. No material shall be allowed to enter the well except through the tremie pipes. At no time shall tremie guide or pipes be raised, lowered or supported by only one pipe. Ten feet of tremie pipe shall be installed below the lower tremie guide. The gravel pack material shall be placed in an approved manner and without significant segregation. The gravel pack shall have a minimum thickness of 6 in. between the outside of the well screen and the outside of the gravel pack and shall be placed above the top of the well screen to the level shown on the drawings. At the commencement of placing operation, the tremie shall rest on the bottom of the hole and it shall be filled with gravel pack material. The tremie shall then be raised in increments approximately equal to the increments of the gravel pack placed. At all times during the placing of the gravel pack, the tremie shall be kept filled to within five (5) feet of its top. If temporary casing is used, the gravel pack shall be placed in increments not to exceed 2 ft; the tremie and temporary casing shall be raised in small increments approximately equal to the increments of the gravel pack placed, except that at no time prior to the completion of placement of the gravel pack shall the bottom of the casing be less than 1 ft. below the top of the gravel pack in the hole. The Contractor shall provide a means of measuring the gravel pack in the hole and also provide a means of measuring the gravel pack depth. The alternate placing of gravel pack material and withdrawing of the tremie and temporary casing shall be continued until the gravel pack has been placed to the level shown on the drawings. During the development of the well, the top of the gravel pack material shall be maintained at the level shown on the drawings. Prior to and during placement of the gravel pack, the top of the temporary casing or hole shall be covered or otherwise shielded to prevent the gravel pack from entering the space around the well except through the tremie pipe. Material that may have entered the well screen and riser pipe shall be removed before development of the well is commenced. Construction of the relief well outlets specified in paragraph 3.1.8 above or of the backfilling specified in paragraph 3.1.13 below shall not commence until the development of the well is completed and the gravel pack has been placed to the elevation shown on the drawings. The filter material may be pumped into the well using two 4-inch tremies with no obstruction as stated above provided the Contractor can pump the gravel pack without

significant segregation of the gravel pack material and can pump in a continuous manner. A plan shall be submitted to the Contracting Officer and, if approved, a well shall be installed and tested before production installation proceeds.

3.1.12 Development

3.1.12.1 General

Following placement of gravel pack materials, the Contractor shall develop the relief well to remove all fines from the well and gravel pack so as to produce a stable well of maximum efficiency. Well development shall be by mechanical procedure (surging) and air pumping. The Contractor shall start the well development and testing process no later than 5 days from the installation of well screen riser and gravel pack. At the time of development of any relief well, the well shall be free of draw down or surcharge effects due to pump testing, developing or drilling at another location. The Contractor shall be responsible for maintaining at the relief well the needed access and work area and clearance in the relief well necessary to accomplish development. The Contractor shall furnish, install or construct the necessary discharge line and troughs to conduct and dispose of the discharge a sufficient distance from the work area to prevent damage. Development shall be conducted to achieve a stable well of maximum efficiency and shall be continued until little or no additional material from the foundation can be pulled through the gravel pack. As development proceeds, gravel pack material shall be added to the annular space around the screen to maintain the top elevation of the gravel pack to the specified elevation. The Contractor shall provide a bubbler tube or other approved means for accurately determining the water level in the well under all conditions. If, at any time during the development process, it becomes apparent in the opinion of the Contracting Officer that the well may be damaged, development operations shall be immediately curtailed. The Contracting Officer may require a change in method if the method selected does not accomplish the desired results. The Contracting Officer may order that wells that continue to produce excessive amounts of fines after development be abandoned, plugged, and backfilled, and may require the Contractor to construct new wells nearby. All materials pulled into the well by the development process shall be removed prior to performing the pumping test.

3.1.12.2 Surge Blocks

Surge blocks shall consist of two groups of neoprene rubber circular disks spaced 4 feet apart and held in place by washers and spacers. Each group of disk shall consist of a one-inch thick, nine-inch diameter rubber disk, with a one-inch thick, eight-inch diameter rubber disk on either side for 10-inch wells. The surge block for a 10-inch well should be composed of a one-inch thick, nine-inch diameter rubber disk, with a one-inch thick 8-inch diameter rubber disk on either side. This combination of rubber disks shall be fixed between rigid washers 2-1/2- to 3-1/2-inches in diameter. The entire assembly shall be rigidly attached to the end of a drill stem or pipe of sufficient mass to cause it to fall free on the downward stroke. The disks shall be replaced whenever they become worn. The Government may require the Contractor to vary the number of disks and increase the rigid washers to a diameter of 4-inches to result in the most effective surging action and yet be flexible enough to prevent damage to the well. The Government may also require the Contractor to make

other minor changes in the design of the surge block as the work proceeds in order to accomplish a more thorough surging action without damage to the well. The surge block shall be operated by equipment capable of varying speeds over the full depth of the wells. The equipment shall be capable of traversing and maintaining the velocity of surge block travel along the well screen at a rate between 1-1/2 and 3 feet per second in both down and up directions. The Contractor shall submit for approval shop drawings for the surge block.

3.1.12.3 Development

Development of wells shall not commence until drilling additives allowed by paragraph 3.1.9.1 (if used) have completely broken down and the chemical treatment specified in paragraph 3.1.12.4 has been completed. The development of wells shall consist of pumping with air to create flow from the well including removal of sediments and operating a double surge block inside the well screen in such a manner to achieve a stable well of maximum efficiency. The static water surface in the well shall not be lowered below the top of the screen during development operations unless permission is given by the Contracting Officer. Immediately following completion of the specified chemical treatment, the Contractor shall measure the depth of the well to record to the nearest .10-foot the depth of the well. This measurement shall be compared with the actual depth of the well to determine if there is any material that has settled to the bottom during the chemical operations before beginning development. The Contractor shall perform sufficient cycles of development until little or no sand can be pulled into the well but must complete three cycles per well as a minimum. Each cycle shall consist of one phase of surging and one of air pumping. The well shall be surged at a rate of between 1.5-3.0 feet per second along the well screen and in a manner such that the surge block shall not impact the bottom of the well. Surging shall proceed for a minimum of 60 minutes per phase. The Contractor shall make continuous adjustments in the length of travel of the surge block to avoid impacting the surge block on the bottom of the well. Development shall begin above the screen and move progressively downward to prevent the surge block from becoming sand locked. The initial surging motion should be relatively gentle and begin in the riser pipe 10 to 15 feet below the static water level. After waiting 5 minutes following completion of each surging phase, the Contractor shall measure and record to the nearest .10-foot, the depth to the top of any material that has been brought into the well and settled at the bottom. Upon completion of each surging phase the well shall be air

pumped at a rate of up to 500 g.p.m. for a minimum of thirty minutes to remove sediment material as directed by the Contracting Officer or may use another method for removing sediment if approved by the Contracting Officer. At the conclusion of the development process, the well shall be subjected to a period of intermittent pumping. This shall be performed by pumping the well at a capacity sufficient to produce a rapid draw down in the well of approximately 5- to 10-feet. The pump shall then be stopped. There shall be no backflow through the pump. The Contractor shall then permit the water surface to rise to its former elevation and then repeat the procedure. Cycle time for this procedure shall vary as directed but shall not be more than 3 cycles per minute. A turbine or centrifugal type pump shall be used with any attachment(s) necessary to accomplish rapid starting and stopping for intermittent pumping. The pump intake shall be set between 2- and 6-ft from the bottom of the well. The amount of draw down or rate of pumping during the intermittent pumping

may be adjusted by the Contracting Officer if in the opinion of the Contracting Officer, the efficiency of the well might be positively affected. Intermittent pumping shall be continued for one hour after which time all material remaining in the well shall be removed. Before removal of sediment in the well, the Contractor shall record the amount of sediment in the bottom of each well after each cycle of development and provide the information to the Contracting Officer. The sediment shall also be recorded after the one-hour intermittent pumping cycle for each well with a zero value given if no sediments are present.

3.1.12.4 Chemicals

To assist in dispersing and removing fines and drilling fluid from the walls of the drilled hole and from the gravel pack, chemicals shall be added to the well between 24 and 36 hours before development of the relief well. Following initial installation of the well screen and riser assembly and placement of the gravel pack and cleanout of the well, calcium hypochlorite (example: HTH) with a minimum of 70 percent available chlorine in the amount of one pound per 100 gallons of water in the well shall be dissolved in water and poured into the well. The chemicals shall be mixed in the well by slowly injecting compressed air at the bottom of the well for a period of 2 hours or by other methods as approved by the Contracting Officer. No discharge from the well shall be allowed during mixing. The chemicals in the well shall be agitated by the method described above for two hours at 8-hour intervals with the last agitation being immediately prior to initiation of development of the relief well.

3.1.13 Backfilling

After the well has been developed and pump tested as stated below, the annular space above the gravel pack shall be backfilled by first placing a minimum 12-inch layer of sand conforming to fine aggregate for concrete as specified in ASTM C 33 on top of the gravel pack and then filling the remainder of the space up to the concrete slab with a grout mix of one bag (94 lbs) of cement to 5 gallons of water with a bentonite-cement ratio of 1 part bentonite to 30 parts cement. This grout mix shall be injected at the bottom of the annular space to be grouted under a maximum pressure of 10 psi. A concrete slab with concrete conforming to the requirements as specified in paragraph 3.4 below shall be placed above the grout, as shown on the drawings. The temporary casing, if used,

shall be withdrawn in increments as the grout is placed. The Contractor shall fill with impervious material to original grade all pits such as that incidental to the reverse rotary method of drilling.

3.1.14 Pumping Tests

3.1.14.1 General

Upon completion of installation, jetting, and development pumping, and before final acceptance, each well shall be subjected to a pumping test. The test pumping and sand infiltration tests hereinafter specified may be performed before placement of the grout mix prescribed in paragraph 3.1.13, except that the concrete slab shall not be placed prior to completion of the pumping and sand infiltration tests. In no event shall the pumping tests be performed when the ground water table at

the well is less than 10 feet above the top of the well screen. Prior to commencement of the pumping test, the Contractor shall provide approved means for accurately determining the water level in the well under all conditions. The Contractor shall furnish and install a flow meter of standard design for the purpose of measuring the discharge from the well during the pumping test. The Contractor shall furnish, install, or construct the necessary pipe discharge line, troughs, or ditches necessary to dispose of the pumping test discharge a sufficient distance from the work area to prevent damage. After completion of the test, the depth of the well shall be measured, by means of an approved method, under the direction of a representative of the Contracting Officer and the amount of sediment in the bottom of the well from the pump test shall be recorded.

3.1.14.2 Equipment

3.1.14.2.1 Pump

The Contractor shall provide a pump capable of producing the specified draw down over a period of time sufficient to satisfactorily perform the pumping test specified. The use of deep well pumps will be permitted provided that the pump itself is kept within the riser pipe, and the Contractor demonstrates that all specified requirements of pumping and sand measurement can be complied with. The pump shall be complete with gasoline, diesel, or electric motor. In case an electric motor is used, the Contractor shall provide, without additional cost to the Government, the electrical power and the necessary wiring that he will remove at the completion of the pumping test.

3.1.14.2.2 Water Level

The Contractor shall provide means for accurately determining the water level in the well under all conditions. This means of measurement shall be capable of determining the water level in the wells before, during, and after pumping tests. The use of a weighted tape shall not be regarded as sufficiently accurate for such measurement.

3.1.14.2.3 Flow Meter

The Contractor shall furnish and install a calibrated flow meter of standard design for the purpose of measuring the discharge from the well during the pumping test. The calibration of the flow meter shall be checked at periodic intervals.

3.1.14.2.4 Sand Infiltration Measurement

A sand infiltration test shall be conducted for the purpose of determining whether sand and/or material is being removed from around the well when the well is discharging flow or more specific during the required pump test for each relief well installed. The Contractor shall measure the amount of sand infiltration from each relief well during pump testing using a Rossum centrifugal sand sampler or an approved equal. The pump discharge line shall be fitted with the necessary fittings to properly conduct the test. The Contractor's employee shall be experienced in conducting the sand infiltration test including placing the sampler at the proper location along the discharge line,

calibrating the proper flow into the meter, and experienced in reading the amount of sand in the sampler. The sand infiltration test shall be conducted and monitored for a minimum of 30 minutes per pump test and shall begin within the first hour of the pumping test. If the amount of sand collected is less than the first readable unit of measure on the sampler, then a trace or an amount less than the minimum readable on the scale shall be recorded (do not try to estimate the amount of sand if it is not a readable amount). The attached sand infiltration test data sheet shall be filled out completely for each test conducted and furnished to the Contracting Officer. If the test fails and additional well development is required, then this information shall also be placed on the data sheet.

3.1.14.3 Data

As a minimum the following test data items shall be obtained and recorded by the Contractor on WES Form 796, a copy of which is attached at the end of this section. The Contracting Officer shall check the last two items.

Time of observation.

Depth of water in well before, during, and after pumping.

Flow in gpm.

Elevation of water in well before and after pumping.

Elevation of water in adjacent wells or piezometers before and during pumping, when requested by the Contracting Officer.

The depth of sand in well before, during, and after pumping.

Amount of sand pumped out of well as recorded from the sand infiltration test.

3.1.14.4 Procedure

The pumping and sand infiltration tests shall be conducted under the direction of the Contracting Officer. The Contractor shall test each well by pumping continuously for a minimum of two hours. The pumping shall be at a constant rate sufficient to produce either a draw down of 10 feet or a production of 500 gpm. No test pumping of a well will be permitted concurrently with drilling, surging, or pumping of any other well within 200 feet therefrom. In the event that the test is interrupted, other than by order of the Contracting Officer, prior to the completion of the specified period of continuous operations, the test shall be re-run at no additional expense to the Government. In addition to the test described above, the Contracting Officer may direct the Contractor to perform additional testing. Such additional testing shall conform in general to the requirements specified above with the exception that the Contracting Officer will determine the duration of the tests and the approximate draw down. The test, to be successful, shall be continuous throughout the specified period. In the event that sand or other material infiltrates into the well as a result of the pumping

test, the following procedure will be followed: If the rate of sand infiltration during the latter part (last hour) of the two hour pumping test has not been reduced to one pint or less per 25,000 gallons pumped (5 parts per million, ppm), the well shall be resurged by manipulation of the test pump for 20 minutes after which the test pumping shall be resumed and shall be continued at the constant rate specified above until the sand infiltration rate is reduced to less than one pint per 25,000 gallons, but not for more than a total of eight hours. If at the end of eight hours of pumping the rate of infiltration of sand is more than one pint per 25,000 gallons pumped, the well shall be abandoned. However, the Contractor may continue the test pumping and perform such other approved remedial work, as he considers desirable, at his own expense. After such additional test pumping and other remedial measures, the sand infiltration rate of a well is reduced to not more than one pint per 25,000 gallons pumped, the well will be accepted. Abandoned wells shall be plugged in accordance with paragraph 3.2 below and a new well installed nearby. Upon completion of the pumping test, any sand or filter material in the bottom of the well shall be recorded and removed by pumping or by other approved methods, after which the Contractor shall remove all equipment, discharge lines, etc., and shall backfill any excavated areas.

3.1.14.5 Records

The Contractor shall obtain and furnish to the representative of the Contracting Officer for record purposes the elevation of the water in each well before and after the development pumping, the flow in gpm at the completion of the pumping and the time of observation. The water surface elevation shall be obtained immediately before starting the surge pump and the water surface elevations and flow shall be obtained just before stopping the pump upon completion of the development pumping. This data shall be recorded on WES Form 797, a copy of which is attached at the end of this section.

3.2 PLUGGING ABANDONED HOLES

New wells ordered abandoned by the Contracting Officer for any reason shall be filled with a neat cement grout as specified in paragraph 3.4. For wells ordered abandoned, the screen and riser pipe shall be salvaged from the hole, if possible. For wells ordered abandoned where the Contracting Officer determines that it is impossible or impractical to salvage the screen and riser pipe, the well shall be grouted with the screen and riser assembly in place. The riser pipe shall be removed for a minimum depth of two feet below natural ground. Once grout has been placed, the top 2 feet below natural ground shall be backfilled with cohesive soils. The grout shall be injected through a pipe with a tip within three feet of the bottom of the well and forced upwards towards the surface. When the grout reaches the surface, it shall be allowed to flow to waste until the Contracting Officer determines that the grouting has been satisfactorily accomplished. The grout shall be injected at a maximum pressure of 1/2 psi per foot of depth of the hole. The grout mix shall consist by weight of one part Portland cement, 4 parts sand, 2 parts Bentonite and shall be mixed with sufficient water to provide a 6" to 8" slump.

3.3 RELIEF WELL GUARD POSTS

Upon completion of the relief well outlet structures for the new wells, the Contractor shall furnish and install four (4) concrete filled steel pipe guard posts, anchored in concrete, around each well as indicated on the drawings. Steel pipe shall be black steel pipe conforming to the requirements of

ASTM A 53, Schedule 40. Concrete shall conform to the requirements of paragraph 3.4 below. After installation, the aboveground portions of the pipe guard posts shall be given one coat of paint conforming to the requirements of SSPC-Paint 25, followed by two (2) coats of yellow paint conforming to the requirements of Fed. Spec. TT-E-489, the specific color to be selected by the Contracting Officer.

3.4 CONCRETE

Concrete shall conform to the requirements of ASTM C 31, C 33, C 39, C 94, C 150, C 171, C 172, and C 231. Concrete shall have a minimum compressive strength of 4,000 psi. Concrete shall consist of one part Portland cement; two parts clean, washed sand; three parts of 1-inch maximum size, clean, well-graded, hard-surfaced coarse aggregate; a suitable air-entraining admixture; and sufficient water to produce a slump between one and four inches. Entrained air shall be six (6) percent, plus or minus 1-1/2 percent. The concrete shall be mixed in a manner so as to produce a mixture having a consistency that will permit placement as indicated on the drawings. Concrete mixed at the job site shall be used in the work within 45 minutes after mixing. Concrete mixed at a commercial mixing plant and transported to the job site in trucks shall be used in the work within 1-1/2 hours after mixing. Retempering of concrete will not be allowed. Concrete shall not be placed when the ambient temperature is below 40 degrees F or above 85 degrees F unless otherwise approved by the Contracting Officer in writing; nor when the concrete, without special protection, is likely to be subjected to freezing temperatures before final set has occurred. Prior to placing concrete, all surfaces upon which the concrete is to be placed or placed against, shall be wetted. Concrete shall be thoroughly consolidated after placement by suitable vibrators or by rodding. Concrete shall be given a trowel finish and shall be cured by keeping the surface continuously wet for a period of not less than 72 hours or by application of an approved curing compound. Submittals shall conform to the Special Contract Requirements, SECTION 00800, paragraph 1.32.

3.5 EMERGENCY WELL CLOSURE DURING CONSTRUCTION

Well construction will not be permitted during periods of high groundwater, during periods prior to high predicted river stages or during other emergencies as directed by the Contracting Officer. All remediation measures will be directed by the Contracting Officer. The Contractor or his representative shall be available at all times during any declared emergency. During periods of high groundwater or high river stages, the Contracting Officer may direct the Contractor to restrict all flow from the wells or may allow the completed/partially completed wells to flow without additional adjustments. If directed by the Contracting Officer, wells shall be plugged with a mechanical test plug to prevent flow from the wells. The mechanical test plug shall be a pipe stem test plug with a bypass, and shall be capable of withstanding maximum water pressure equivalent to 20 feet of head. The mechanical plugs will be provided by the Contractor at no additional cost to the government. The Contracting Officer may also direct the Contractor to temporarily fill the space between the riser pipe and the drill hole for any partially completed well.

3.6 WELL CLOSURE DURING CONSTRUCTION

All holes for temporary casing exceeding 3 feet in depth shall be covered. All wells not having permanent well guards installed should be plugged with a mechanical test plug of the type specified in paragraph 3.5 above.

-- End of Section --

DIVISION 2 - SITE WORK

SECTION 02936

ESTABLISHMENT OF TURF

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	AREAS TO BE TURFED
PART 2	PRODUCTS
2.1	MATERIALS
2.1.1	Fertilizer (and Limestone)
2.1.2	Mulch
2.1.2.1	General
2.1.2.2	Wood Cellulose Fiber Mulch
2.1.3	Water
2.1.4	Spot Sod
2.1.5	Sprigs
2.1.6	Soil for Repairs
2.2	SAMPLING AND TESTING
2.2.1	General
2.2.2	Soil Testing
2.2.3	Material Testing
2.2.3.1	Fertilizer and Limestone (If used)
PART 3	EXECUTION
3.1	COMMENCEMENT, PROSECUTION, AND COMPLETION
3.1.1	General
3.1.2	Sequence of Work
3.2	PREPARATION OF GROUND SURFACE
3.2.1	General
3.2.2	Clearing
3.2.3	Dressing
3.3	SPECIAL EQUIPMENT
3.4	APPLICATION OF FERTILIZER AND/OR LIMESTONE (IF USED)
3.5	SPOT SODDING

- 3.6 SPRIGGING
- 3.7 APPLYING AND ANCHORING MULCH
- 3.8 HYDRAULIC SLURRY METHOD
- 3.9 ESTABLISHMENT
 - 3.9.1 General
 - 3.9.2 Maintenance
- 3.10 INSPECTION AND ACCEPTANCE
 - 3.10.1 General
 - 3.10.2 Areas Requiring Returfing

DIVISION 2 – SITE WORK

SECTION 02936

ESTABLISHMENT OF TURF

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all plant, labor, equipment, and materials, and performing all operations necessary for establishment and mowing of turf on areas either as specified herein or as shown on the drawings.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for turfing operations to assure compliance with the contract requirements and shall maintain records of his quality control for all construction operations, including, but not limited to, the following:

(1) Soil Testing

The tests are specified in paragraph 2.2.2 below.

(2) Preparation of Ground Surface

Location and quality of finish dressing, including necessary clearing, filling, or dressing out of washes, smoothness and uniformity of surfaces, and time of year.

(3) Fertilizing (and Liming)

Quality of materials, area fertilized (and limed), quantity applied, and method of application.

(4) Type of Turf

Quality, source, placing, covering, and compaction effort.

(5) Mulching (If Used)

Type of materials, area mulched, quantity applied, method of application.

(6) Maintenance and Repair

Location and type of maintenance problems and remedial treatment performed.

(7) Watering (If Used)

Quality of water, area watered, quantity applied, and method of application.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 AREAS TO BE TURFED

Turf shall be established on all surfaces of the embankment placed under this contract, areas disturbed by haul roads, except on areas to receive other types of surfacing, and all other disturbed areas.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Fertilizer (and Limestone)

If the Contractor elects to use fertilizer, the fertilizer shall meet the requirements of the State of Mississippi for commercial fertilizer. Fertilizer shall consist of a mixture containing nitrogen, phosphorous, and potash, and shall be uniform in composition and free-flowing. The fertilizer may be delivered to the site in bags or other convenient containers or delivered in bulk. If delivered in bags or containers, the fertilizer shall be fully labeled in accordance with the applicable fertilizer laws of the State of Mississippi, and shall bear the name, tradename or trademark, and warranty of the producer. Should the commercial fertilizer be furnished in bulk, the Contractor shall furnish certified weight tickets and a certified quantitative analysis report, in triplicate, from a recognized testing laboratory certifying the nutrient ratio of the materials. In the event the commercial mixture is delivered to the job site in the original containers, unopened, the analysis report will not be required. Quantity of fertilizer (and lime), if used, required per acre shall be determined by certified soil tests as specified in paragraph 2.2.2 below. Limestone shall be approved agricultural grade limestone containing not less than 85 percent total carbonates. Limestone shall be ground to such fineness that 25 percent will pass a 100-mesh sieve and 100 percent will pass an 8-mesh sieve.

2.1.2 Mulch

2.1.2.1 General

If the Contractor elects to use mulch to protect the turfed areas, the material used for mulching shall be materials that do not contain noxious grass or weed seed that might be detrimental to the turfing being established or to adjacent farmland.

2.1.2.2 Wood Cellulose Fiber Mulch

Wood cellulose fiber mulch for use with hydraulic application equipment shall consist of wood cellulose fiber, processed to contain no growth or germination inhibiting factors, and dyed an appropriate color to facilitate visual metering of application of the materials. The wood cellulose fiber shall contain not in excess of 10 percent moisture, air dry weight basis. The wood cellulose fiber shall be manufactured so that after addition and agitation in slurry tanks, with water, and any other additives, the fibers in the material will become uniformly suspended to form a homogeneous slurry; and that when hydraulically sprayed on the ground, the material will form a blotter-like ground cover which, after application, will allow the absorption of moisture and allow rainfall or mechanical watering to percolate to the underlying soil. The Contractor shall be prepared to submit, on request, certification from the supplier that laboratory and field testing of the product has been accomplished, and that the product meets the foregoing requirements.

2.1.3 Water

If the Contractor elects to use water as an aid to establish turf, the water used shall be free of injurious quantities of oil, acid, alkali, salt, and other substances harmful to growth of grass.

2.1.4 Spot Sod

If the Contractor elects to spot sod, the sod used to turf the areas specified shall contain a minimum of 85 percent Bermuda grass. Each piece of sod shall have an area of not less than 16 square inches and shall have not less than 2 inches of earth adhering to the roots. Sod that contains noxious grasses and weeds that might be detrimental to the turfing being established will not be acceptable.

2.1.5 Sprigs

If the Contractor elects to sprig, the sprigs used to turf the areas specified shall consist of Bermuda grass. Sprigs that contain noxious grasses and weeds that might be detrimental to the turfing being established will not be acceptable.

2.1.6 Soil for Repairs

For fill of areas to be repaired, soil shall be of a quality at least equal to that which exists in areas adjacent to the area to be repaired. Soil used shall be free from roots, stones, and other materials that hinder grading, planting, and maintenance operations and shall be free from objectionable weed seeds and toxic substances.

2.2 SAMPLING AND TESTING

2.2.1 General

Sampling and testing shall be the responsibility of the Contractor and shall be performed at no additional cost to the Government. Sampling and testing shall be performed by a recognized testing agency.

2.2.2 Soil Testing

Prior to beginning turfing operations, soil from the areas to be turfed shall be tested to determine soil nutrient and limestone requirements. At least one sample per acre shall be tested. Certified test results, and application rates for nitrogen, phosphorous, potash, and limestone (if required), indicated by the soil tests shall be furnished to the Contracting Officer prior to fertilizing.

2.2.3 Material Testing

2.2.3.1 Fertilizer and Limestone (If used)

Duplicate signed copies of invoices from suppliers shall be submitted to the Contracting Officer. Invoices for fertilizer shall show quantities and the percentages of nitrogen, phosphorous, and potash. If limestone is used, the limestone invoice shall show the quantity and the percentages of limestone that pass the 100- and 8-mesh sieves. Upon completion of the project, a final check of the total quantity of fertilizer used will be made against total area treated, and if minimum rates of application have not been met, an additional quantity of material sufficient to make up the minimum application rate shall be distributed as directed.

PART 3 EXECUTION

3.1 COMMENCEMENT, PROSECUTION, AND COMPLETION

3.1.1 General

The dressing and turfing operation for embankments shall commence as soon as practicable following the completion of construction in an area. Dressing and turfing operations on other areas shall commence upon completion of all work in that area. Prior to prosecuting the turfing operation, the Contractor shall repair rainwash, if any, dress, and prepare the areas for turfing. All turfing operations shall be accomplished during the season between 1 March and 30 June, or between 1 September and 15 November, inclusive, unless otherwise authorized by the Contracting Officer.

3.1.2 Sequence of Work

The sequence of operations for work prescribed in this section shall be as follows:

- (1) Preparation of ground surface.
- (2) Fertilizing.

- (3) Spot sodding or sprigging.
- (4) Compacting, where applicable.
- (5) Mulching, where applicable

3.2 PREPARATION OF GROUND SURFACE

3.2.1 General

Equipment, in good condition, shall be provided for the proper preparation of the ground and for handling and placing all materials. Equipment shall be approved by the Contracting Officer before work is stated.

3.2.2 Clearing

Prior to grading and finish dressing, vegetation that may interfere with turfing operations shall be removed and shall be disposed of as specified in SECTION 02114 CLEARING, paragraph 3.2. The surface shall be cleared of roots, cable, wire, and other materials that might hinder the work or subsequent maintenance.

3.2.3 Dressing

Surfaces to be turfed shall be dressed to the extent necessary to provide drainage and the specified slopes, and as necessary to remove high points and fill depressions sufficiently to provide reasonably smooth surfaces. Necessary repairs to previously graded areas shall be made with suitable material placed and compacted as directed by the Contracting Officer. Suitable material for repairs may be obtained from the required excavation or from an off site borrow area as specified in SECTION 02225 EARTHWORK, paragraph 3.3.2.

3.3 SPECIAL EQUIPMENT

Hydraulic equipment used for the application of slurry of prepared wood cellulose fiber mulch shall have a built-in agitation system with an operating capacity sufficient to agitate, suspend, and homogeneously mix a slurry. The slurry distribution lines shall be large enough to prevent stoppage. The discharge line shall be equipped with hydraulic spray nozzles that will provide even distribution of the slurry on the various slopes to be mulched. The slurry tank shall have a minimum capacity of 1,000 gallons and shall be mounted on a traveling unit, which may be either self-propelled or drawn by a separate unit, that will place the slurry tank and spray nozzles near the areas to be mulched so as to provide uniform distribution without waste. The Contracting Officer may authorize equipment with a smaller tank capacity provided that the equipment has the necessary agitation system and sufficient pump capacity to spray the slurry in a uniform coat over the surface of the area to be mulched.

3.4 APPLICATION OF FERTILIZER AND/OR LIMESTONE (IF USED)

Fertilizer and limestone (if used) shall be distributed uniformly over the areas to be sprigged or spot sodded at the rate determined as specified in 2.2.2 above and shall be incorporated into the soil by light disking, harrowing, or other acceptable methods immediately following the application.

3.5 SPOT SODDING

If the Contractor elects to spot sod, the areas to be turfed shall be spot sodded with Bermuda grass in any manner selected by the Contractor to meet the coverage requirements set forth in paragraph 3.9.1 below.

3.6 SPRIGGING

If the Contractor elects to sprig, the areas to be turfed shall be sprigged with Bermuda grass in any manner selected by the Contractor to meet the coverage requirements set forth in 3.9.1 below.

3.7 APPLYING AND ANCHORING MULCH

Mulch shall be spread uniformly in a continuous blanket, using 2 tons per acre of straw mulch or 1,200 pounds per acre of wood cellulose fiber mulch. Straw mulch shall be spread either by hand or by a manure spreader or by a modified grain combine with straw-spreader attachment or by a blower-type mulch spreader. Mulching shall be started at the windward side of relatively flat areas, or at the upper part of a steep slope, and continued uniformly until the area is covered. The mulch shall not be bunched. Immediately following spreading, straw mulch shall be anchored to the soil by a V-type-wheel land packer, a scalloped-disk or other suitable equipment operated parallel to the embankment centerline. The number of passes needed, not to exceed three, will be determined by the Contracting Officer. Wood cellulose fiber mulch shall be applied with equipment conforming to the requirements of 3.3 above.

3.8 HYDRAULIC SLURRY METHOD

The hydraulic slurry method of fertilizing and mulching, or any combination thereof, may be used by the Contractor, except that in no event shall the mulch be applied prior to fertilizing. Equipment to be used for application of materials by the hydraulic slurry method shall conform to the requirements specified in 3.3 above.

3.9 ESTABLISHMENT

3.9.1 General

Turfing will be considered to be completed when the areas to be turfed show that growth of the specified grass has reached a point of maturity such that it has produced stems or runners which overlap adjacent similar growth over 85 percent of the entire area as determined by random sampling on a square-yard basis with no bare spot exceeding 36 square inches.

3.9.2 Maintenance

The Contractor shall be responsible for the turfed areas while grass is becoming established to the point of acceptance by the Contracting Officer. During establishment and prior to acceptance of the sodded areas, the Contractor shall repair rainwash damage, if any, to the completed embankment at the contract. Turfed areas shall be kept mowed to a height between 4 and 12 inches above the turfed no additional cost to the Government. The turfed areas shall be maintained by mowing for the life of earth surface. Should the Contractor fail to mow the turfed areas to the limits as specified above, the Government will assume the responsibility for the mowing and deduct the cost thereof from any payments due the Contractor.

3.10 INSPECTION AND ACCEPTANCE

3.10.1 General

Acceptance of the turfed areas will be determined by visual inspection. Existence of rainwash damage or dead and dying turf will not be acceptable. Twenty-five percent (25%) of this item cost will retained pending final acceptance of turfing.

3.10.2 Areas Requiring Returfing

Areas being inspected for completion that do not meet the requirements for completion as specified hereinabove shall be returfed at no additional cost to the Government.

-- End of Section --

DIVISION 3 - CONCRETE

SECTION 03307

CONCRETE FOR MINOR STRUCTURES

TABLE OF CONTENTS

PART 1	GENERAL
1.1	REFERENCES
1.2	GENERAL
1.3	STORAGE
1.4	QUALITY CONTROL
1.5	SUBMITTALS
1.5.1	Shop Drawings
1.5.2	Certificates of Compliance
1.5.3	Submitting Mix Proportions
PART 2	PRODUCTS
2.1	MATERIALS
2.1.1	Anchorage Items
2.1.2	Concrete Materials
2.1.3	Curing Materials
2.1.4	Form Coating
2.1.5	Form Materials
2.1.6	Form Ties
2.1.7	Reinforcement
2.2	CONCRETE QUALITY
2.2.1	Compressive Strength
2.2.2	Entrained-Air Content
2.2.3	Slump
PART 3	EXECUTION
3.1	FORMWORK
3.1.1	Material
3.1.2	Construction
3.1.3	Coating
3.1.4	Removal

- 3.2 STEEL REINFORCEMENT
- 3.3 INSTALLATION OF ANCHORAGE ITEMS
- 3.4 JOINTS
 - 3.4.1 Construction Joints
- 3.5 PLACING
- 3.6 CONSOLIDATION OF CONCRETE
- 3.7 FINISH OF CONCRETE
- 3.8 CURING
 - 3.8.1 Pigmented Type Curing Compound
 - 3.8.2 Curing Compound

SECTION 03307

CONCRETE FOR MINOR STRUCTURES

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI) STANDARD

318/318R Building Code Requirements for Reinforced Concrete.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 615/A615 M Deformed and Plain Billet-Steel Bars for Concrete Reinforcement

C 94 Ready-Mixed Concrete.

1.2 GENERAL

The work shall be in conformance with ACI 318, part entitled "Construction Requirements," except as specified herein. Concrete shall conform to ASTM C 94.

1.3 STORAGE

Materials shall be stored so as not to deteriorate or become contaminated.

1.4 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements and maintain records of his quality control for all construction operations including but not limited to the following:

(1) Materials

Review of submittals prior to submission, materials conform to specifications.

(2) Construction

Preparation of surfaces, placement of steel reinforcement, placement of concrete, mixing, consolidation, finishing, tolerances, treatment of joints, air content, slump, water-cement ratio.

A copy of these records and tests, as well as corrective action taken, shall be furnished the Government.

1.5 SUBMITTALS

1.5.1 Shop Drawings

Shop drawings shall be submitted for approval in accordance with SPECIAL CONTRACT REQUIREMENT Clause 1.14. Shop drawings shall show details of reinforcement, sizes and grades of steel, and bending and splicing details; welded steel anchor ring details; and form details.

1.5.2 Certificates of Compliance

Certificates of compliance attesting that all materials used in the concreting work meet the requirements specified shall be furnished in accordance with the Special Clauses. Certified copies of laboratory test reports for applicable materials shall be made by an approved commercial laboratory.

1.5.3 Submitting Mix Proportions

Prior to commencing operations, the Contractor shall furnish a statement giving the proportions of all ingredients that will be used in the manufacture of each strength of concrete proposed for use and in accordance with paragraph 1.5.2 above. Aggregate weights shall be based on the saturated surface dry condition. The statement shall be accompanied by test results from an independent commercial testing laboratory, attesting that the proportions selected will produce concrete of the qualities indicated. No substitutions shall be made in the materials used in the work without additional tests to show the quality of the concrete is satisfactory.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Anchorage Items

Anchorage items for anchoring work of other trades to concrete shall be of standard manufacture and of types to engage with anchors provided and installed under other sections.

2.1.2 Concrete Materials

Concrete materials shall conform to ASTM C 94, with Portland cement conforming to either Type I or II cement. Maximum coarse aggregate size for slab, 1-1/4 inches, for all other concrete, 3/4 inch. Only one brand of any one type of cement shall be used for exposed concrete surfaces of any individual structure.

2.1.3 Curing Materials

Curing materials shall be impervious sheet or membrane-forming curing compound. The impervious sheet shall be white opaque polyethylene 4 mil thick, waterproof kraft paper, or polyethylene-coated burlap. The membrane-forming curing compound shall be of commercial formulation, sprayable, non-toxic, and will form a film highly resistant to moisture loss from concrete while curing and will dry within 4 hours. The compound shall be clear with fugitive dye, resin-base or chlorinated-rubber-base-type.

2.1.4 Form Coating

Form coating shall be nonstaining form oil or form release agent that will not deleteriously affect concrete surfaces nor impair subsequent applications.

2.1.5 Form Materials

Form materials shall be plywood or hardboard especially made for concrete form use or other materials that will produce the specified finishes without adversely affecting the concrete surfaces.

2.1.6 Form Ties

Form ties shall be metal, factory-fabricated removable or snap-off, that will leave holes not less than 1/4 inch nor more than 1 inch in diameter and not more than 1 inch deep. That portion of the tie remaining permanently in the concrete shall not project beyond the surface of the concrete and shall be recessed at least 1 inch from any concrete surface that will be exposed, painted, damp proofed, or will receive direct applications of plaster.

2.1.7 Reinforcement

Reinforcement bars shall conform to ASTM A 615, Grade 60 bars.

2.2 CONCRETE QUALITY

Proportioning of concrete mixes to meet the requirements specified below shall be the Contractor's responsibility.

2.2.1 Compressive Strength

Concrete shall be proportioned and mixed for a minimum compressive strength in 28 days of 3,000 psi. The compressive strength shall be reached in 7 days when high-early-strength cement is used.

2.2.2 Entrained-Air Content

Entrained-air content of exterior concrete shall be maintained at 4.5 percent, \pm 1.5 percent by volume of concrete.

2.2.3 Slump

Slump shall be 2 inches minimum to 4 inches maximum.

PART 3 EXECUTION

3.1 FORMWORK

3.1.1 Material

Forms shall be of wood, steel, or other material approved by the Contracting Officer. The type, size, shape, quality, and strength of all materials of which the forms are made shall be subject to approval. The Contractor is responsible for the design, construction and shoring of all formwork. The Contractor shall submit to the Contracting Officer for approval, shop drawings detailing the materials used and the design of the forms.

3.1.2 Construction

Forms shall be true to line and grade, mortar-tight and sufficiently rigid to prevent objectionable deformation under load. Forms for all exposed concrete shall be material that is not reactive with concrete. Forms shall be substantial and sufficiently tight to prevent leakage of mortar. All exposed joints and edges shall be chamfered in accordance with applicable ACI standards unless otherwise directed by the Contracting Officer. Internal ties shall be so arranged that when the forms are removed all metal will be not less than 2 inches from concrete surfaces permanently exposed to view or exposed to water on the finished structure.

3.1.3 Coating

Forms for exposed surfaces shall be coated with a nonstaining form oil, which shall be applied shortly before concrete is placed. Forms for unexposed surfaces may be thoroughly wetted in lieu of oiling, immediately before placing of concrete, except that when the ambient temperature is below 40 degrees F the nonstaining form oil must be used.

3.1.4 Removal

All form removals shall be accomplished in such a manner as to prevent injury to the concrete. Forms shall not be removed before the expiration of 24 hours after concrete placement except where otherwise specifically authorized by the Contracting Officer. When conditions on the work are such as to justify the requirements, forms will be required to remain in place for longer periods. Backfilling against walls is not permitted until 28 day strength of concrete has been reached and walls are braced to resist loads of retained earth while backfilling is underway.

3.2 STEEL REINFORCEMENT

All reinforcing steel shall conform to ASTM A 615 Grade 60. The Contractor shall submit to the Contracting Officer for approval, shop drawings detailing the material used, cutting and bending of steel, spacing of reinforcement, splicing of reinforcements, and supports that may be used in placing the steel. These drawings shall be submitted to and approved by the Contracting Officer before construction of the concrete work commences.

3.3 INSTALLATION OF ANCHORAGE ITEMS

Anchorage items shall be of number, size, and location to insure sufficient anchorage for purpose intended.

3.4 JOINTS

3.4.1 Construction Joints

Construction joints shall be located as indicated or approved. Where concrete work is interrupted by weather, end of work shift, or other similar type of delay, location and type of construction joint shall be subject to approval of the Contracting Officer.

3.5 PLACING

The concrete footings for the inlet and outlet (head wall) structures shall be placed upon clean undisturbed surfaces free from frost, ice, and water.

3.6 CONSOLIDATION OF CONCRETE

Consolidation of concrete shall be with internal concrete vibrators supplemented by handspading, rodding, and tamping. Vibrating equipment shall be adequate to thoroughly consolidate the concrete.

3.7 FINISH OF CONCRETE

Fins and loose material shall be removed. Unsound concrete, voids over 1/2-inch in diameter, and tie-rod and bolt holes shall be cut back to solid concrete, reamed, brush-coated with cement grout, and filled solid with a stiff portland-cement-sand mortar mix. Grout shall be cork- or wood-floated to fill voids, excess scraped off with a trowel, and visible grout film removed by rubbing with burlap. Grout shall be kept damp until set.

3.8 CURING

3.8.1 Pigmented Type Curing Compound

A pigmented type curing compound conforming to CRD-C 300 may be used on surfaces which will not be exposed to view when the project is completed. A non-pigmented type curing compound, containing a fugitive dye, conforming to CRD-C 300 with the reflective requirements waived may be used on surfaces which will be exposed to view when the project is completed. In hot weather, concrete cured with the non-pigmented type shall be shaded from the direct rays of the sun for the first 3 days of the curing period.

3.8.2 Curing Compound

The curing compound shall be applied to formed surfaces immediately after the forms are removed and all necessary repairs have been performed. Immediately after the removal of forms, all surfaces shall be kept continuously wet until repairs have been performed and curing compound applied. The curing compound shall be applied as recommended by the Contracting Officer. Concrete surfaces which have been subjected to rainfall within 3 hours after curing compound has been applied shall be resprayed.

-- End of Section --

Invitation No. DACW66-03-B-0011

DIVISION 4 –MASONRY

THRU

DIVISION 14-CONVEYING SYSTEMS

(NOT USED)

DIVISION 15-MECHANICAL

SECTION 15175

DISCHARGE PIPE AND APPURTENANCES

TABLE OF CONTENTS

PART 1	GENERAL
1.1	SCOPE
1.2	QUALITY CONTROL
1.3	APPLICABLE PUBLICATIONS
1.4	SUBMITTALS
PART 2	PRODUCTS
2.1	MATERIALS
2.1.1	Pipe
2.1.2	Fittings
2.1.3	Flexible Couplings
2.1.4	Vent Pipes
2.2	COATINGS
PART 3	EXECUTION
3.1	PREPARATION FOR SHIPMENT AND STORAGE
3.2	STORAGE
3.3	FABRICATION AND INSTALLATION

SECTION 15175

DISCHARGE PIPE AND APPURTENANCES

PART 1 GENERAL

1.1 SCOPE

The work provided for herein consists of furnishing all shop drawings, plant, labor, materials and equipment and manufacturing, factory testing, coating, delivering, storing and installing the water pump discharge pipes complete with all necessary accessories and appurtenances to include sump pumps and appurtenances, all as shown on the contract drawings and specified herein.

1.2 QUALITY CONTROL

The Contractor shall establish and maintain quality control for the work specified in this section to assure compliance with contract requirements and maintain records of his quality control for all construction operations, including but not limited to the following:

- (1) All shop fabrication.
- (2) Shop coating.
- (3) Use of specified material.
- (4) Shop tests.
- (5) Preparation for shipment and storage at the worksite.
- (6) Inspection at the worksite for damage to and defects in all material and equipment.
- (7) Storage at the worksite.
- (8) Field Coating.
- (9) Installation.
- (10) Maintenance after Installation.

A copy of these records and tests, as well as the records of corrective action taken, shall be furnished the Government.

1.3 APPLICABLE PUBLICATIONS

The following publications of the issue listed below, but referred to thereafter by basic designation only, forms a part of this specification to the extent indicated by the reference thereto:

AMERICAN WATER WORKS ASSOCIATION (AWWA)

C200	Steel Water Pipe 6 Inches and Larger
C203	Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape – Hot – Applied
C208	Dimensions for Steel Water Pipe Fittings
M11	Steel Pipe Design and Installation

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A 53	Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
------	---

FEDERAL SPECIFICATIONS (FS)

TT-P	Paint, Aluminum, Ready-Mixed
------	------------------------------

MILITARY SPECIFICATIONS (MS)

MIL-C-16173D	Corrosion Preventive Compound, Solvent Cutback, Cold-Application
--------------	--

STEEL STRUCTURES PAINTING COUNCIL

SSPC Paint 25	Red Iron Oxide, Zinc Oxide, Raw Linseed Oil and Alkyd Primer (Without Lead and Chromate Pigments)
---------------	--

1.4 SUBMITTALS

Complete shop drawings of the water pump discharge pipes, appurtenances and accessories shall be submitted to the Contracting Officer for approval in accordance with SECTION 00800, paragraph 1.16. Drawings of any items made specially or specifically for this project shall be true shop drawings, but catalog cuts will be sufficient for standard manufactured articles, and outline drawings of such equipment may be used in the assembly drawings. However, for those items for which true shop drawings are not required, sufficient descriptive data and/or other information, in addition to the catalog cuts, shall be submitted to demonstrate compliance with the specifications. The shop drawings shall show clearly all information required for connecting, coupling, coating, electrically bonding and installing the discharge pipes, appurtenances, and accessories, and shall specify the materials used.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Pipe

Pipe for the storm water pump discharge line shall be fabricated and tested in accordance with the applicable requirements of AWWA C200. Test pressure shall be not less than 30 pounds per square inch gage. The pipe shall have a nominal outside diameter of 16 inches and a minimum nominal wall thickness of 3/8 inch. The pipe shall have plain ends and thrust rod lugs to accommodate the flexible couplings.

2.1.2 Fittings

Changes in direction or elevation of the discharge pipe shall be made using either segments of factory-made long-radius steel welding elbows specially fabricated from the same material as the discharge pipe or metal elbows in accordance with table 2 of AWWA C208. The elbows shall conform to the requirements indicated on the contact drawings and shall have the same diameter, thickness, and coating as the discharge pipe.

2.1.3 Flexible Couplings

Flexible couplings shall be the gasketed, sleeve type, of proper diameter to fit the discharge pipe, and shall be furnished complete with gaskets and bolts and the associated thrust rods and nuts. The middle ring of the coupling shall be a true circular section free from irregularities, flat spots or surface defects. It shall be fabricated into a one-piece element, with all longitudinal joints flush butt welded. After welding, it shall be tested by being cold-expanded a minimum of one percent beyond the yield point to proof-test the weld to the strength of the parent metal. The weld shall then be subjected to an air test for porosity. The thickness of the middle ring shall be at least the nominal thickness of the discharge pipe. The middle ring shall not have a pipe stop. The followers shall be fabricated into one-piece elements from a contoured mill section by being flush butt welded and then cold-expanded as required for the middle ring. The followers shall be of sufficient strength to accommodate the number of bolts necessary to obtain adequate gasket pressure. The shape of the followers shall be of such design as to provide positive confinement of the gasket. Coupling bolts shall be the elliptic-neck, track-head type with rolled threads. All bolt holes in the followers shall be oval for greater strength. Gaskets shall be composed of either a natural or synthetic rubber compounded with other products to produce a material, which will not deteriorate from age, heat or exposure to air under normal storage conditions. The compound shall also possess the quality of resilience and the ability to resist cold flow so that the joint will remain sealed and tight indefinitely when subjected to shock, vibration, pulsation and temperature changes in the discharge pipe.

2.1.4 Vent Pipe

The steel vent pipe shall be constructed in accordance with the requirements as specified in ASTM A-53. The vent pipe shall be sized not less than the 1/4 dia. of the discharge pipe.

2.2 COATINGS

The storm water pump discharge pipes shall be coated inside and out in the manufacturer's plant and in accordance with the applicable provisions of AWWA C203. All coatings shall be touched up in the field as necessary. The coating of pipe to be placed underground shall be finished with a coat of water-resistant whitewash. Any of the underground coating which remains exposed after installation of the discharge pipe and completion of the embankment work shall be given an additional coat of water-resistant whitewash equivalent to that applied at the factory. Flexible couplings shall be cleaned, primed and coated with coal tar enamel in accordance with the applicable provisions of AWWA C203 for "Specials", and the use of coupling coating pans or "cocoon" as described in AWWA Manual M11 will be acceptable. Any portions of the pipe and fittings not shop coated in order to facilitate assembly shall be thoroughly cleaned and coated in the field and in accordance with AWWA C203. The exposed portion of the vent pipe shall be painted with one coat of red iron oxide paint conforming to the requirements of SSPC Paint 25, and then painted with two coats of aluminum paint conforming to the requirements of TT-P-38. The underground portion of the vent shall be painted in accordance with the applicable provisions of AWWA C203. The Contractor shall furnish, under separate cover, an affidavit that the materials and workmanship comply with the applicable requirements of AWWA C203.

PART 3 EXECUTION

3.1 PREPARATION FOR SHIPMENT AND STORAGE

Protected pipe shall be handled at all times with equipment such as wide slings and wide padded skids designed to prevent damage to the coating. Bare wire rope, chains, hooks, metal bars and narrow skids shall not be permitted to come in contact with the coating. When shipped by rail, all pipe and couplings shall be carefully loaded on properly padded saddles or bolsters. All bearing surfaces and dunnage shall be properly padded with approved materials. Pipe sections and couplings shall be separated so that they do not bear against each other, and the whole load shall be securely fastened together to prevent movement in transit. The pipe shall be loaded and tied into a unit load, in strict accordance with the current loading rules of the American Railway Association whenever they are applicable. When shipped by truck, the pipe and couplings shall be supported in wide cradles of suitably padded timbers hollowed out on the supporting surface to fit the curvature of the pipe, and all wire rope, chains and other fastening equipment shall be carefully padded. Prior to being loaded on the carrier, any portions of the storm water pump discharge pipe not coated because of future field welding or other installation requirements shall be protected with a coat of rust preventative meeting the applicable requirements of MS MIL-C-16173, Grade 2. This coating shall be removed prior to any field welding or coating.

3.2 STORAGE

Upon delivery at the worksite, the discharge pipe sections, accessories, appurtenances, fittings and the metal parts of the flexible couplings may be stored outdoors provided they are stored on wood blocking not less than 8 inches above a base of washed gravel or crushed stone not less than 2 inches thick. The gaskets shall be stored indoors.

3.3 FABRICATION AND INSTALLATION

Except where flexible couplings are shown on the contract drawings, the storm water pump discharge pipe shall be shop assembled with welded joints and welded fittings. The pipe shall be in lengths not to exceed 45 feet. The pipe shall be handled and transported in such manner that neither the pipe nor the coatings will be damaged. The bottom of the trench shall be so shaped and compacted that each section of pipe will rest on a foundation of uniform density. Excavation and backfill shall be as specified in SECTION 02704-STEEL PIPE INSTALLATION. Space shall be provided to accommodate the larger diameter of the flexible couplings. Where the discharge pipe is embedded in a wall, anchor rings shall be provided. The size, thickness and attachment shall be as shown on the contract drawings. Flexible couplings shall be installed in accordance with the manufacturer's instructions, including recommended bolt torques, and in such manner as to secure permanently tight joints under all reasonable conditions of expansion, contraction, shifting and settlement. Thrust rods shall be installed at the couplings.

-- End of Section --

Invitation No. DACW66-03-B-0011

DIVISION 16 –ELECTRICAL

(NOT USED)